

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated November 13, 2009

**LUZERNE COUNTY – SR 2004(370) #8637**

**PROPOSAL:\$21.84 PLANS:\$31.02 12X18:\$549.90 X-SEC:\$6.82 12X18:\$8.37 24X36:\$120.90** For the rehabilitation and improvement of a certain section of STATE HIGHWAY in LUZERNE COUNTY, CITY OF WILKES BARRE AND PLAINS TOWNSHIP , Commonwealth of Pennsylvania , STATE ROUTE 2004 , SECTION 370,371 AND 372 The project being situated as follows – From a point approximately 42,240 linear feet (8.00 miles) north of Nanticoke Borough at Segment 0070 , Offset 1709 (Station 10+00) to a point approximately 42,240 linear feet (8.00 miles) south of City of Pittston at Segment 0080 , Offset 0887 (Station 30+00) . For the construction of a pre stressed box beam bridge and removal of a steel girder bridge, rehabilitation of a Masonry Arch structure consisting of reconstructing stone barriers, steel fence, roadway pavement And sidewalk; construct reinforced concrete toe wall, provide scour protection and rehabilitate masonry stone surfaces consisting of reset stones, place new stones, clean and Repair and re point joints and repair spalling and delaminated stones in arch barrel and abutment walls. , mine opening closure and rehabilitation, MSE retaining wall , temporary bridge and roadway , bituminous wearing course overlay 1 ½ inches depth, pavement widening, pavement markings , drainage , sidewalks , concrete curbing , and traffic control all contained within an overall project length of 1900.00 linear feet (0.379 mile ) as indicated on the approved drawings included in the bid package. DBE 3%, Anticipated Notice to Proceed 1-28-10, Required Completion 11-24-11.

---

**CHESTER COUNTY – SR 3026(BPB) #62297**

**PROPOSAL:\$11.40 PLANS:\$20.68 12X18:\$25.38 24X36:\$366.60** The description and location of the project is as follows: This Project involves improvements in service quality for bicycle facilities which includes shoulder delineation, widening and reconstruction, installation of bike lanes, replacement of drainage grates on existing roadways and other miscellaneous construction, as indicated on the approved drawings included in the bid package for various locations in Chester, Delaware, Montgomery and Philadelphia Counties in Pennsylvania. DBE 6%, Anticipated Notice to Proceed 2-1-10, Required Completion 6-1-10.

---

**PHILADELPHIA COUNTY – SR 0(GSM) #82540**

**PROPOSAL:\$18.48** The description and location of the project is as follows: the repair and replacement of Type A, Type B and Type E signs as well as Overhead signs and other miscellaneous construction, all as indicated on the drawings approved July 10, 2009 for Various STATE ROUTES in BUCKS, CHESTER, DELAWARE, MONTGOMERY, AND PHILADELPHIA COUNTIES. MBE 4%, WBE 2%, Anticipated Notice to Proceed 1-18-10, Required Completion 1-18-13.

---

**LUZERNE COUNTY – SR 309(331) #57708**

**PROPOSAL:\$12.48 PLANS:\$16.06 12X18:\$19.71 24X36:\$284.80 X-SEC:\$6.38 12X18:\$7.83 24X36:\$113.10** For the rehabilitation and improvement of a certain section of STATE HIGHWAY in LUZERNE COUNTY , BUTLER TOWNSHIP , Commonwealth of Pennsylvania, STATE ROUTE 0309 , SECTION 331. The project being situated as follows – From a point approximately 21,120 linear feet (4.00 miles) NORTH of Minesville Borough at Segment 0260 , Offset 1397 and Segment 0261 Offset 1359 (Station 502+45) to a point approximately 53,856 linear feet (10.2 miles) south of Mountaintop Borough at Segment 0270 , Offset 1470 and Segment 0271 Offset 1464 (Station 532+00) . For the installation of traffic signals, bituminous wearing course overlay 1 ½ inches depth, pavement widening, pavement markings , drainage , concrete curbing and traffic control all contained within an overall project length of 3000.00 linear feet (0.57 mile ) as indicated on the approved drawings included in the bid package. DBE 0%, Anticipated Notice to Proceed 1-18-10, Required Completion 12-10-10.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated November 10, 2009

**NORTHAMPTON COUNTY – SR 248(ADA) #86001**

**PROPOSAL:\$8.76** This is an Economic Recovery Project. The description and location of the project is as follows: Curb Ramps Design and Curb Ramp installation and/or replacement on Various SR's in Northampton County as listed on the attachment entitled "Location Roster for Northampton County. DBE 3%,Anticipated Notice to Proceed 12-21-09, Required Completion 12-31-10.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated November 9, 2009

**ALLEGHENY COUNTY – SR 910(A17) #28121**

**PROPOSAL:\$15.60 PLANS:\$10.56 12X18:\$12.96 24X36:\$187.20 X-SEC:\$1.32 12X18:\$1.62 24X36:\$23.40** The description and location of the project is as follows: For the concrete culvert bridge replacement, roadway approachment, guiderail, pavement marking, and other miscellaneous construction, all within a length of 175 linear feet (0.033 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 0910, SECTION A17 (Gibsonia Road), in ALLEGHENY COUNTY, RICHLAND TOWNSHIP, Commonwealth of Pennsylvania. This project being situated as follows: From a point approximately 176 feet west of Grubbs Road (T-584) at Segment 0160 Offset 0704 (Station 105+00) to a point approximately 26 feet west of Gibson Road (T-794) at Segment 0160 Offset 1054 (Station 108+50). MBE 2%, WBE 2%, Anticipated Notice to Proceed 2-1-10, Required Completion 10-15-10.

---

**ALLEGHENY COUNTY – SR 2087(A01) #27329**

**PROPOSAL:\$17.16 PLANS:\$27.28 12X18:\$33.48 24X36:\$483.60 X-SEC:\$3.08 12X18:\$3.78 24X36:\$54.60** The description and location of the project is as follows: for the removal of an existing steel bridge and replacement with a single span composite steel multi-girder bridge; approach work including bituminous pavement, guide rail, minor drainage, pavement markings and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 2087, SECTION A01, in ALLEGHENY COUNTY, NORTH VERSAILLES TOWNSHIP from approximately 285 feet East of Union Avenue (Local Street) at Station 9+75 to approximately 715 feet West of Union Avenue at Station 19+75. DBE 5%, Anticipated Notice to Proceed 1-19-10, Required Completion 11-24-10.

---

**BERKS COUNTY – SR 422(14M) #10977**

**PROPOSAL:\$7.68 PLANS:\$8.14 12X18:\$9.99 24X36:\$144.30** The description and location of the project is as follows: The limits of work on STATE ROUTE 0222 SECTION 24M are North Bound from Segment 0132 Offset 2835 to Segment 0192 Offset 0050; SOUTH BOUND from Segment 0133 Offset 2893 to Segment 0193 Offset 0050 in the Borough of Wyomissing in BERKS COUNTY for an approximate length of 10,927 feet (2.07 miles). The major items of roadway work are to include: new concrete pavement joints, concrete spall repairs, concrete patching, diamond grinding, clean and reseal concrete pavement joints, pavement relief joint repair, milling, bituminous tack coat shoulders, pavement markings, the replacement and removal of guide rail and other miscellaneous construction, all as indicated on the approved drawings. DBE 5%, Anticipated Notice to Proceed 1-28-10, Required Completion 9-8-10.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated November 6, 2009

**ALLEGHENY COUNTY - #87228**

**PROPOSAL:\$12.60** The description and location of the project is as follows: Bridge demand maintenance of various structure types including but not limited to structural steel repairs, concrete deck repairs, concrete substructure repairs, bearing repairs, along with other miscellaneous construction as indicated on the attached details included in the bid package for VARIOUS STATE ROUTES, in VARIOUS MUNICIPALITIES, in ALLEGHENY, BEAVER, AND LAWRENCE COUNTIES. MBE 2%, WBE 2%, Anticipated Notice to Proceed 1-19-10, Required Completion 1-31-11.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated November 5, 2009

**BLAIR COUNTY – SR 0(89S) #74530**

**PROPOSAL:\$12.24 PLANS:\$5.72 12X18:\$7.02 24X36:\$101.40 X-SEC:\$66 12X18:\$81 24X36:\$11.70** The description and location of the project is as follows: This project is for the replacement of a single span concrete deck bridge over Brush Run and replaced with a 10'-0" X 6'-0" Precast Reinforced Concrete Box Culvert, drainage upgrades, minor approach work and other miscellaneous construction all as indicated on the approved drawings included in the bid package for 8th Street Bridge, in BLAIR COUNTY, City of Altoona at the following location: STATION 1+30.00 TO STATION 3+40.00. DBE 0%, Anticipated Notice to Proceed 2-1-10, Required Completion 8-12-10.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated November 4, 2009

**BEDFORD COUNTY – SR 7401(WAT) #48007**

**PROPOSAL:\$27.96 PLANS:\$16.06 12X18:\$19.71 24X36:\$284.70 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30** The description and location of the project is as follows: This project is for the replacement of the structure carrying Watson Street over Shober's Run in Bedford County. The existing structure consists of a single-lane, three span, non-composite, prestressed concrete adjacent plank structure with concrete abutments and is to be replaced with a One-Span Composite Prestressed Concrete Spread Box Beam Bridge with minimal roadway approach work and other miscellaneous construction, all as indicated on the approved drawings included in the bid package for STATE ROUTE 7401, SECTION WAT, in BEDFORD COUNTY, BEDFORD BOROUGH at the following location: STATION 8+00.00 TO STATION 15+50.00. DBE 1%, Anticipated Notice to Proceed 1-18-10, Required Completion 10-5-10.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated November 2, 2009

**DELAWARE COUNTY – SR 95(LW9) #8008**

**PROPOSAL:\$30.24 PLANS:\$5.50 12X18:\$6.75 24X36:\$97.50 X-SEC:\$11.22 12X18:\$13.77 24X36:\$198.90**  
**EXSTRUCT:\$50.60 12X18:\$62.10 24X36:\$897.00** The description and location of the project is as follows: This project is for Design/Build Sound Barrier, drainage, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0095, SECTION LW9, in DELAWARE COUNTY, RIDLEY TOWNSHIP from approximately Ketcham Avenue at segment 0071 offset 1778 to approximately Darby Creek at segment 0081 offset 1347. MBE 3%, WBE 2%, Anticipated Notice to Proceed 1-18-10, Required Completion 6-27-11.

---

**BUTLER COUNTY – SR 4007(258) #24707**

**PROPOSAL:\$ 12.36 PLANS:\$15.62 12X18:\$19.17 24X36:\$276.90 X-SEC:\$88 12X18:\$1.08 24X36:\$15.60**

**EXSTRUCT:\$3.30 12X18:\$4.05 24X36:\$58.50** The description and location of the project is as follows: For the deck replacement and rehabilitation of two structures; 1.) three span prestressed concrete box beam structure over SR 422 and 2.) three span prestressed concrete I-beam structure over Muddy Creek and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 4007, SECTION 258 and 255, in Butler COUNTY Muddy Creek and Worth TOWNSHIPS from approximately 1.) 2.9 miles north of Portesville at segment 0062 offset 0000 proceeding northward approximately 152 feet to segment 0062 offset 152; 2.) 2.9 miles north of Portesville at segment 0072 offset 0000 proceeding northward approximately 249 feet to segment 0072 offset 249. MBE 2%, WBE 2%, Anticipated Notice to Proceed 1-19-10, Required Completion 9-3-10.

---

**BERKS COUNTY – SR 73(05B) #83963**

**PROPOSAL:\$43.20 PLANS:\$7.26 12X18:\$8.91 24X36:\$128.70 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30**

The description and location of the project is as follows: The existing structure will be fully replaced with a single span structure which will carry two lanes of traffic across Oysterville Creek and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0073, SECTION 05B, in Berks COUNTY, Oley TOWNSHIP from approximately segment 0280 offset 0790 to approximately segment 0280 offset 1265. MBE 2%, WBE 2%, Anticipated Notice to Proceed 1-14-10, Required Completion 5-24-11.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated October 30, 2009

**DAUPHIN COUNTY – SR 147(011) #81258**

**PROPOSAL:\$16.80 PLANS:\$11.88 12X18:\$14.58 24X36:\$210.60 EXTSTRUCT:\$1.54 12X18:\$1.89 24X36:\$27.30**

This project consists of superstructure replacement at the structure over the Wiconisco Creek, substructure repairs/modifications, minor approach roadway work, and other miscellaneous items, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 0147, SECTION 011, in DAUPHIN COUNTY, MILLERSBURG BOROUGH and UPPER PAXTON TOWNSHIP, from Segment 0310 Offset 0389 to Segment 0320 Offset 0141, for an overall project length of 850.00 linear feet (0.161 mile). MBE 2%, WBE 3%, Anticipated Notice to Proceed 1-19-10, Required Completion 11-6-10.

---

**INDIANA COUNTY – SR 217(451) #25527**

**PROPOSAL:\$14.28 PLANS:\$9.90 12X18:\$12.15 24X36:\$175.50 EXSTRUCT:\$1.54 12X18:\$1.89 24X36:\$27.30**

The description and location of the project is as follows: For the rehabilitation of a four span continuous riveted steel builtup girder bridge and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 217, SECTION 451, in Indiana COUNTY Blacklick and Burrel TOWNSHIPS from approximately 1.5 miles northeast of the SR217/SR 3009 intersection at segment 0100 offset 0995 to approximately 1.7 miles northeast of the SR 217/SR 3009 intersection at segment 0100 offset 2145. MBE 2%, WBE 2%, Anticipated Notice to Proceed 1-19-10, Required Completion 5-31-11.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated October 26, 2009

**CLEARFIELD COUNTY – SR 3001(A01) #3561**

**PROPOSAL:\$82.44 PLANS:\$3.74 12X18:\$4.59 24X36:\$66.30 X-SEC:\$2.20 12X18:\$2.70 24X36:\$39.00**

**EXSTRUCT:\$3.08 12X18:\$3.78 24X36:\$54.60** The description and location of the project is as follows: For the Design and Construction of a certain section of STATE HIGHWAY in CLEARFIELD COUNTY, MAHAFFEY BOROUGH, BELL TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 3001, SECTION A01 - This project being situated as follows: On SR 3001 from Segment 0230 Offset 1218 to Segment 0240 Offset 0487. Construction also includes the paving of the detour routes: SR 3001 from Segment 0180 Offset 0000 to Segment 0230 Offset 1434; SR 3016 from Segment 0100 Offset 0000 to Segment 0120 Offset 3395; SR 3023 from Segment 0010 Offset 0000 to Segment 0020 Offset 2730. Total construction length is 31334 feet (5.957 miles) For the Design and Construction of a replacement bridge for the existing Single Span Warren Truss Bridge (span of 149' - 11"), work includes design and construction of temporary road, design and paving of the detour route, design and paving of roadway, design and construction of a removable bridge, and miscellaneous construction as indicated on the approved construction drawings. DBE 1%, Anticipated Notice to Proceed 1-18-10, Required Completion 11-3-10.

---

**VENANGO COUNTY – SR 8(A03) #2276**

**PROPOSAL:\$17.40 PLANS:\$49.50 12X18:\$60.75 24X36:\$877.50 X-SEC:\$39.16 12X18:\$48.06 24X36:\$694.20**

For the construction of a certain section of STATE HIGHWAY in VENANGO COUNTY; CHERRYTREE TOWNSHIP; Commonwealth of Pennsylvania; STATE ROUTE 0008, SECTION A03. This project being situated as follows: From approximately 519 feet north of the intersection with PA 417 (SR 0417) at Segment 0610 Offset 0858 (Station 363+50.00) to approximately 3532 feet south of the intersection with Buxton Road (S.R. 4022) at Segment 0650 Offset 2072 (Station 482+50.00). For the realignment and construction of a two lane roadway with Superpave Asphalt Mixture Designs; for the removal of an existing bridge; for the construction of a single span composite pre-stressed concrete spread box beam bridge having an overall length of 50 feet; and also for signing, pavement markings, drainage, and guiderail all within a project length of 11,772.20 feet (2.230 miles) as indicated on the approved drawings. DBE 5%, Anticipated Notice to Proceed 12-28-09, Required Completion 9-24-10.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated October 19, 2009

**LEHIGH COUNTY – SR 2002(KBC) #75072**

**PROPOSAL:\$8.28 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30**

The description and location of the project is as follows: Construction of two access driveways and removal of an access driveway, construction of an auxiliary deceleration lane, drainage pipe, manhole and inlet construction, curbing, milling, overlay, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 2002, SECTION KBC, in LEHIGH COUNTY, from approximately Public Road at segment 0130 offset 0946 in Salisbury Township to approximately Norway Place at segment 0140 offset 1449 in the Borough of Fountain Hill. DBE 1%, Anticipated Notice to Proceed 12-1-09, Required Completion 12-1-09, Required Completion 12-15-12.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 3, 2009**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated October 16, 2009

**INDIANA COUNTY – SR 3003(450) #25409**

**PROPOSAL:\$41.88 PLANS:\$19.14 1X18:\$23.49 124X36:\$339.30 X-SEC:\$2.42 12X18:\$2.97 24X36:\$42.90**

**EXSTRUCT:\$1.10 12X18:\$1.35 24X36:\$19.50** The description and location of the project is as follows: For the remediation of damaged geotechnical areas using gabions, dumped rock, and other restoration methods to repair washouts, slopes, drainage systems, bituminous or concrete roadway and shoulder failures, pavement marking, and other miscellaneous construction as indicated in the bid package for various STATE ROUTES in ALLEGHENY COUNTY, VARIOUS MUNICIPALITIES, Commonwealth of Pennsylvania. This project being situated as follows: SR 19, Segment 420; SR 48, Segments 220-240, Segments 330-360; SR 60, Segment 140; SR 130, Segment 142, Segments 202-242; SR 2022, Segment 20; SR 2031, Segments 20-30; SR 2037, Segments 10-20; SR 2053, Segments 10-20; SR 2058, Segments 60-70; SR 2065, Segments 10-80; SR 2098, Segment 10; SR 2112, Segment 20; SR 3077, Segment 200; SR 4011, Segment 90; SR 4033, Segments 20-50; SR 3075, Segment 10; SR 4032, Segment 40; SR 4035, Segments 10-30; SR 4080, Segments 20-50, and the Christy Park Stockpile in Allegheny County. DBE 5%, Anticipated Notice to Proceed 1-19-10, Required Completion 3-28-11.

---

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION