

**SSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 15, 2011**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**Updated November 29, 2011**

**ALLEGHENY COUNTY – SR 1028(A09) #63355**

**PROPOSAL:\$21.12 PLANS:\$8.80 12X18:\$10.80 24X36:\$156.00 X-SEC:\$1.76 12X18:\$2.16 24X36:\$31.20** The description and location of the project is as follows: replacement of an existing bridge superstructure with a pre-stressed concrete spread box beam superstructure, concrete substructure repair, scour protection, milling and resurfacing of approach roadway, guiderail and other miscellaneous construction construction, all within a length of 704.52 Linear feet (0.133 Miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 1028, SECTION A09, in ALLEGHENY COUNTY, FAWN TOWNSHIP from approximately the intersection with SR 1034 (Bull Creek Road) at Segment 180 Offset 83 to a point approximately 845 feet east of the same intersection at Segment 180 Offset 928. MBE 3%, WBE 3%, Anticipated Notice to Proceed 1-30-12, Required Completion 10-11-12.

---

**LUZERNE COUNTY – SR 7230(BRG) #8927**

**PROPOSAL:\$22.32 PLANS:\$14.30 12X18:\$17.55 24X36:\$253.50 X-SEC:\$1.10 12X18:\$1.35 24X36:\$19.50** For the rehabilitation and improvement of a certain section of County Bridge and LOCAL ROAD in LUZERNE COUNTY, SUGARLOAF TOWNSHIP, Commonwealth of Pennsylvania, Township Road-336, MILL HILL ROAD, SR 7230, SECTION BRG. From a point near the intersection with Pecora Road (STA. 100+00.00) to a point approximately 1 mile from West County Road (STA. 106+25.00) along Township Road – 336 (Mill Hill Road). The project includes the removal and replacement of an existing single span warren truss County Bridge No. 57305 with Two Span P/S Concrete Spread Box Beam Bridge. Other work includes full depth bituminous roadway approach construction, excavation, temporary excavation & support, drainage, traffic impact attenuator, guiderail, signal, concrete curb, signs, temporary traffic control, temporary detour signing, landscaping, erosion & sediment control measures and other miscellaneous construction all contained within an overall project length 545 linear feet (0.103 mile) as indicated on the approved drawings included in the bid package. DBE 4%, Anticipated Notice to Proceed 3-19-12, Required Completion 9-13-13.

---

**LEHIGH COUNTY – SR (OAS) #86852**

**PROPOSAL:\$17.04 PLANS:\$5.06 12X18:\$6.21 24X36:\$89.70** The description and location of the project is as follows: Streetscape improvements consisting of the installation of curb, sidewalk, crosswalks, ADA ramps, decorative lighting, benches, trash receptacles and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 9900, SECTION OAS, in Lehigh COUNTY, Allentown CITY along the south side of Turner Street between N. 10th Street and N. Fountain Street and within the 12 block area of the Old Allentown Historic District. DBE 5%, Anticipated Notice to Proceed 2-15-12, Required Completion 6-1-12.

---

**LAWRENCE COUNTY – SR 108(L12) #29375**

**PROPOSAL:\$71.64 PLANS:\$14.08 12X18:\$17.28 24X36:\$249.60 X-SEC:\$2.20 12X18:\$2.70 24X36:\$39.00** The description and location of the project is as follows: For the bridge replacement, roadway approach, drainage, guide rail, pavement marking, and other miscellaneous construction, all within a length of 635.0 linear feet (0.120 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 0108, SECTION L12 (Harlansburg Road), in LAWRENCE COUNTY, SCOTT TOWNSHIP, Commonwealth of Pennsylvania. This project being situated as follows: From a point approximately 470 feet west of Stoughton Road (T-485) at Segment 0410 Offset 2013 (Station 554+91) to a point approximately 265 feet east of Stoughton Road (T-485) at Segment 0420 Offset 0382 (Station 562+26). DBE 7%, Anticipated Notice to Proceed 1-30-12, Required Completion 4-30-13.

---

**BEAVER COUNTY – SR 1015(B01) #28925**

**PROPOSAL:\$18.60 PLANS:\$15.62 12X18:\$19.17 24X36:\$276.90 X-SEC:\$2.42 12X18:\$2.97 24X36:\$42.90** The description and location of the project is as follows: Project consists of bridge replacement, minor approach work, pavement markings, and guide rail and end treatment upgrades and delineation, and other miscellaneous construction, all as indicated on the drawings for State Route 1015, Section B01, in Beaver County, Marion and Franklin Townships from approximately 274 feet south of the intersection of Eckert Stop Road at segment 0070 offset 2407 to approximately 105 feet East of the intersection of SR 1015 & SR 1009 (Fombell Road) on SR 1009 (Old Furnace Road) at segment 0050 offset 2205 and also to approximately 125 feet West of the intersection of SR 1015 & SR 1009 (Old Furnace Road) on SR 1009 (Fombell Road) at segment 0060 offset 0125. MBE 3%, WBE 3%, Anticipated Notice to Proceed 1-30-12, Required Completion 10-4-12.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 15, 2011**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**Updated November 14, 2011**

**ERIE COUNTY – SR 832(B01) #990**

**PROPOSAL:\$16.44 PLANS:\$14.08 12X18:\$17.28 24X36:\$249.60 X-SEC:\$2.42 12X18:\$2.97 24X36:\$42.90** For the construction and rehabilitation of a certain section of STATE HIGHWAY in ERIE COUNTY, MILLCREEK TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 0832 SECTION B01. This project being situated as follows: From approximately 2.5 miles north of SR 0090 (I-90) at Sta 545+00.00 to approximately 1.3 miles south of the intersection with SR 4011 (Grubb Rd) at Sta 553+53.00. For construction of a single span composite steel multi-girder bridge with a total span of 210 feet; removal of existing structure; construction of new approach roadways using Superpave Asphalt Mixture Designs; guiderail, drainage, delineation, signing and landscaping all within a project length of 653.00 feet (0.124 mile) as indicated on the approved drawings. DBE 4%, Anticipated Notice to Proceed 1-30-12, Required Completion 10-16-12.

---

**ARMSTRONG COUNTY – SR 1028(150) #24124**

**PROPOSAL:\$22.32 PLANS:\$9.24 12X18:\$11.34 24X36:\$163.80 X-SEC:\$1.76 12X18:\$2.16 24X36:\$31.20** The description and location of the project is as follows: For the replacement of the existing structure over the South Fork of Pine Creek with a Simple-Span Steel Multi-Beam Bridge with minimal approach work and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 1028, SECTION 150, in Armstrong COUNTY Valley and Boggs Townships from approximately 100' north of SR 1028/SR 1035 intersection at segment 0110 offset 0100 to approximately 150' west of the SR 1028/SR 1035 intersection at segment 0120 offset 0150. MBE 3%, WBE 3%, Anticipated Notice to Proceed 2-21-12, Required Completion 9-5-12.

---

**BRADFORD COUNTY – SR 1026(003) #5293**

**PROPOSAL:\$40.56 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00 X-SEC:\$1.76 12X18:\$2.16 24X36:\$31.20** The description and location of the project are as follows: This work is for the design and construction of bridge structure over Gaylord Creek and removal of a temporary roadway all within a length of 492.00 linear feet (0.093 miles) all as indicated on the approved drawings included in the bid package for STATE ROUTE 1026, SECTION 003 from approximately 2.33 miles northeast of the intersection with State Route 1011 at Segment 0080, Offset 1976 to approximately 0.13 miles southwest of the intersection with State Route 4017 at Segment 0080, Offset 2693 in PIKE TOWNSHIP, BRADFORD COUNTY. MBE 1%, WBE 1%, Anticipated Notice to Proceed 1-30-12, Required Completion 11-16-12.

---

**FOREST COUNTY – SR 1003(B02) #1375**

**PROPOSAL:\$16.44 PLANS:\$9.02 12X18:\$11.07 24X36:\$159.90 X-SEC:\$1.32 12X18:\$1.62 24X36:\$23.40** For the construction or improvement of a certain section of STATE HIGHWAY in FOREST COUNTY, HOWE TOWNSHIP Commonwealth of Pennsylvania, STATE ROUTE 1003, SECTION B02. This project is situated as follows: From approximately 0.7 mile north of the intersection with T-371 (Job Corp Rd.) at Segment 0110 Offset 0587 (Station 262+40.00) then north to approximately 0.3 mile south from the intersection with SR 666 at Segment 0110 Offset 1137 (Station 267+90.00). For the structure replacement with a 1-Span Prestressed Concrete Spread Box Beam Bridge over Blue Jay Creek having an overall length of 85'-0"; Also for the concrete and bituminous roadway approaches, drainage, signs, and guiderail all within a project length of 350.00 feet (0.066 mile) as indicated on the approved drawings. DBE 6%, Anticipated Notice to Proceed 1-30-12, Required Completion 7-6-12.

---

**MONTGOMERY COUNTY – SR (CTP) #87091**

**PROPOSAL:\$37.20 PLANS:\$4.18 12X18:\$5.13 24X36:\$74.10** The description and location of the project is as follows: This project involves construction of trail head at Cynwyd Station to provide an improved access to the station and the proposed Cynwyd Trail. Improved pedestrian accommodations includes ADA access to the train platform, proposed trail, station, and parking lot. Streetscape enhancements includes sidewalks, reconstructed platform, relocated lighting, ornamental fencing, and plantings, all as indicated on the drawings approved for STATE ROUTE 0000, SECTION CTP, in MONTGOMERY COUNTY, LOWER MERION TOWNSHIP. DBE 5%, Anticipated Notice to Proceed 3-19-12, Required Completion 12-18-12.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 15, 2011**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**Updated November 9, 2011**

**BERKS COUNTY – SR 422(17M) #92820**

**PROPOSAL:\$21.36 PLANS:\$22.80** The description and location of the project is as follows: This project is a highway betterment project on SR 422, involving pavement and bridge preservation including; resurfacing, mill, patch and overlay, drainage, guiderail and shoulders preservation. Bridge Preservation is limited to deck repair only that include patch repair, type 2 & type 3 repairs, joints repair and bridge overlay, as indicated on approved drawings included in the bid package for STATE ROUTE 0422, SECTION 17M IN BERKS COUNTY in various (Boroughs of Wyomissing and West Reading; City of Reading; Cumru and Exeter Townships) Municipalities from approximately at segment 0352 offset 1420 NB to segment 0460 offset 1839 NB and segment 0353 offset 1567 SB to segment 0471 to offset 680 SB for total of approximately 11.1 lane miles. DBE 2%, Anticipated Notice to Proceed 3-12-12, Required Completion 11-14-12.

---

**CLEARFIELD COUNTY – SR 80(ITS) #3654**

**PROPOSAL:\$19.32 PLANS:\$30.58 12X18:\$37.53 24X36:\$542.10** The description and location of the project is as follows: For construction and relocation of Intelligent Transportation System (ITS) devices at certain sections of State Route 80 in VARIOUS TOWNSHIPS in CENTRE, CLEARFIELD, CLINTON, and JEFFERSON COUNTIES and State Route 99 in VARIOUS TOWNSHIPS in CENTRE COUNTY, Commonwealth of Pennsylvania. The construction length is approximately 15,397 feet (2.92 miles). Construction includes sixteen dynamic message signs (DMS) with speed detection at each site, four DMS retrofits to include speed detection capabilities, seven closed circuit television (CCTV) cameras, three highway advisory radio (HAR) beacons, relocation of one HAR beacon, two HAR transmitters, and relocation of one HAR transmitter, and miscellaneous construction as indicated on the approved construction drawings. DBE 1%, Anticipated Notice to Proceed 1-30-12, Required Completion 9-19-13.

---

**ALLEGHENY COUNTY – SR 376(A35) #50958**

**PROPOSAL:\$72.24 PLANS:\$182.38 12X18:\$223.83 24X36:\$3,233.10 EXSTRUCT:\$34.98 12X18:\$42.93 24X36:\$620.10** The description and location of the project is as follows: For the rehabilitation of the Squirrel Hill Tunnel, update electrical systems, lighting system, control system, ventilation system, structural repairs to the walls and arched ceiling, installation of water line, bridge repair, expansion dam replacement, bridge rehabilitation, and other miscellaneous construction, all within a length of 14,282 linear feet (2.70 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 0376, SECTIONS A35 and A47 (Penn Lincoln Parkway), in ALLEGHENY COUNTY, CITY OF PITTSBURGH, Commonwealth of Pennsylvania. This project being situated as follows: From the Squirrel Hill Interchange at Segment 0745/0744 Offset 0511/0459 (Station 865+50) to a point approximately the Swissvale Interchange at Segment 0771/0770 Offset 1714/1804 (Station 1009+20). Limit of Signing - From a point approximately 1500 feet east of Forbes Ave exit from SR 376 East at Segment 0721/0720 Offset 2246/2220 (Station 750+00) to a point approximately 100 feet east of Business Route 22 entrance to SR 376 westbound at Segment 0791/0790 Offset 2331/2274 (Station 1121+00). DBE 6%, Anticipated Notice to Proceed 1-30-12, Required Completion 7-25-14.

---

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**ECMS PROJECTS - ADVANCED INFORMATION – LETTING DECEMBER 15, 2011**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**Updated November 3, 2011**

**JEFFERSON COUNTY – SR 310(0) #87571**

**PROPOSAL:\$33.60 PLANS:\$5.72 12X18:\$7.02 24X36:\$101.40 X-SEC:\$2.86 12X18:\$3.51 24X36:\$50.70** The description and location of the project is as follows: For the replacement of the existing structures with a single span Composite Steel Multi-Girder bridge and a Pre-cast Reinforced Concrete Box Culvert with approach work and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 310, SECTION 552, in Jefferson COUNTY Young TOWNSHIP from approximately 1.2 miles north of the SR 310/SR 2015 intersection at segment 0050 offset 0071 to approximately 4.4 miles south of the SR 310/SR2017 intersection at segment 0050 offset 2122. MBE 1%, WBE 3%, Anticipated Notice to Proceed 1-30-12, Required Completion 5-30-14.