

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated February 9, 2016

LAWRENCE COUNTY – SR 18(L27) #29441

PROPOSAL:\$24.48 PLANS:\$21.34 12X18:\$26.19 24X36:\$378.30 The description and location of the project is as follows: This is a partial Design Build roadway project. Design activities are limited to: Concrete curb ramps For the milling and resurfacing, drainage, guide rail, shoulders, curb and sidewalk, concrete curb ramps, signing and pavement marking, signals, and other miscellaneous construction, all within a length of 23,606 linear feet (4.47 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 18, SECTION L27 (Jefferson Street / Wilmington Road), in LAWRENCE COUNTY, CITY OF NEW CASTLE, NESHANNOCK TOWNSHIP, Commonwealth of Pennsylvania. This project being situated as follows: From a point approximately 130 feet south of Grant Street at Segment 0350 Offset 1120 (Station 0+00) to a point approximately 285 feet north of SR 4012 (Mitchell Road) at Segment 0470 Offset 0346 (Station 237+06). Anticipated Notice to Proceed 4-11-16, Required Completion 10-28-16.

BEAVER COUNTY – SR 0000(FSR) #86975

PROPOSAL\$22.32 PLANS:\$12.10 12X18:\$14.85 24X36:\$214.50 X-SEC:\$8.58 12X18:\$10.53 24X36:\$152.10 The description and location of the project is as follows: This is a partial Design Build roadway project. Design activities are limited to: Concrete curb ramps For the bituminous trail, drainage, lighting, pavement marking, and other miscellaneous construction, all within a length of 6,348.76 linear feet (1.202 miles) as indicated on the approved drawings included in the bid package for SAFE ROUTES TO SCHOOL, in BEAVER COUNTY, CENTER TOWNSHIP, Commonwealth of Pennsylvania. This project being situated as follows: From the Municipal Building on Center Grange Road at Station 0+00 continuing along Poplar Drive to Community College Drive to the High School at Station 63+49. DBE 6%, Anticipated Notice to Proceed 5-25-16, Required Completion 10-19-16.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated February 4, 2016

LAWRENCE COUNTY – SR 2012(L02) #29388

PROPOSAL:\$35.16 PLANS:\$7.48 12X18:\$9.18 24X36:\$132.60 X-SEC:\$3.30 12X18:\$4.05 24X36:\$58.50 The description and location of the project is as follows: For the bridge replacement, including minor approach roadway work, and other miscellaneous construction, all within a length of 805 linear feet (0.152 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 2012, SECTION L02 (Union Valley Road), in LAWRENCE COUNTY, TAYLOR and SHENANGO TOWNSHIPS, Commonwealth of Pennsylvania. This project being situated as follows: From a point approximately 3610 linear feet east of SR 168 at Segment 0010 Offset 2575 (Station 71+50) to a point approximately 1460 linear feet west of Savannah Rd (SR 2001) at Segment 0020 Offset 0940 (Station 81+55). Anticipated Notice to Proceed 4-11-16, Required Completion 11-1-16.

BEAVER COUNTY – SR 4047(B04) #105007

PROPOSAL:\$29.52 PLANS:\$19.36 12X18:\$23.76 24X36:\$343.20 X-SEC:\$23.32 12X18:\$28.62 24X36:\$413.40 The description and location of the project is as follows: For the correction of a landslide condition with a rock buttress, reconstruction of bituminous roadway, drainage, guide rail, shoulder, and other miscellaneous construction all within a length of 6,597.9 linear feet (1.25 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 4047, SECTION B04 (Smiths Ferry Road), in BEAVER COUNTY, OHIOVILLE BOROUGH, Commonwealth of Pennsylvania. This project being situated as follows: From SR 68 at Segment 0010 Offset 0000 (Station 721+60) to a point approximately 4,325 feet south of the Westwood Road at Segment 0030 Offset 1717 (Station 789+30). Anticipated Notice to Proceed 3-7-16, Required Completion 11-24-16.

CLEARFIELD COUNTY – SR 879(A10) #69465

PROPOSAL:\$32.16 PLANS:\$22.00 12X18:\$27.00 24X36:\$390.00 X-SEC:\$4.84 12X18:\$5.94 24X36:\$85.80

EXSTRUCT:\$1.76 12X18:\$2.16 24X36:\$31.20 The description and location of the project is as follows: For the improvement of a certain section of STATE HIGHWAY in CLEARFIELD COUNTY, GOSHEN TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 0879, Section A10. The project being situated as follows: On State Route 0879 from Segment 0440 Offset 0062 to Segment 0440 Offset 1092, which is at the Village of Shawville near the intersection of SR 0879 with SR 0970. For the replacement of the bridge superstructure. Construction of approach and roadway consisting of Superpave Asphalt Mixture Designs for the base, binder and wearing courses. Installation of pavement base drain, drainage and inlets, guide rail, pavement markings and miscellaneous construction for a total construction length of approximately 785 linear feet (0.149 miles) as indicated on the approved drawings included in the bid package. DBE 3%, Anticipated Notice to Proceed 3-24-16, Required Completion 3-16-17.

ARMSTRONG COUNTY – SR 1029(150) #24016

PROPOSAL:\$25.32 PLANS:\$2.52 The description and location of the project is as follows: For the [describe the various construction activities involved including number of lanes and number of spans as appropriate. Try to keep the total number of characters to 300.] and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 1029, SECTION 150, in _____ COUNTY _____ CITY/BOROUGH/TOWNSHIP from approximately __ (geographical reference) __ at segment _____ offset _____ to approximately __ (geographical reference) __ at segment _____ offset _____. Anticipated Notice to Proceed 4-11-16, Required Completion 8-16-16.

INDIANA COUNTY – SR 1012(450) #83369

PROPOSAL:\$26.04 PLANS:\$2.76 The description and location of the project is as follows: Design, detailing, fabrication, storage, delivery, setting in place, post-tensioning, and grouting of a 24'-0" x 8'-6" Precast Box Culvert with precast End Sections on a Department prepared site and other miscellaneous construction as indicated on the approved drawings included in the bid package for STATE ROUTE 1012, SECTION 450, in Indiana COUNTY Cherryhill TOWNSHIP on SR 1012 over Penn Run at segment 0220 offset 2195. Also, a 24'-0" x 11'-0" Precast Box Culvert with precast End Sections on a Department prepared site and other miscellaneous construction as indicated on the approved drawings included in the bid package for STATE ROUTE 1029, SECTION 150, in Armstrong COUNTY Boggs TOWNSHIP on SR 1029 over North Fork of Pine Creek at segment 0020 offset 0544. Anticipated Notice to Proceed 4-11-16, Required Completion 7-19-16.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated February 3, 2016

ADAMS COUNTY – SR 116(030) #85652

PROPOSAL:\$18.00 PLANS:\$6.16 12X18:\$7.56 24X36:\$109.20 X-SEC:\$2.42 12X18:\$2.97 24X36:\$42.90 This intersection improvement project consist of widening the westbound SR 0116 approach to its intersection with SR 2008 for an additional left turn lane. Activities include full depth widening, resurfacing, curb, sidewalk, pavement markings and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 116, SECTION 030, in ADAMS COUNTY, McSHERRYSTOWN BOROUGH and CONEWAGO TOWNSHIP, from Segment 0480 Offset 3495 to Segment 0490 Offset 0544, for an overall project length of 728.88 linear feet (0.137 mile). DBE 6%, Anticipated Notice to Proceed 4-11-16, Required Completion 6-28-16.

BLAIR COUNTY – SR 7208(369) #95932

PROPOSAL:\$24.24 PLANS:\$8.36 12X18:\$10.26 24X36:\$148.20 The description and location of the project is as follows: This project is for the rehabilitation of two existing structures in Blair County. Roadway work will include roadway approaches, guiderail and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 7208, SECTION 369, in BLAIR COUNTY, HUSTON & TAYLOR TOWNSHIPS. Anticipated Notice to Proceed 5-23-16, Required Completion 10-3-16.

DAUPHIN COUNTY – SR 322(038) #19150

PROPOSAL:\$22.68 PLANS:\$13.64 12X18:\$16.74 24X36:\$241.80 This project consists of resurfacing the existing roadway and shoulders using Superpave wearing, scratch, and ultra-thin friction course; milling; concrete patching; guide rail replacement; base repair; minor drainage improvements; roadside development items; pavement markings; ADA ramp improvements; and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 0322, SECTION 038, in DAUPHIN COUNTY, SWATARA & DERRY TOWNSHIPS and HUMMELSTOWN BOROUGH, from the Eisenhower Interchange at Segment 0042/0043 Offset 1456/0585 to the Hershey Interchange at Segment 0230/0211 Offset 1712/2788, a length of 36,709.59 linear feet (6.95 miles). Also included is STATE ROUTE 0422, SECTION 029, from the Hershey Interchange at Segment 0010/0011 Offset 0000/0000 to North Orchard Road at Segment 0070/0061 Offset 0236/0295, a length of 8,778.82 linear feet (1.66 miles). Also included are SR 8012, SR 8014, and SR 8016. Overall project length is 90,386.73 linear feet (17.12 miles). DBE 4%, Anticipated Notice to Proceed 4-11-16, Required Completion 6-9-17.

LANCASTER COUNTY – SR 372(014) #63220

PROPOSAL:\$21.96 PLANS:\$13.20 12X18:\$16.20 24X36:\$234.00 X-SEC:\$2.20 12X18:\$2.70 24X36:\$39.00 This project consists of: (1) replacing a single-span reinforced concrete slab with a precast box culvert and (2) replacing a single-span reinforced slab structure with a prestressed adjacent box beam bridge structure, and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 0372, SECTION 014, in LANCASTER COUNTY, SADBURY TOWNSHIP, from Segment 0390 Offset 0125 to Segment 0390 Offset 0525, and from Segment 0400 Offset 2436 to Segment 0410 Offset 0176, for an overall project length of 443.96 linear feet (0.084 mile). Anticipated Notice to Proceed 4-11-16, Required Completion 9-14-16.

YORK COUNTY – SR 1043(002) #106244

PROPOSAL:\$16.20 PLANS:\$3.08 12X18:\$3.78 24X36:\$54.60 EXSTRUCT:\$5.72 12X18:\$7.02 24X36:\$101.40 This project consists of the rehabilitation of the existing two-lane four-span bridge that carries SR 1043 (Burgs Lane) over US 0030. The work includes the repair of the existing prestressed concrete superstructure due to collision damage, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 1043, SECTION 002, in YORK COUNTY, HELLAM TOWNSHIP, from Segment 0010 Offset 0000 to Segment 0010 Offset 0266, for an overall project length of 266.00 linear feet (0.05 mile). Anticipated Notice to Proceed 4-11-16, Required Completion 8-31-16.

CLEARFIELD COUNTY – SR 36(ST2) #104648

PROPOSAL:\$33.96 PLANS:\$8.14 12X18:\$9.99 24X36:\$144.30 The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAYS in CLEARFIELD, ELK and CAMERON COUNTIES, VARIOUS TOWNSHIPS and BOROUGHs, Commonwealth of Pennsylvania, Group 2-16-ST2. For the improvement to 27 State Routes having a combined construction length of approximately 256,202 linear feet (48.5 miles); involving various combinations of milling, scratch and resurfacing, using various Superpave Asphalt Mixture Designs for binder and wearing courses, curbing, sidewalks, detectable warning surfaces, guide rail, various pavement markings and legends, and miscellaneous construction as indicated on the approved drawings. Anticipated Notice to Proceed 4-11-16, Required Completion 11-3-16.

ALLEGHENY COUNTY – SR 4086(A05) #102210

PROPOSAL:\$29.88 PLANS:\$22.44 12X18:\$27.54 24X36:\$397.80 X-SEC:\$6.82 12X18:\$8.37 24X36:\$120.90 The description and location of the project is as follows: For widening to construct turning lanes, widening/rehabilitation of a bridge, guiderail, signing, curb, sidewalk, drainage, pavement markings, traffic signals and other miscellaneous construction, all within a length of 1,365 Linear Feet (0.26 Miles) as indicated on the approved drawings contained in the Bid Package for STATE ROUTE 4086 SECTION A05, ALLEGHENY COUNTY, MCCANDLESS TOWNSHIP from approximately 500' West of the intersection with SR 19 at Segment 30 Offset 2766 to the intersection with SR 4003 (McKnight Road) at Segment 40 Offset 1015. DBE 6%, Anticipated Notice to Proceed 4-11-16, Required Completion 12-2-16.

BERKS COUNTY – SR 422(20M) #94857

PROPOSAL:\$25.20 PLANS:\$129.14 12X18:\$158.49 24X36:\$2,289.30 X-SEC:\$90.86 12X18:\$111.51

24X36:\$1,610.70 EXSTRUCT:\$2.64 12X18:\$3.24 24X36:\$46.80 The description and location of the project is as follows: Highway resurfacing, safety improvements, and other miscellaneous construction including drainage improvements, new ADA compliant curb ramps, and bridge maintenance work (deck repairs, guiderail upgrades, scour protection) as indicated on the approved drawings included in the bid package for STATE ROUTE 0422, SECTION 20M, in BERKS COUNTY, HEIDELBERG, LOWER HEIDELBERG & SOUTH HEIDELBERG TOWNSHIP'S, WOMELSDORF, ROBESONIA & WERNERSVILLE BOROUGH'S from segment 0090 offset 0464 to segment 0230 offset 1812 and for STATE ROUTE 0422, SECTION 18M, in BERKS COUNTY, LOWER HEIDELBERG & SOUTH HEIDELBERG TOWNSHIP'S, SINKING SPRING & WERNERSVILLE BOROUGH'S from segment 0230 offset 1812 to segment 0290 offset 0000. DBE 6%, Anticipated Notice to Proceed 4-11-16, Required Completion 11-24-17.

WASHINGTON COUNTY – SR 7206(0) #70284

PROPOSAL:\$26.88 PLANS:\$14.52 12X18:\$17.82 24X36:\$257.40 X-SEC:\$1.10 12X18:\$1.35 24X36:\$19.50

EXSTRUCT:\$0.88 12X18:\$1.08 24X36:\$15.60 The description and location of the project is as follows: Replacement of Mawhinney Road Bridge over Millers Run, updating signing and pavement markings, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for Township Road T-706, Section MR3, in Washington County, Cecil Township from approximately Station 2+18.16 to 5+00.00. DBE 6%, Anticipated Notice to Proceed 4-26-16, Required Completion 11-28-16.

BEAVER COUNTY – SR 65(B29) #29032

PROPOSAL:\$74.64 PLANS:\$52.36 12X18:\$64.26 24X36:\$928.20 RXSTRUCT:\$38.94 12X18:\$47.79

24X36:\$690.30 The description and location of the project is as follows: This is a partial Design Build roadway project. Design activities are limited to: Traffic control plan and concrete curb ramps. For the full depth roadway reconstruction, milling and resurfacing, drainage, guide rail, curb and sidewalk, signing and pavement marking, signals, bridge preservation, and other miscellaneous construction, all within a length of 19,778 linear feet (3.745 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 0065, SECTION B29 (Ohio River Boulevard), in BEAVER COUNTY, CONWAY, FREEDOM, EAST ROCHESTER, and ROCHESTER BOROUGH'S, Commonwealth of Pennsylvania. This project being situated as follows: From a point approximately 1,100 feet north of Crow's Run Road at Segment 0160/0161 Offset 1111/1049 (Station 356+75) to the SR 18 off ramp to SR 0068 WB at Segment 0530 Offset 0612 (Station 516+22). DBE 8%, Anticipated Notice to Proceed 4-11-16, Required Completion 8-18-17.

YORK COUNTY – SR 24(023) #90913

PROPOSAL:\$18.36 PLANS:\$5.50 12X18:\$6.75 24X36:\$97.50 This project consist of roadway resurfacing, shoulder

repair, milling, base replacement, drainage updates, new signage, pavement marking replacement, and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 0024, SECTION 023, in York COUNTY, YORK & WINDSOR TOWNSHIPS and RED LION BOROUGH, from East Prospect Street at Segment 0320 Offset 1522 to Windsor Road at Segment 0420 Offset 0150, for an overall project length of 21,430.00 linear feet (4.06 Miles). Anticipated Notice to Proceed 4-11-16, Required Completion 10-7-16.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated January 25, 2016

LUZERNE COUNTY – SR 115(CRS) #104411

PROPOSAL:\$13.80 PLANS:\$1.92 The description and location of the project is as follows: This project is for the construction of full depth bituminous shoulders, milled shoulder rumble strips, and line painting as indicated on the approved drawings included in the bid package for STATE ROUTE 115, SECTION CRS, in LUZERNE COUNTY. Work will be performed on various state routes (115, 424, 437 & 924) with a total length of 13.22 mi (69,826 ft). DBE 5%, Anticipated Notice to Proceed 4-11-16, Required Completion 7-5-16.

SUSQUEHANNA COUNTY – SR 167(SLD) #96814

PROPOSAL:\$37.80 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00 X-SEC:\$2.20 12X18:\$2.70 24X36:\$39.00 This is a Design/ Build Project. For the rehabilitation and improvement of a certain section of STATE HIGHWAY in SUSQUEHANNA COUNTY, BROOKLYN TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 0167, SECTION SLD. The project being situated as follows – From a point approximately 0.52 miles NORTH of the intersection with SR 2049 (Oakley Road) at Station 137+45 to a point approximately 0.68 miles NORTH of the intersection with SR 2049 (Oakley Road) at Station 145+50 along SR 0167. This project involves reconstruction and stabilization of the embankment with geosynthetic reinforced soil (GRS). A signalized lane closure will be utilized. Drainage improvements and guiderail repair are also planned. Other work includes bituminous paving, line painting and guiderail work, all contained within an overall project length of 722.04 linear feet (0.137 mile) as indicated on the approved drawings included in the bid package. Anticipated Notice to Proceed 4-11-16, Required Completion 12-13-17.

SUSQUEHANNA COUNTY – SR 1022(SLD) #96815

PROPOSAL:\$43.08 PLANS:\$4.84 12X18:\$5.94 24X36:\$85.80 X-SEC:\$2.64 12X18:\$3.24 24X36:\$46.80 This is a Design/ Build Project. For the rehabilitation and improvement of a certain section of STATE HIGHWAY in SUSQUEHANNA COUNTY, LIBERTY TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 1022, SECTION SLD. The project being situated as follows – From a point approximately 0.25 miles EAST of the intersection with T806 at Station 186+50 to a point approximately 0.26 miles EAST of the intersection with T806 at Station 145+50 along SR 1022. This project involves the slope failure requiring a 112' soldier pile retaining wall. Drainage improvements will include two cross pipes to convey drainage away from the wall and down the slope and guiderail repair are also planned. Other work includes bituminous paving and line painting, all contained within an overall project length of 650 linear feet (0.123 mile) as indicated on the approved drawings included in the bid package. Anticipated Notice to Proceed 4-11-16, Required Completion 10-23-17.

NORTHAMPTON COUNTY – SR 248(03S) #94864

PROPOSAL:\$24.24 PLANS:\$6.38 12X18:\$7.83 24X36:\$113.10 X-SEC:\$2.86 12X18:\$3.51 24X36:\$50.70 The description and location of the project is as follows: this projects incorporates upgrade from beacon to signal and safety improvements for the intersection of S.R. 0248 and S. R 4003 (Walnut Dr.) Work involves approach roadway construction, new traffic signal supports and equipment, minor drainage improvements, limited signing and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 248, SECTION 03S, in NORTHAMPTON COUNTY, LEHIGH TOWNSHIP from approximately 1000 feet from S.R. 0248 / S.R 4003 (Walnut Dr.) at segment 150 offset 260 to segment 140 offset 1593 and for STATE ROUTE 4003 from segment 100 offset 2466 to segment 110 offset 0609. DBE 8%, Anticipated Notice to Proceed 4-11-16, Required Completion 11-8-16.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated January 21, 2016

WASHINGTON COUNTY – SR 136(G10) #30749

PROPOSAL:\$29.76 PLANS:\$20.24 12X18:\$24.84 24X36:\$358.80 X-SEC:\$2.86 12X18:\$3.51 24X36:\$50.70

EXSTRUCT:\$1.10 12X18:\$1.35 24X36:\$19.50 The description and location of the project is as follows: Bridge replacement on SR 0136, Section G10 over Allegheny Valley Railroad and Little Chartiers Creek, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0136, SECTION G10, in WASHINGTON COUNTY, N. STRABANE, S. STRABANE, and SOMERSET TOWNSHIPS from segment 0140 offset 1981 to segment 0150 offset 0045. Anticipated Notice to Proceed 4-11-16, Required Completion 8-22-16.

WESTMORELAND COUNTY – SR 31(RDI) #104423

PROPOSAL:\$14.04 PLANS:\$4.62 12X18:\$5.67 24X36:\$81.910 The description and location of the project is as follows: Roadway Departure Implementation Project. Various municipalities in Greene, Washington and Westmoreland Counties all as indicated on the approved drawings for Dist12-15RDIP-3. The improvements will consist of the removal of cable guide rail and installing new guide rail. DBE 6%, Anticipated Notice to Proceed 4-11-16, Required Completion 7-1-16.

FOREST COUNTY – SR 948(03M) #97893

PROPOSAL:\$16.08 PLANS:\$8.36 12X18:\$10.26 24X36:\$148.20 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30 For the construction or improvement of a certain section of STATE HIGHWAY in ELK, FOREST, WARREN COUNTIES, HIGHLAND, HOWE, JENKS, AND SHEFFIELD TOWNSHIPS, Commonwealth of Pennsylvania, STATE ROUTE 0948 SECTION 03M. This project being situated as follows: From approximately 3.9 miles east of the intersection with SR. 0666 at Segment 0560 Offset 2942 (Station 0+00) then west to the Elk/Forest County Line at Segment 0560 Offset 2992 (Station 0+50.00). From the Elk/Forest County Line at Segment 0010 Offset 0000 (Station 0+50.00) then west to the Forest/ Warren County Line at Segment 0070 Offset 2359 (Station 163+28.00). From Forest/Warren County Line at Segment 0010 Offset 0000 (Station 163+28.00) then west to approximately 1.7 miles east of SR. 0066 at Segment 0010 Offset 0100 (Station 164+28.00). For the bituminous milling and overlay with Warm Mix Superpave Asphalt Mixture Designs 22' in width; also for drainage, guiderail, paved shoulders, signing, and pavement markings all within a project length of 16,278 feet (3.083 miles) as indicated on the approved drawings. Anticipated Notice to Proceed 4-11-16, Required Completion 5-2-17.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated January 19, 2016

CRAWFORD COUNTY – SR 79(A17) #91570

PROPOSAL:\$21.48 PLANS:\$9.90 12X18:\$12.15 24X36:\$175.50 For the improvement of STATE ROUTE 79, SECTION A17, in CRAWFORD COUNTY, Vernon, Hayfield, Greenwood and Union Townships, Commonwealth of Pennsylvania, from approximately 4,364 feet north of the Greenwood/Union Township line at segment 1414 Offset 1919, to approximately 2,396 north of the intersection with State Route 198 at segment 1534 offset 100. For the milling and resurfacing of the existing roadway, and guiderail, drainage, and signing updates, and also for miscellaneous structure repairs, as indicated on the approved drawings. DBE 6%, Anticipated Notice to Proceed 4-11-16, Required Completion 5-1-17.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated January 18, 2016

MONTOUR COUNTY – SR 0000(LBR) #88528

PROPOSAL:\$26.76 PLANS:\$5.94 12X18:\$7.29 24X36:\$105.30 X-SEC:\$1.76 12X18:\$2.16 12X18:\$31.20 The description and location of the project are as follows: For the removal of the existing bridge, construction of a 20'-0" x 5'-6" precast reinforced concrete box culvert over Middle Branch Chillisquaque Creek, selected borrow excavation rock, guide rail, seeding and soil supplements, signs, and other miscellaneous construction within an overall length of 450.00 feet (0.085 mile) as indicated on the approved drawings included in the bid package for T-361 (Fairview Road) from approximately 0.9 mile southeast of the intersection with State Route 1011 at Station 10+00.00 to approximately 0.4 mile northwest of the intersection with State Route 44 at Station 15+50.00 in ANTHONY TOWNSHIP, MONTOUR COUNTY. DBE 1%, Anticipated Notice to Proceed 5-9-16, Required Completion 9-30-16.

CRAWFORD COUNTY – SR 6(B17) #57942

PROPOSAL:\$74.76 PLANS:\$26.84 12X18:\$32.94 24X36:\$475.80 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30
EXSTRUCT:\$15.62 12X18:\$9.17 24X36:\$276.90 For the construction of a certain section of STATE HIGHWAY in CRAWFORD COUNTY, WEST MEAD AND VERNON TOWNSHIPS AND CITY OF MEADVILLE; Commonwealth of Pennsylvania; STATE ROUTE 0006, SECTION B17. This project situated as follows: From approximately 0.4 miles east from SR. 0102 at Segment 0490 Offset 2029 (Station 945+14.00) then east to approximately 0.04 miles west of the intersection with SR. 0322 at Segment 0510 Offset 0475 (Station 981+41.00). For the structure rehabilitation of a multi-span box beam bridge on SR. 0006 over French Creek, having an overall length of 1623'-1/8" feet; Also for bituminous milling and overlay, and bituminous full depth reconstruction with WMA Mixture Designs, concrete pavement patching, guide rail, asbestos removal, design and construction of structure lighting system, pavement markings, and other miscellaneous work all within a project length of 3427.00 feet (0.649 mile) as indicated on the approved drawings. The description and location of the project is as follows: For the bridge rehabilitation of SR 6 (Smock Bridge) over French Creek Parkway and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0006, SECTION B17, in Crawford COUNTY in West Mead and Vernon Townships and the City of Meadville from approximately __ (geographical reference) __ at segment _____ offset _____ to approximately __ (geographical reference) __ at segment _____ offset _____. DBE 2%, Anticipated Notice to Proceed 4-11-16, Required Completion 10-11-16.

SOMERSET COUNTY – SR 3025(04B) #23457

PROPOSAL:\$42.60 PLANS:\$15.84 12X18:\$19.44 24X36:\$280.80 X-SEC:\$3.52 12X18:\$4.32 24X36:\$62.40 The description and location of the project is as follows: This project is for the replacement of the structure that carries SR 3025 over the CSX Railroad tracks. The existing SR 3025 bridge is a single lane, one-span steel truss and will be replaced with a two lane structure on alignment. Roadway improvements will include improving the SR 3025/SR 3015 intersection and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 3025, SECTION 04B in SOMERSET COUNTY, SOMERSET TOWNSHIP at the following location: Station 10+00.00 to Station 9+15.00 Segment 0010, Offset 0000 to Segment 0010, Offset 0842. DBE 6%, Anticipated Notice to Proceed 4-11-16, Required Completion 11-9-16.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated January 13, 2016

BRADFORD COUNTY – SR 0000 #102860

PROPOSAL:\$13.44 PLANS:\$2.40 The description and location of the project is as follows: Pipe linings and other miscellaneous construction, as indicated on the approved drawings included in the bid package for VARIOUS STATE ROUTES, VARIOUS TOWNSHIPS in BRADFORD, NORTHUMBERLAND, AND TIOGA COUNTIES. Anticipated Notice to Proceed 4-11-16, Required Completion 10-21-16.

CLEARFIELD COUNTY – SR 219(A09) #88655

PROPOSAL:\$20.52 PLANS:\$8.80 12X18:\$10.80 24X36:\$156.00 X-SEC:\$2.64 12X18:\$3.24 24X36:\$46.80 The description and location of the project is as follows: For the improvement of a certain section of STATE HIGHWAY in CLEARFIELD COUNTY, BELL TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 0219, SECTION A09. The project is situated as follows: On State Route 0219 from Segment 0350 Offset 1575 to Segment 0360 Offset 0368 approximately 2.2 miles East of the Village of Mahaffey. For a construction length of approximately 510 feet (0.097 miles). For the removal of the existing single span Reinforced Concrete T-Beam bridge and the construction of its replacement, a Single Cell Precast Reinforced Concrete Box Culvert. Construction includes Superpave Asphalt Mixture Designs for the base, binder, and wearing courses, guide rail, pavement markings, and miscellaneous construction as indicated on the approved construction drawings. DBE 2%, Anticipated Notice to Proceed 3-28-16, Required Completion 10-18-16.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated January 8, 2016

UNION COUNTY – SR 0(BR) #7500

PROPOSAL:\$45.84 PLANS:\$16.50 12X18:\$20.25 24X36:\$292.50 X-SEC:\$3.08 12X18:\$3.78 24X36:\$54.60 The description and location of the project are as follows: For the removal of the existing bridge, construction of a single span composite prestressed concrete spread box beam bridge or an approved equal over Buffalo Creek, excavation, selected borrow excavation rock, superpave asphalt mixture design base and wearing courses, subbase, drainage, guide rail, plain cement concrete curb, seeding and soil supplements, signs, utility relocation and other related work within an overall length of 800.00 linear feet (0.152 miles) all as indicated on the approved drawings included in the bid package for NORTH THIRD STREET (County Bridge No. 14 over Buffalo Creek) from approximately 0.51 miles north of the intersection with State Route 45 to approximately 0.49 miles south of the intersection with Township Road 347 (Green Ridge Road) in MIFFLINBURG BOROUGH, UNION COUNTY. DBE 2%, Anticipated Notice to Proceed 5-25-16, Required Completion 5-19-17.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
ECMS ADVANCED INFORMATION – LETTING FEBRUARY 25, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

COLUMBIA COUNTY – SR 239(018) #74029

PROPOSAL:\$23.04 PLANS:\$13.20 12X18:\$16.20 24X36:\$234.00 X-SEC:\$5.94 12X18:\$7.29 24X36:\$105.30 The description and location of the project are as follows: For the removal of the existing bridge, construction of a single span prestressed concrete spread box beam bridge, or an approved equal, over West Creek, selected borrow excavation rock, superpave base and wearing courses, drainage, guide rail, pavement markings, and other related work within an overall length of 616.00 linear feet (0.117 miles) all as indicated on the approved drawings included in the bid package for STATE ROUTE 236, SECTION 018 from approximately 4.12 miles southeast of the intersection with State Route 118 at SEGMENT 0170 OFFSET 2216 to approximately 2.14 miles northwest of the intersection with State Route 487 at SEGMENT 0170 OFFSET 1400 in SUGARLOAF TOWNSHIP, COLUMBIA COUNTY. DBE 0%, Anticipated Notice to Proceed 11-16-15, Required Completion 10-21-16.
