

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING JULY 8, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated June 27, 2016

ERIE COUNTY – SR 0 #105871

PROPOSAL:\$17.76 PLANS:\$1.10 12X18:\$1.35 24X36:\$19.50 Project A251-1031 includes - Removal of the current roofing system and Replacement with a 60 mil, Energy Star Rated, Black, fully adhered E.P.D.M. Roofing System. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING JULY 8, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated June 15, 2016

CENTRE COUNTY – SR 0000 #107189

PROPOSAL;\$35.64 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 A251-1059 (0.2), includes site demolition, fencing, landscaping and soils, installation of new concrete pads and fenced enclosures, building work – including framing of openings, patching of existing openings in various locations along with interior / exterior painting and site restoration. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

CENTRE COUNTY – SR 0000 #107190

PROPOSAL;\$34.32 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 A251-1059 (0.4), includes the removal of existing electrical connections, demolition work and installation of new breakers, transformer and electrical panels along with extension of circuits to serve new equipment. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING JULY 8, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated June 14, 2016

CLINTON COUNTY – SR 0 #107139

PROPOSAL:\$37.68 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 A251-0944.2 Includes site demolition fencing, landscaping and soils, installation of new concrete pads and fenced enclosures, building work including framing of openings and patching of existing openings in various locations and interior and exterior painting and site restoration. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

CLINTON COUNTY – SR 0 #107140

PROPOSAL:\$37.92 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 A251-0944.4 includes the removal of existing electrical connections serving demolition work and installation of new breakers, transformer and electrical panels and extension of circuits to serve new equipment. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16

CENTRE COUNTY – SR 0 #107191

PROPOSAL:\$35.64 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 A251-1060 (0.2), includes site demolition, fencing, landscaping and soils, installation of new concrete pads and fenced enclosures, building work – including framing of openings, patching of existing openings in various locations along with interior / exterior painting and site restoration. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

CENTRE COUNTY – SR 0 #107192

PROPOSAL:\$35.64 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 A251-1060 (0.4), includes the removal of existing electrical connections, demolition work and installation of new breakers, transformer and electrical panels along with extension of circuits to serve new equipment. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

LEHIGH COUNTY – SR 0000 #107007

PROPOSAL:\$24.36 PLANS:\$1.10 12X18:\$1.35 24X36:\$19.50 A251-0997 is for the removal and replacement of the existing concrete curb and sidewalk at the District 5 office building in the city of Allentown PA. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

SOMERSET COUNTY – SR 0000 #107402

PROPOSAL:\$31.68 PLANS:\$5.72 12X18:\$7.02 24X36:\$101.40 A251-1044 (.1) Demolition of an existing domed salt storage building. Demolition shall include removal and disposal of all timber framing and concrete base at an approved landfill. Construct a new 60' wide by 80' long timber framed, concrete base salt storage building in accordance to approved plans. Construction shall include grading to provide a level building pad prior to excavation for footings and walls; reinforced concrete footings and walls as shown having a wall height extending 10' above highest grade on finished floor; timber framing anchored to concrete walls, extending to a required height to provide an underclearance of 24' above highest grade on finish floor; a 6" reinforced concrete floor slab and concrete approach apron over a 6' subbase; and a bituminous apron along the entire perimeter of the building as shown. Anticipated Notice to Proceed 8-19-16, Required Completion 12-19-16.

SOMERSET COUNTY – SR 0000 #107403

PROPOSAL:\$11.88 PLANS:\$5.72 12X18:\$7.02 24X36:\$101.40 A251-1044 (.4) De-energize and remove all electrical fixtures, conduit, conductors, and hardware from the existing building prior to demolition. Work shall be coordinated with .1 Contractor. Install a new panel at the Main Distribution Panel and a new 100-Amp subpanel at the building. Install all interior/exterior lighting, receptacles, switches, conductors, conduit and miscellaneous hardware necessary to make the building electrical system 100% operational. Anticipated Notice to Proceed 8-19-16, Required Completion 12-19-16.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
ECMS PROJECTS - ADVANCED INFORMATION – LETTING JULY 8, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

LANCASTER COUNTY – SR 0000 #107335

PROPOSAL:\$24.60 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 A251-0935.1 Seal wall opening, infill window frames, remove and replace ceiling tiles. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

LANCASTER COUNTY – SR 0000 #107336

PROPOSAL:\$ 24.60 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 A251-0935.2 Remove existing HVAC equipment, install new HVAC equipment. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.

LANCASTER COUNTY – SR 0000 #107337

PROPOSAL:\$ 24.60 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 A251-0935.4 Disconnect existing HVAC equipment, furnish and install new breakers, conduit, wiring, and connections to new HVAC equipment. Anticipated Notice to Proceed 8-19-16, Required Completion 11-17-16.
