

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING AUGUST 11, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated July 20, 2016

MERCER COUNTY – SR 0(BR) #1694

PROPOSAL:\$19.08 PLANS:\$10.78 12X18:\$13.23 X-SEC:\$0.88 12X18:\$1.08 24X36:\$15.60 For the construction or improvement of a certain sections of LOCAL HIGHWAY in MERCER COUNTY, SANDY LAKE BOROUGH, Commonwealth of Pennsylvania, T-569 (Walnut Street), SECTION 000. This project is situated as follows: From Turner Craig Town Park at Station 5+00.00 then north to approximately 0.07 mile south of the intersection with SR. 0358 at Station 8+00.00. For bridge structure replacement with a 1-Span Composite Prestressed Concrete Adjacent Box Beam Bridge over Outlet to Sandy Lake having an overall length of 23'-00" feet; Also includes removal of existing structure, drainage, guiderail, and bituminous roadway approaches with Warm Mix Asphalt designs all within a project length of 200.00 feet (0.038 mile) as indicated on the approved drawings. DBE 4%, Anticipated Notice to Proceed 11-7-16, Required Completion 9-26-17.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING AUGUST 11, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated July 15, 2016

VENANGO COUNTY – SR 0000 #107129

PROPOSAL:\$22.32 The maintenance, repair and replacement of highway lighting, sign lighting, flashing warning devices and other miscellaneous construction on various state routes in CRAWFORD, ERIE, MERCER AND VENANGO COUNTIES as indicated. Anticipated Notice to Proceed 9-26-16, Required Completion 6-30-18.

MIFFLIN COUNTY – SR 322(717) #104261

PROPOSAL:\$18.72 PLANS:\$8.80 12X18:\$10.80 24X36:\$156.00 The description and location of the project is as follows: For construction of Intelligent Transportation System (ITS) devices at certain sections of State Route 322 in BROWN and ARMAGH TOWNSHIPS in MIFFLIN COUNTY, Commonwealth of Pennsylvania. The construction length is approximately 7,761 feet (1.47 miles). Construction includes one dynamic message sign (DMS) with a speed feedback detection device, five closed circuit television (CCTV) cameras, one highway advisory radio (HAR) transmitter, and miscellaneous construction as indicated on the approved construction drawings. DBE 1%, Anticipated Notice to Proceed 9-26-16, Required Completion 1-29-18.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS PROJECTS - ADVANCED INFORMATION – LETTING AUGUST 11, 2016
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

ELK COUNTY – SR 66(N29) #93587

PROPOSAL:\$38.52 PLANS:\$12.10 12X18:\$14.85 24X36:\$214.50 X-SEC:\$4.40 12X18:\$5.40 24X36:\$78.00 The description and location of the project is as follows: For the improvements of a certain section of STATE HIGHWAY IN ELK COUNTY, HIGHLAND TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 66, SECTION N29. The project being situated as follows: On SR 66 starting approximately 1650 feet before the intersection with SR 948. Construction is from Segment 0090 Offset 0677 to Segment 0100 Offset 1043 for a total construction length of approximately 2,760 feet (0.523 miles). On SR 948 starting at the intersection with SR 66. Construction is from Segment 0522 Offset 0516 to Segment 0520 Offset 0780 for a total construction length of approximately 828 feet (0.157 miles). For the relocation of SR 948 at the intersection of SR 66. Construction includes Superpave Asphalt Mixture Designs for the base, binder, and wearing courses, subbase, pavement markings, guide rail, drainage items, roadway signs, tree planting, and miscellaneous construction as indicated on the approved construction drawings. DBE 3%, Anticipated Notice to Proceed 9-26-16, Required Completion 10-27-17.

SULLIVAN COUNTY – SR 4008(019) #103518

PROPOSAL:\$12.84 PLANS:\$4.18 12X18:\$5.13 24X36:\$74.10 The description and location of the project is as follows: Procuring and setting of pre-cast box culvert and inlet and outlet section, including grouting and post-tensioning and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 4008, SECTION 019, in SULLIVAN COUNTY, ELKLAND TOWNSHIP from approximately 1.8 miles east of the intersection with SR 4006 at segment 0080 offset 0350 to approximately 1.7 miles northwest of the intersection with SR 4007 at segment 0080 offset 0814. Anticipated Notice to Proceed 9-26-16, Required Completion 8-18-17.

SCHUYLKILL COUNTY – SR 1017(ADA) #106251

PROPOSAL:\$19.08 PLANS:\$1.08 The description and location of the Partial Design/Build project is as follows: Replacing 109 Existing Concrete Curb Ramps, existing curb, Sidewalk, and other miscellaneous construction, items as indicated on the approved drawings included in the bid package for Various STATE ROUTES, SECTION 1017/ ADA, in SCHUYLKILL COUNTY- ORWIGSBURG BORO SR 443 SEG/OFF 470/0463(STRAUB AVE.)TO SEG/OFF. 0480/0652 (CHURCH ST.) MCADOO BORO, KLINE TWP. SR 1009 SEG./OFF. 20/000 (JAMES ST.) TO 40/1854(PUTNUM ST.) MONROE COUNTY- MT. POCONO BORO, COOLBAUGH TWP. SR 196 SEG/OFF. 10/0109(AT SR611) AND SEG/OFF. 70/0590(WILDFLOWER DR.) NORTHAMPTON COUNTY,NORTHAMPTON COUNTY- LOWER SAUCON TWP. TO THE CITY OF BETHLEHEM SR 378 SEG/OFF. 30/0791 (SAUCON VALLEY SQUARE) TO SEG/OFF. 60/0449 (ITASKA ST.) Project length N/A. Anticipated Notice to Proceed 9-26-16, Required Completion 10-31-17.

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN
SUBSCRIPTION