

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ADVANCED INFORMATION – LETTING JUNE 2, 2017
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

As of May 16, 2017

FULTON COUNTY – SR 0000 #107716

PROPOSAL:\$36.24 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 FM 6328, Welcome Center B HVAC Construction: 1. Provide new Air Handling Unit and Energy Recovery Unit along with associated ductwork, controls, supports, etc. as shown on the drawings and described in the specifications. 2. Perform air balancing and testing as described in the specifications. 3. Remove existing mechanical equipment as indicated on the drawings. 4. Provide permanent fencing. 5. Provide temporary facilities and construction fencing. 6. Perform all work designated to be by "Lead Contractor". Anticipated Notice to Proceed 7-14-17, Required Completion 10-12-17.

FULTON COUNTY – SR 0000 #107717

PROPOSAL:\$36.36 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10 FM 6328, Welcome Center B Electrical Construction 1. Provide new panelboard and branch circuits. 2. Provide power to new HVAC equipment. Anticipated Notice to Proceed 7-14-17, Required Completion 10-12-17.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
ADVANCED INFORMATION – LETTING JUNE 2, 2017
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

YORK COUNTY – SR 0000 #107257

PROPOSAL:\$36.12 PLANS:\$1.54 12X18:\$1.89 24X36:\$27.30 Removal of existing gate and fence, installation of new fence and automatic gate operator including power supply. Anticipated Notice to Proceed 7-14-17, Required Completion 10-12-17.

YORK COUNTY – SR 0000 #107350

PROPOSAL:\$36.12 PLANS:\$1.54 12X18:\$1.89 24X36:\$27.30 Installation of conduit and power supply from existing electrical panel to the location of the new gate operator. Anticipated Notice to Proceed 7-14-17, Required Completion 10-12-17.

LANCASTER COUNTY – SR 0000 #107335

PROPOSAL:\$24.60 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 A251-0935.1 Seal wall opening, infill window frames, remove and replace ceiling tiles. Anticipated Notice to Proceed 7-14-17, Required Completion 11-13-17.

LANCASTER COUNTY – SR 0000 #107336

PROPOSAL:\$24.60 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 A251-0935.2 Remove existing HVAC equipment, install new HVAC equipment. Anticipated Notice to Proceed 7-14-17, Required Completion 11-13-17.

LANCASTER COUNTY – SR 0000 #107337

PROPOSAL:\$24.60 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 A251-0935.4 Disconnect existing HVAC equipment, furnish and install new breakers, conduit, wiring, and connections to new HVAC equipment. Anticipated Notice to Proceed 7-14-17, Required Completion 11-13-17.

YORK COUNTY – SR 0000 #105882

PROPOSAL:\$ Remove bituminous pavement in area of building footprint. Provide the following: a. Foundation system: concrete footing, cmu foundation walls and concrete slab on grade. b. One-story, 19'x36' wood framed building with office, staging and utility room. c. Wood truss roofing system above. d. Exterior wall finish: Vinyl siding over "zip" system sheathing with impregnated weather barrier and taped edge joints. e. Interior wall: OSB on framing with FRP glued to OSB. f. Ceiling: Metal panels on furring attached to underside of trusses. g. Metal roofing system: 36" panel, 3/4" rib, exposed fastener, lap seam. h. Gutters and downspouts to catch and direct water away from building and adjacent salt barn. i. ADA compliant throughout with 6" ramp at entry. Anticipated Notice to Proceed 7-14-17, Required Completion 11-13-17.

YORK COUNTY – SR 0000 #107614

PROPOSAL:\$42.72 PLANS:\$2.42 12X18:\$2.97 24X36:\$42.90 Provide 2-zone ductless minis-split conditioning system. Air handlers shall be mounted in ceiling of staging room and office, and single condenser located on concrete slab between ramp / sidewalk and building. Anticipated Notice to Proceed 7-14-17, Required Completion 11-13-17.

YORK COUNTY – SR 0000 #107615

PROPOSAL:\$42.72 PLANS:\$2.42 12X18:\$2.97 24X36:\$42.90 Replace existing meter base and panel board with 200A, 120/240 single phase base and panel board. Provide the following: a. Circuit to staging facility b. Interior light fixtures mounted on ceiling c. Exterior fixtures on all sides and connected to motion sensors d. Exhaust fan in storage room. e. Reconnect all existing circuits to the new panel. f. Infra-Red and Arch Flash reports. Anticipated Notice to Proceed 7-14-17, Required Completion 11-13-17.

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION