

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING SEPTEMBER 28, 2017
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated September 5., 2017

BLAIR COUNTY – SR 0000 #109802

PROPOSAL:\$37.92 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 Provide removal and disposal of all elements of the current HVAC system requiring replacement; prior to disposal, coordinate with the Using Agency to determine retention. Provide the current system with new air terminal units, power wiring, low voltage wiring, and data network as required. Provide a Direct Digital Control System using BACnet protocol from an approved control system manufacturer as indicated on the attachments to operate the system. Provide new VAV dampers as necessary, replace metal ductwork to accommodate new VAV dampers if necessary. Provide and integrate all necessary system components including metal ductwork and controls to make the HVAC System Up-grades 100% functional and other miscellaneous construction, as indicated in the bid package for the project located in Hollidaysburg Borough, Blair County. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

BLAIR COUNTY – SR 0000 #109809

PROPOSAL:\$37.92 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20 Provide Power wiring to new HVAC equipment. Provide New panel board installations. Removal and reinstallation new ceiling lights as indicated in the bid package for the project located in Hollidaysburg Borough, Blair County. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

WESTMORELAND COUNTY – SR 0000 #109789

PROPOSAL:\$49.80 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00 Demolition of existing 60-foot-tall masonry chimney and associated flue duct and wall Penetration as indicated in the bid package for the project located in Greensburg Borough, Westmoreland County. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

WESTMORELAND COUNTY – SR 0000 #109790

PROPOSAL:\$49.80 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00 Brine storage and pumping system including controls, piping, valves, fittings, and pipe supports. System connection to existing brine generation system, the painting of piping and the system testing and inspection for the project located in Greensburg Borough, Westmoreland County. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

WESTMORELAND COUNTY – SR 0000 #109791

PROPOSAL:\$49.80 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00 Demolition of existing panels and installation of new and supply Electrical service to the new equipment and new Exterior lighting and power for the project located in Greensburg Borough, Westmoreland County. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

ALLEGHENY COUNTY – SR 0000 #86974 (T EH)

PROPOSAL:\$18.60 PLANS:\$2.86 12X18:\$3.51 24X36:\$50.70 The description and location of the project is as follows: This is a partial Design Build roadway project. Design activities are limited to: Concrete curb ramps For the sidewalk and curb restoration, crosswalks and other miscellaneous construction, all within the length of 2626.50 linear feet (0.497 miles) as indicated on the approved drawings included in the bid package for the SAFE ROUTES TO SCHOOL PROJECT, in ALLEGHENY COUNTY, BOROUGH OF MUNHALL, Commonwealth of Pennsylvania. This project being situated as follows: Along Main Street, from the intersection with Sycamore Drive to the intersection with Farragut Street. DBE 6%, Anticipated Notice to Proceed 12-26-17, Required Completion 8-6-18.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING SEPTEMBER 28, 2017
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated August 30, 2017

BEDFORD COUNTY – SR 0000 #109765

PROPOSAL:\$54.24 PLANS:\$2.42 12X18:\$2.97 24X36:\$42.90 Provide a level building pad for construction of the new personnel staging building having a finish floor elevation six inches above proposed finish exterior grade and slope adjacent grade to slope away from the building. Construction of a new personnel staging building, 24' by 20' and other miscellaneous construction, as indicated in the bid package for the project located in South Woodburg Township, Bedford County. Anticipated Notice to Proceed 11-13-17, Required Completion 3-13-18.

BEDFORD COUNTY – SR 0000 #109766

PROPOSAL:\$54.24 PLANS:\$2.42 12X18:\$2.97 24X36:\$42.90 Install cove radiant heating electric panels (Air conditioning will not be included) and other miscellaneous construction, as indicated in the bid package for the project located in South Woodburg Township, Bedford County. Anticipated Notice to Proceed 11-13-17, Required Completion 3-13-18.

BEDFORD COUNTY – SR 0000 #109767

PROPOSAL:\$54.24 PLANS:\$2.42 12X18:\$2.97 24X36:\$42.90 Install a new 400-Amp Main Distribution Panel at a location capable of servicing the new staging building and future expansion of the site including all saw cutting, trenching, bedding, conduit, conductors and backfill necessary to complete the installation. Install a new subpanel in the utility room of the new staging building capable of meeting the electrical requirements of the building and provide for any future expansion. Installation of two 20-Amp circuits from the building subpanel to the pressure treated timber posts installed for truck heater receptacles; include all trenching, bedding, conduit, conductors, PVC weatherproof receptacle boxes, truck heater receptacles and weatherproof covers and other miscellaneous construction, as indicated in the bid package and the project located in South Woodburg Township, Bedford County. Anticipated Notice to Proceed 11-13-17, Required Completion 3-13-18.

BERKS COUNTY – SR 0000 #109760

PROPOSAL:\$18.84 PLANS:\$5.06 12X18:\$6.21 24X36:\$89.70 is to replace and upgrade finished, fixtures, and accessories for two existing restrooms, and other miscellaneous construction, as indicated on the approved drawings included in the bid package located in Berks County, Muhlenberg Twp. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

BERKS COUNTY – SR 0000 #109761

PROPOSAL:\$18.84 PLANS:\$5.06 12X18:\$6.21 24X36:\$89.70 is to replace and upgrade plumbing for two existing restrooms, and other miscellaneous construction, as indicated on the approved drawings included in the bid package located in Berks County, Muhlenberg Twp. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

BERKS COUNTY – SR 0000 #109762

PROPOSAL:\$18.84 PLANS:\$5.06 12X18:\$6.21 24X36:\$89.70 is to replace and upgrade lights, receptacles, equipment's, conduits and wire for two existing restrooms, and other miscellaneous construction, as indicated on the approved drawings included in the bid package located in Berks County, Muhlenberg Twp. Anticipated Notice to Proceed 11-13-17, Required Completion 2-12-18.

ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING SEPTEMBER 28, 2017
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)

Updated August 25, 2017

BUCKS COUNTY – SR 0000 #105645

PROPOSAL:\$19.08 PLANS:\$9.46 12X18:\$11.61 24X36:\$167.70 The description and location of the project is as follows: This project involves traffic signal upgrades at three intersections, two in Bristol Township and one in Falls Township along with the installation of traffic adaptive signal equipment at 12 intersections along two corridors in Bucks County; Lincoln Hwy (SR 0413/2037) and Woodbourne Road (SR 2033) both in Middletown Township. The project limits for the adaptive system along Lincoln Highway (SR 0413/2037) is from approximately the I-95 SB on Ramp at segment 0180 offset 0000 to approximately Oxford Valley Road at segment 0160 offset 0170 and along Woodbourne Road (SR 2033) from approximately Lincoln Highway at segment 0080 offset 0780 to approximately 4th Street/Oxford Valley Mall Access at segment 0090 offset 1718. The project limits for the two individual intersections planned for upgrades in Bristol Township are Bristol-Oxford Valley Road (SR 2029) & Bath Rd (SR 2049)/Lakeland Ave from segment 0030 offset 1858 to approximately segment 0040 offset 0221 along Bristol-Oxford Valley Road and New Falls Road (SR 2006) & Oxford Valley Rd/Levittown Parkway (SR 2051) from segment 0084 offset 0105 to approximately segment 0084 offset 0755 along New Falls Road. The one intersection planned for upgrades in Falls Township is Mill Creek Parkway & Levittown Parkway (SR 2051) from segment 0020 offset 1859 to approximately segment 0020 offset 2360 along Levittown Parkway. Anticipated Notice to Proceed 11-13-17, Required Completion 7-31-18.

YORK COUNTY – SR 462(046) #99506

PROPOSAL:\$ 20.76 PLANS:\$9.68 12X18:\$11.88 24X36:\$171.60 The project consists of installing the InSync Adaptive Signal Control Systems, placement of video detection, signal controller cabinets, left turn on yellow signal heads, along with other miscellaneous construction items, and signal re-timing, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 0462, SECTION 046, in SPRING GARDEN & SPRIGGETTSBURY TOWNSHIPS, from Segment 0100/1364 to Segment 0150/0300, and from Segment 0101/1367 to Segment 0150/0300. Also included are replacing the existing traffic signal strain poles and wires with mast poles and arms, installing conduit, ADA ramps, curb, sidewalk, along with roadway base replacement along with other miscellaneous construction items on STATE ROUTE 0024, SECTION 024, from Segment 0454/0110 to Segment 0470/0500 and from Segment 0455/0000 to Segment 0471/0500. DBE 1%, Anticipated Notice to Proceed 11-13-17, Required Completion 12-31-18.

MONROE COUNTY – SR 4008(01B) #102216

PROPOSAL:\$17.04 PLANS:\$11.22 12X18:\$13.77 24X36:\$198.90 X-SEC:\$2.42 12X18:\$2.97 24X36:\$42.90 The description and location of the project is as follows: Replacement of the bridge carrying SR 4008 over Tobyhanna Creek on the same alignment. Work includes, demolition of the existing 2-span stone masonry closed spandrel deck arch structure, construction of a single span pre-stressed spread box beam structure on integral abutments, construction of roadway approaches, drainage and other miscellaneous construction, road detour and pedestrian detour as indicated on the approved drawings included in the bid package for STATE ROUTE 4008, SECTION 01B, in MONROE COUNTY, Coolbaugh TOWNSHIP from approximately 125 feet east of existing bridge at segment 0030 offset 1816 to approximately 350 feet west of the existing structure at segment 0030 offset 1216 for an overall project length of 475.00 linear feet (0.090 mile). DBE 5%, Anticipated Notice to Proceed 11-13-17, Required Completion 11-20-18.

MERCER COUNTY – SR 18(S02) #106595

PROPOSAL:\$16.68 PLANS:\$1.32 12X18:\$1.62 24X36:\$23.40 For the construction or improvement of signalized intersection on STATE HIGHWAY in MERCER COUNTY, PYMATUNING TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 0018, SECTION S02. The project being situated as follows: From approximately 0.73 miles north of the intersection with SR. 3022 at Segment 0410 Offset 1147 (Station 1162+00.00) then north to approximately 1.05 miles south of the intersection with SR. 4012 at Segment 0420 Offset 0262 (Station 1167+50.00). For the improvement of traffic signal equipment including electrical service, wiring, signal equipment, signing, and pavement markings all within a project length of 450.00 feet (0.084 miles) as indicated on the approved drawings. DBE 2%, Anticipated Notice to Proceed 11-13-17, Required Completion 6-1-18.

LEBANON COUNTY – SR 422(027) #94936

PROPOSAL:\$20.52 PLANS:\$24.64 12X18:\$30.24 24X36:\$436.80 This safety corridor project extends along SR 0422 (Lincoln Avenue) from 500 feet west of of SR 0645 (North Locust Street) to T-644(Martin Road). The project consists of signalized intersection improvements of at three intersections including SR 0645 (N. Locust Street), SR 0501(N. College Street) and (Dutchway Drive). Work includes adding geometric changes to SR 0501 and N. Railroad Street intersections including widening for additional lanes, mountable median installation, milling and overlay, sidewalk & ADA improvements, and minor drainage. Corridor wide other improvements include curbing for access management, signs and pavement markings, guide rail upgrades, and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 0422, SECTION 027, in LEBANON COUNTY, JACKSON TOWNSHIP and MYERSTOWN BOROUGH, from Segment 0330 Offset 1802 to Segment 0370 Offset 1365, for an overall project length of 9037.00 linear feet (1.712 miles). DBE 6%, Anticipated Notice to Proceed 11-13-17, Required Completion 10-23-18.

BERKS COUNTY – SR 7203(01B) #103136

PROPOSAL:\$19.56 PLANS:\$10.56 12X18:\$12.96 24X36:\$187.20 X-SEC:\$1.98 12X18:\$2.43 24X36:\$35.10
EXSTRUCT:\$1.32 12X18:\$1.62 24X36:\$23.40 The description and location of the project is as follows: the replace the existing superstructure (deck and beams), approach work, guide rail, signing, pavement markings and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 7203 (Blackburn Road, T-469), SECTION 01B, in Berks COUNTY Amity TOWNSHIP from approximately 0.9 miles from the intersection with SR 0662 at Station 20+65 to approximately 0.5 miles from the intersection of SR 562 at Station 29+45. DBE 5%, Anticipated Notice to Proceed 11-13-17, Required Completion 10-3-18.

ALLEGHENY COUNTY – SR 2084(A02) #92939

PROPOSAL:\$19.32 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00 X-SEC:\$7.48 12X18:\$9.18 24X36:\$132.60 The description and location of the project is as follows: For the slide remediation, bituminous pavement, drainage, guide rail, pavement marking, and other miscellaneous construction, all within a length of 1,382.0 linear feet (0.262 miles) as indicated on the approved drawings included in the bid package for STATE ROUTE 2084, SECTION A02 (Milltown Road), in ALLEGHENY COUNTY, PLUM BOROUGH, Commonwealth of Pennsylvania. This project being situated as follows: From a point approximately 400 feet east of Mill Street at Segment 0014 Offset 0380 (Station 11+25) to a point approximately 550 feet west of Deerlake Road at Segment 0020 Offset 1760 (Station 51+00). Anticipated Notice to Proceed 11-13-17, Required Completion 7-17-18.

MONROE COUNTY – SR 2006(DFB) #106329

PROPOSAL:\$17.28 PLANS:\$3.74 12X18:\$4.59 24X36:\$66.30 The description and location of the project is as follows: REPLACEMENT OF BOX CULVERT and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 2006, SECTION DFB, in MONROE COUNTY SMITHFIELD TOWNSHIP from approximately STA 276+6 at segment 110 offset 2700 to approximately STA 276+73 at segment 120 offset 0036. This is a department force project. Anticipated Notice to Proceed 11-13-17, Required Completion 6-18-18.

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
ECMS ADVANCED INFORMATION – LETTING SEPTEMBER 28, 2017
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

SULLIVAN COUNTY – SR 1002(016) #94803

PROPOSAL:\$14.40 PLANS:\$4.18 12X18:\$5.13 24X36:\$74.10 The description and location of the project are as follows: The work is the furnishing and installation of a 18'-0" x 7'-0" precast reinforced concrete box culvert over Pigeon Creek at a Department-prepared site with an overall length of 384.10 linear feet (0.073 mile) as indicated on the approved drawings included in the bid package for STATE ROUTE 1002, SECTION 016 and Township Road T-826 (Dutch Mountain Road) from approximately 8.1 miles north of the intersection with State Route 487 at Station 453+78.19 to approximately 4.4 miles southeast of the intersection with State Route 87 at Station 459+62.59 in COLLEY TOWNSHIP, SULLIVAN COUNTY. Anticipated Notice to Proceed 11-13-17, Required Completion 7-27-18.
