

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 3, 2022
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 01.26.22

BERKS COUNTY – SR 0422(BOB) #114391

PROPOSAL:\$24.00 PLANS:\$9.24 12X18:\$11.34 24X36:\$163.80 Ex St:\$6.60 12x18:\$8.10 24x36:\$117.00

This project consists of bridge repairs of various structure types, including but not limited to overlay, concrete deck repairs, concrete beam and substructure repairs, joint repairs/joint sealing, along with other miscellaneous construction as indicated on the attached details included in the Bid Package for State Routes 422, 737, 3067, 4011, and 4047 in Albany, Exeter, Muhlenberg, and Upper Bern Townships in Berks County.

ELK COUNTY – SR 555(0) #108980

**PROPOSAL:\$11.88 PLANS:\$22.88 12X18:\$28.08 24X36:\$405.60 X-SEC:\$18.04 12X18:\$22.14
24X36:\$319.80**

The description and location of the project is as follows: For the improvements to a certain section of LOCAL ROADWAY in ELK COUNTY, BENEZETTE TOWNSHIP, Commonwealth of Pennsylvania, T-520 Winslow Hill Road. The project being situated as follows: On Winslow Hill Road T-520, from approximately the bottom of Winslow Hill to the top of the hill past the PA State Game Land Elk Viewing Center near the intersection with Dewey Road. For roadway safety improvements including resurfacing, minor widening, improving shoulders, guiderail, drainage improvements and other miscellaneous construction, as indicated on the approved drawings included in the bid package.

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 3, 2022
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 01.07.22

PHILADELPHIA COUNTY – SR 95(CP3) #80014 – Moved 12/16/21 to 1/13 to 2/3/22

**PROPOSAL:\$217.92 PLANS:\$130.24 12X18:\$159.84 24X36:\$2,308.80 X-SEC:\$53.02 12X18:\$65.07
24X36:\$939.90 Ex St:\$179.08 12x18:\$219.78 24x36:\$3,174.60**

The description and location of the project is as follows: This project is for the reconstruction of SR 95 and SR 0073 (New State Road) for an approximate total length of 1.4 miles. Included is the construction of one (1) retaining wall, construction of four (4) sign structures, relocation of approximately 700 LF of sanitary sewer box culvert, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 95, SECTION CP3, in the CITY OF PHILADELPHIA and PHILADELPHIA COUNTY.

BRADFORD COUNTY – SR 0000(LBR) #57557

PROPOSAL:\$30.12 PLANS:\$11.00 12X18:\$13.50 24X36:\$195.00 X-SEC:\$1.76 12X18:\$2.16 24X36:\$31.20

Removal of existing bridge over Wallace Run, construction of a 48” x 21” one-span prestressed concrete spread box beam bridge or an approved equal, selected borrow excavation rock, base and wearing courses, guide rail, and other related work within an overall length of 450.00 linear feet (0.085 mile) as indicated on approved drawings for TOWNSHIP ROAD T-553 (Covered Bridge Road) from approximately 0.2 mile east of the intersection with State Route 6 at Station 11+50.00 to approximately 3.4 miles southwest of the intersection with State Route 4001 at Station 17+00.00 BURLINGTON TOWNSHIP, BRADFORD COUNTY.

BEDFORD COUNTY – SR 31(01B) #21562

PROPOSAL:\$17.28 PLANS:\$11.44 12X18:\$14.04 24X36:\$202.80 Ex St:\$1.76 12x18:\$2.16 24x36:\$31.20

This project is for the rehabilitation of the existing 4-Span Composite R.C. T-Beam/Adjacent Box Beam Bridge carrying the Raystown Branch of the Juniata River on SR 0031 in Bedford County. Bridge work includes removal of asphalt pavement on bridge deck, removal of deteriorated concrete, new reinforced concrete deck overlay, barrier encasement/replacement, superstructure and substructure repairs. Roadway work includes minor roadway approaches and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0031, SECTION 01B, in BEDFORD COUNTY, HARRISON and NAPIER TOWNSHIPS.

LUZERNE COUNTY – SR 3007(D50) #67409

PROPOSAL:\$11.04 PLANS:\$9.90 12X18:\$12.15 24X36:\$175.50 X-SEC:\$2.20 12X18:\$2.70 24X36:\$39.00

For the improvement of certain section of highways and bridges in LUZERNE COUNTY, SLOCUM TOWNSHIP, COMMONWEALTH OF PENNSYLVANIA, STATE ROUTE 3007, SECTION D50. The proposed project involves the replacement of the existing structure carrying S.R. 3007 (Blue Ridge Trail) Section D50 over Little Wapwallopen Creek in Slocum Township, Luzerne County. As currently proposed the replacement efforts for this project will consist of online replacement of the existing bridge structure. The horizontal geometry will match the existing horizontal geometry while the vertical geometry will closely match the existing profile of the roadway. The existing structure consists of a reinforced concrete box culvert with concrete wingwalls beneath fill and a bituminous overlay, which will be replaced with a 12' 0" x 9' 6" cast-in-place concrete box culvert with cast-in-place concrete wingwalls. The approach roadway work includes roadway widths to taper back from being full-width at the culvert locations to the existing widths at the project tie-ins. Guiderail updates will include replacement of the guiderails throughout the entire length of the project and new signage will be installed. To restore the toe slope of the roadway and to minimize wetland impacts the slopes of the roadway will be rock lined at approximately the same location. Maintenance and protection of traffic during project construction is to consist of a planned detour. All work contained within an overall length of 605 linear feet (0.115 miles) as indicated on the approved drawings included in the bid package.

ALLEGHENY COUNTY – SR 51(13A) #109357

PROPOSAL:\$22.56 PLANS:\$5.06 12X18:\$6.21 24X36:\$89.70

The description and location of the project is as follows: This is a partial Design Build roadway project. Design activities are limited to: Concrete curb ramps and utility coordination. For the base replacement, asphalt pavement patching, curb and sidewalk, detectable warning surface, traffic signals, signing and pavement marking, and other miscellaneous construction, all within a length of 3,062 linear feet (0.580 miles), as indicated on the approved drawings included in the bid package for the 2022 ADA CURB RAMP PROJECT, in ALLEGHENY, BEAVER and LAWRENCE COUNTIES, VARIOUS MUNICIPALITIES, Commonwealth of Pennsylvania. This project being situated as follows: At various locations throughout Allegheny, Beaver and Lawrence Counties.

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 3, 2022
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 01.05.22

FRANKLIN COUNTY – SR 3011(008) #100163

PROPOSAL:\$46.92 PLANS:\$9.02 12X18:\$11.07 24X36:\$159.90 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30

This project consists of culvert replacement under detour and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 3011, SECTION 008, in FRANKLIN COUNTY PETERS TOWNSHIP from approximately east of Buchanan Trail at segment 0020 offset 0363 to segment 0020 offset 0733.

FRANKLIN COUNTY – SR 2026(DFP) #109332

PROPOSAL:\$12.00 PLANS:\$4.84 12X18:\$5.94 24X36:\$85.80

Department Force culvert replacement and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 2026, SECTION DFP, in FRANKLIN COUNTY, GUILFORD TOWNSHIP, on Loop Road from Segment 0020 Offset 1983 to Segment 0030 Offset 0156.

GREENE COUNTY – SR 19(SIP) #116406

PROPOSAL:\$6.96 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20

Surface improvement contract of certain sections of various State Routes in Greene County. Construction consists of milling, asphalt courses, base repair, pavement markings, and other miscellaneous construction on all or portions of the selected State Routes, all as indicated on the approved drawings for various State Routes in Greene County.

LUZERNE COUNTY – SR 309(366) #67366

PROPOSAL:\$46.68 PLANS:\$18.04 12X18:\$22.14 24X36:\$319.80 X-SEC:\$1.32 12X18:\$1.62 24X36:\$23.40

Ex St:\$39.38 12x18:\$48.33 24x36:\$698.10

For the improvement of certain section of highways and bridges in LUZERNE COUNTY, WILKES BARRE CITY AND PLAINS TOWNSHIP, COMMONWEALTH OF PENNSYLVANIA, STATE ROUTE 0309, SECTION 366. Bridge preservation repairs to a 11-span mixed adjacent spread box beam bridge carrying State Route 309 (North Cross Valley Expressway) over State Route 2022, Mill Creek and Norfolk Southern Railway in the City of Wilkes-Barre, Luzerne County. Superstructure repairs will consist of scarifying of the existing concrete deck, performing Type 3 deck repairs and placing 1" Polyester Polymer Concrete overlay, replacing existing neoprene strip seal gland and sealing open joints in parapets. Substructure repairs include concrete repairs to the abutments and piers. Maintenance and Protection of Traffic will be 2 phase construction maintaining 2 lanes of traffic at all times. Approach roadway will be milled and paved.

LUZERNE COUNTY – SR 1012(371) #68966

PROPOSAL:\$14.16 PLANS:\$11.88 12X18:\$14.58 24X36:\$210.60 X-SEC:\$2.86 12X18:\$3.51 24X36:\$50.70

For the construction of a certain section of STATE HIGHWAY in Luzerne County, Jackson Township, Commonwealth of Pennsylvania, STATE ROUTE 1012, SECTION 371. The project being situated as follows: From a point on SR 1012 (Chase Road) at Segment 0010 Offset 2035 (Station 9+51) to a point approximately 523 feet along SR 1012 at Segment 0010 Offset 2759 (Station 16+74). This project is the replacement of an existing stone masonry arch culvert with a concrete encased steel I-beam slab extension with a 10' span. The proposed replacement structure is a precast reinforced concrete arch culvert on the existing alignment with a 28' span. The project also includes full depth pavement replacement, milling and resurfacing, drainage, guide rail, and other miscellaneous construction. Traffic control will be maintained under a 11.2 mile detour.

YORK COUNTY – SR 2002(019) #91359

PROPOSAL:\$16.08 PLANS:\$8.36 12X18:\$10.26 24X36:\$148.20 X-SEC:\$1.98 12X18:\$2.43 24X36:\$35.10

This project consists of replacing a single-span steel stringer structure with a precast box culvert over an unnamed tributary to Mill Creek, minor approach work, and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 2002, SECTION 019, in YORK COUNTY, YORK TOWNSHIP, from Segment 0080 Offset 0385 to Segment 0080 Offset 0970.

LYCOMING COUNTY – SR 54(110) #115027

PROPOSAL:\$6.00 PLANS 8.5x11:\$2.52

Micro-surfacing and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 54, SECTION 110, in LYCOMING COUNTY, MONTGOMERY BOROUGH from approximately 800 feet south of the intersection with School House Road at segment 0070 offset 0807 to the intersection with West Houston Ave at segment 0090 offset 0612, and for STATE ROUTE 2016, SECTION 024, in LYCOMING COUNTY, CITY OF WILLIAMSPORT and LOYALSOCK TOWNSHIP from approximately 100 feet east of the intersection with Grove Street at segment 0120 offset 1263 to the intersection with SR 2014 at segment 0150 offset 1557, and for STATE ROUTE 2026, SECTION 005, in LYCOMING COUNTY, MONTTOURSVILLE BOROUGH from the intersection with SR 2043 at segment 0010 offset 0000 to the Montoursville Borough line at segment 0020 offset 0100.

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS
ECMS ADVANCED INFORMATION – LETTING FEBRUARY 3, 2022
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

LYCOMING COUNTY – SR 0000(LBR) #110203

PROPOSAL:\$27.00 PLANS:\$10.12 12X18:\$12.42 24X36:\$179.40 X-SEC:\$1.32 12X18:\$1.62 24X36:\$23.40

Bridge replacement, roadway, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for T-556, SECTION LBR, in LYCOMING COUNTY, UPPER FAIRFIELD TOWNSHIP from approximately 85 feet north of the intersection of SR 864 and T-556 to approximately 1.0 miles south of the intersection of SR 2032 and T-556.

CLEARFIELD COUNTY – SR 36(RAR) #116541

PROPOSAL:\$9.36 PLANS:\$1.54 12X18:\$1.89 24X36:\$27.30

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAY in CLEARFIELD COUNTY, VARIOUS BOROUGH AND TOWNSHIPS, Commonwealth of Pennsylvania, Group 2-22-RAR2. For the repair or replacement of guide rail, median barrier, bridge railing, right-of-way fence, and appurtenances damaged by traffic and for new guide rail installation for safety updates on various state routes in CLEARFIELD COUNTY.

CAMERON COUNTY – SR 46(RAR) #116542

PROPOSAL:\$11.40 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAY in POTTER AND CAMERON COUNTY, VARIOUS BOROUGH AND TOWNSHIPS, Commonwealth of Pennsylvania, Group 2-22-RAR3. For the repair or replacement of guide rail, median barrier, bridge railing, right-of-way fence, and appurtenances damaged by traffic and for new guide rail installation for safety updates on various state routes in POTTER AND CAMERON COUNTY.

ELK COUNTY – SR 66(RAR) #116544

PROPOSAL:\$11.64 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAY in MCKEAN AND ELK COUNTY, VARIOUS BOROUGH AND TOWNSHIPS, Commonwealth of Pennsylvania, Group 2-22-RAR5. For the repair or replacement of guide rail, median barrier, bridge railing, right-of-way fence, and appurtenances damaged by traffic and for new guide rail installation for safety updates on various state routes in MCKEAN AND ELK COUNTY.

INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION