

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 17, 2022**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 02.01.22

**JEFFERSON COUNTY – SR 80(54F) #106224**

**PROPOSAL:\$22.20 PLANS:\$21.34 12X18:\$26.19 24X36:\$378.30**

This is a resurfacing project of Interstate 80 to include milling, patching, binder, leveling and wearing courses, bridge preservation work that includes an epoxy overlay and repair of bridge deck and approaches and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 80, SECTION 54F, in JEFFERSON COUNTY ROSE and PINE CREEK TOWNSHIPS and BROOKVILLE BOROUGH from approximately 8.4 miles east of Clarion at segment 0720 offset 2180 to approximately 14.7 miles west of Falls Creek at segment 0834 offset 2049. Also associated with this project is a bridge preservation that includes an epoxy overlay and repair of bridge approaches as indicated on the approved drawings included in the bid package for STATE ROUTE 80, SECTION 301, in CLARION COUNTY RICHLAND, BEAVER, PAINT and MONROE TOWNSHIPS and VENANGO COUNTY SCRUBGRASS TOWNSHIP from approximately 2.3 miles east of the Venango/Butler County line at segment 0460 offset 0998 to 0.82 miles east of the SR 66 north interchange at segment 0610 offset 0137.

---

**ALLEGHENY COUNTY – SR 3027(A05) #28525**

**PROPOSAL:\$35.64 PLANS:\$39.92 12X18:\$48.87 24X36:\$705.90**

The description and location of the project is as follows: For the Bridge preservation activities include replacement of orthotropic sidewalks on Lenticular Truss Spans 3 and 4, structural steel repairs and spot paint, bearing repair and replacement, concrete repairs and deck epoxy overlay. The project also includes overhead lane control system upgrades, new pedestrian push button controllers and other miscellaneous construction, all as indicated on the approved drawings for STATE ROUTE 3027, SECTION A05, in Allegheny COUNTY, CITY of Pittsburgh, Commonwealth of Pennsylvania. The Project being situated as follows: From the Carson Street intersection with Smithfield Street at segment 0010 offset 0013 to immediate north of the Fort Pitt Boulevard intersection with Smithfield Street at segment 0010 offset 0256.

---

**NORTHUMBERLAND COUNTY – SR 4010(009) #106285**

**PROPOSAL:\$21.48 PLANS:\$5.06 12X18:\$6.21 24X36:\$89.70**

The description and location of the project are as follows: For resurfacing and design and construct of ADA curb ramps including base repairs, milling, Superpave Asphalt Mixture Design scratch and wearing courses, pavement markings, and other miscellaneous construction within an overall length of 3,340.00 linear feet (0.63 miles) all as indicated on the approved drawings included in the bid package for STATE ROUTE 4010, SECTION 009 from approximately 0.34 miles southeast of the intersection with SR 147 at Segment 0020 Offset 0010 and approximately 0.00 miles northwest of the intersection with State Route 4012 at Segment 0030 Offset 1599 in the CITY OF SUNBURY, NORTHUMBERLAND COUNTY and STATE ROUTE 147, SECTION 119 from approximately 0.76 miles northeast of the intersection with SR 147 and Yeagers Hill Road (T-407) at Segment 0090 Offset 2575 and approximately 0.14 miles southwest of the intersection with SR 147 and Toad Valley Road (T- 337) at Segment 0120 Offset 0630 in LOWER MAHANoy TOWNSHIP, NORTHUMBERLAND COUNTY

---

**ALLEGHENY COUNTY – SR 0000(---) #109514**

**PROPOSAL:\$15.96 PLANS:\$7.04 12X18:\$8.64 24X36:\$124.80**

The description and location of the project is as follows: For the installation of various safety improvements including pavement markings, rumble strips and other miscellaneous construction, as indicated on the approved drawings included in the bid package for SAFETY LCSIP 2020, ALLEGHENY, BEAVER, and LAWRENCE COUNTIES, VARIOUS MUNICIPALITIES, Commonwealth of Pennsylvania. This project being situated as follows: At various high crash locations in Allegheny, Beaver, and Lawrence Counties.

---

**POTTER COUNTY – SR 449(A07) #105915 – *Withdrawn 1/25, Re-added 1/27/22***

**PROPOSAL:\$12.60 PLANS:\$8.36 12X18:\$10.26 24X36:\$148.20 X-SEC:\$2.64 12X18:\$3.24 24X36:\$46.80**

The description and location of the project is as follows: For the improvement of a certain section of STATE HIGHWAY in POTTER COUNTY, ULYSSES TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 449, SECTION A07. The project being situated as follows: On State Route 449 from Segment 0120/Offset 1341 to Segment 0130/Offset 0356. For the removal of the existing Reinforced Concrete Arch Culvert and construction of its replacement a Precast Reinforced Concrete Box Culvert. Construction of approach work including Superpave Asphalt Mixture Designs for the base, binder and wearing courses, pavement base drain, guide rail, pavement markings, and miscellaneous construction for a total construction length of approximately 525 feet (0.099 mile) as indicated on the approved drawings included in the bid package.

---

**ALLEGHENY COUNTY – SR 0000(---) #109518**

**PROPOSAL:\$21.72 PLANS:\$1.98 12X18:\$2.43 24X36:\$35.10**

The description and location of the project is as follows: Installation of raised pavement markers and replacement of existing lenses and other miscellaneous construction for various STATE ROUTES in ALLEGHENY, BEAVER, AND LAWRENCE COUNTIES, VARIOUS MUNICIPALITIES, Commonwealth of Pennsylvania.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 17, 2022  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 01.21.22

**JEFFERSON COUNTY – SR 36(506) #99607**

**PROPOSAL:\$9.24 PLANS:\$5.72 12X18:\$7.02 24X36:\$101.40**

This is a highway maintenance project on SR 0036 that includes milling of the existing bituminous surface and adding leveling, binder and wearing courses and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0036, SECTION 506, in JEFFERSON COUNTY, OLIVER, BEAVER and ROSE TOWNSHIPS and BROOKVILLE BOROUGH from approximately 2.17 miles north of intersection of SR 0036 and SR 3031 at segment 0530 offset 2081 to the intersection of SR 0036 and SR 0322 at segment 0700 offset 1398.

---

**LACKAWANNA COUNTY – SR 6(D04) #61813**

**PROPOSAL:\$16.32 PLANS:\$58.52 12X18:\$71.82 24X36:\$1,037.40 Ex St:\$111.76 12x18:\$137.16 24x36:\$1,981.20**

This is a Concrete Pavement and Bridge Structure Preservation Project. This project will address the aging concrete roadway pavement by replacing damaged and broken slabs where necessary while retrofitting existing slabs to give them stability, replace damaged or missing pavement joints and the final surface will be diamond ground to make the most of ride quality. The same preservation activities will be applied to all ramp legs along the length of the highway. The bridge structures along the mainline and interchange ramps will receive preventative maintenance work to increase the service life and prevent future deterioration.

---

**FAYETTE COUNTY – SR 21(B10) #79306**

**PROPOSAL:\$23.88 PLANS:\$52.80 12X18:\$64.80 24X36:\$936.00 X-SEC:\$13.86 12X18:\$17.01  
24X36:\$245.70 Ex St:\$2.42 12x18:\$2.97 24x36:\$42.90**

The description and location of the project is as follows: The scope of work consists of the replacement of the existing structure carrying PA 21 (Roy E. Furman Highway) over PA 166 including approach roadway along SR 0021. In addition, SR 0166 will be reconstructed (lower the vertical grade) beginning at the SR 0166/ SR 8021 (Ramp B) intersection and ending at the SR 0166/SR 8021 (Ramp E) intersection. In addition, upgrades to the drainage including the installation of a stormwater management facility, signing & pavement marking and guide rail. Several detours will be implemented for the SR 0166 roadway improvements and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0021, SECTION B10, in FAYETTE COUNTY MASON TOWN BOROUGH & GERMAN TOWNSHIP. The project begins SR 21/SR 8021 (Ramp A & E) intersection (segment 0050/1440 & segment 0051/1415) and ends at the SR 21/SR 8021 (Ramp 1 & 2) intersection (segment 0060/0000 & segment 0061/0000).

---

**POTTER COUNTY – SR 449(A07) #105915**

**PROPOSAL:\$12.60 PLANS:\$8.36 12X18:\$10.26 24X36:\$148.20 X-SEC:\$2.64 12X18:\$3.24 24X36:\$46.80**

The description and location of the project is as follows: For the improvement of a certain section of STATE HIGHWAY in POTTER COUNTY, ULYSSES TOWNSHIP, Commonwealth of Pennsylvania, STATE ROUTE 449, SECTION A07. The project being situated as follows: On State Route 449 from Segment 0120/Offset 1341 to Segment 0130/Offset 0356. For the removal of the existing Reinforced Concrete Arch Culvert and construction of its replacement a Precast Reinforced Concrete Box Culvert. Construction of approach work including Superpave Asphalt Mixture Designs for the base, binder and wearing courses, pavement base drain, guide rail, pavement markings, and miscellaneous construction for a total construction length of approximately 525 feet (0.099 mile) as indicated on the approved drawings included in the bid package.

---

**MERCER COUNTY – SR 62(STU) #111622**

**PROPOSAL:\$12.84 PLANS:\$6.16 12X18:\$7.56 24X36:\$109.20**

For the construction of intersection improvements including asphalt paving, traffic signals, concrete curb, drainage, guide rail, pavement markings and landscaping, as indicated on the approved drawings included in the bid package for STATE ROUTE 62 Section STU, in Mercer COUNTY, City of Sharon, from approximately 70 feet south of the intersection with Addison Avenue at Segment 0010 Offset 0000 to approximately 350 east of the intersection with South Irvine Avenue at Segment 0020 Offset 0428.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN  
SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 17, 2022  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 01.18.22

**CAMBRIA COUNTY – SR 271(019) #106513**

**PROPOSAL:\$30.96 PLANS:\$25.74 12X18:\$31.59 24X36:\$456.30 X-SEC:\$2.86 12X18:\$3.51 24X36:\$50.70**

This project is for the pavement preservation of approximately 9.251 miles of SR 0271 in Cambria County. Work includes milling and resurfacing, drainage improvements, guide rail upgrades, signing and pavement markings, tree trimming, traffic signal upgrades, slip lining of 42" pipe, slide correction, design and construct ADA curb ramps and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0271, SECTION 019, in CAMBRIA COUNTY, EAST CONEMAUGH, FRANKLIN, SOUTHMONT & WESTMONT BOROUGH, EAST TAYLOR & UPPER YODER TOWNSHIPS and CITY OF JOHNSTOWN at the locations indicated on the plans in the bid package.

---

**CLEARFIELD COUNTY – SR 453(ST2) #108731**

**PROPOSAL:\$20.40 PLANS:\$4.40 12X18:\$5.40 24X36:\$78.00**

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAYS in CLEARFIELD, ELK and CAMERON COUNTIES, VARIOUS TOWNSHIPS and BOROUGHES, Commonwealth of Pennsylvania, Group 2-21-ST2. For the improvement to 15 State Routes having a combined construction length of approximately 348,478 linear feet (65.9 miles), involving various combinations of milling, various Superpave Asphalt Mixture Designs for binder and wearing courses, including pavement designs using recycled shingles, concrete curbing, sidewalks including detectable warning surfaces, various pavement markings, and miscellaneous construction as indicated on the approved drawings.

---

**FRANKLIN COUNTY – SR 16(TAP) #111394**

**PROPOSAL:\$12.24 PLANS:\$2.64 12X18:\$3.24 24X36:\$46.80**

This project consists of constructing street lighting on PA 16 (Main Street) between Broad Street and Franklin Street, Walnut Street between 2nd and 3rd Street, PA 16 and Clayton Avenue intersection, and other miscellaneous items, all as indicated on the approved drawings included within the Bid Package for STATE ROUTE 0016, SECTION TAP, in FRANKLIN COUNTY, BOROUGH OF WAYNESBORO.

---

**VENANGO COUNTY – SR 4022(V21) #116438**

**PROPOSAL:\$7.32 PLANS 8.5x11:\$2.52**

Asphalt binder overlay, base repair, guiderail, shoulder backup, seal coat, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 4022, in Venango COUNTY Plum TOWNSHIP from the intersection with SR 428 then East 6.1 miles to the intersection with SR 8.

---

**BERKS COUNTY – SR 222(31M) #110007**

**PROPOSAL:\$61.20 PLANS:\$21.78 12X18:\$26.73 24X36:\$386.10 Ex St:\$26.40 12x18:\$32.40 24x36:\$468.00**

Concrete patching, microsurfacing, bridge preventative maintenance and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 222, SECTION 31M, in the Berks COUNTY Borough of Wyomissing Reading Boulevard from approximately Reading Boulevard at segment 0142 offset 0000 to approximately State Hill Road at segment 0172 offset 2573.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 17, 2022  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 01.14.22

**UNION COUNTY – SR 304(017) #98895**

**PROPOSAL:\$11.88 PLANS 8.5X11:\$2.52**

Microsurfacing, epoxy overlay, strip seal gland replacement, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 304, SECTION 017, in UNION COUNTY, LIMESTONE TOWNSHIP from approximately 0.46 miles southeast of the intersection of SR 304 and SR 45 at segment 0020 offset 1450 to approximately 7.02 miles west of the intersection of SR 304 and SR 15 at segment 0150 offset 0100 and STATE ROUTE 3007, SECTION 019, in UNION COUNTY, WEST BUFFALO TOWNSHIP from approximately the intersection of SR 3007 and SR 45 at segment 0010 offset 0000 to approximately The intersection of SR 3007 and SR 192 at segment 0090 offset 2356 .

---

**BUTLER COUNTY – SR 488(250) #98730**

**PROPOSAL:\$21.72 PLANS:\$42.02 12X18:\$51.57 24X36:\$744.90 X-SEC:\$5.94 12X18:\$7.29 24X36:\$105.30**

Replacement of the existing structure carrying PA 488 (East Portersville Road) over Interstate 79 northbound and southbound with a 2 span composite steel multi girder bridge and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 488, SECTION 250, in Butler COUNTY Muddy Creek TOWNSHIP from approximately .5 miles east of Portersville at segment 0050 offset 1792 to approximately 3.4 miles west of SR 3025 at segment 0070 offset 0046.

---

**CLARION COUNTY – SR 66(311) #100175**

**PROPOSAL:\$9.12 PLANS:\$3.30 12X18:\$4.05 24X36:\$58.50**

This is a highway improvement project along SR 66 that includes milling of the existing bituminous wearing course, bituminous patching and paving and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0066, SECTION 311, in CLARION COUNTY KNOX and FARMINGTON TOWNSHIPS from approximately 2.9 miles north of the town of Arthurs at segment 0520 offset 2519 to approximately 2.2 miles south of the town of Crown at segment 0660 offset 0050.

---

**McKEAN COUNTY – SR 3011(ST5) #108832**

**PROPOSAL:\$12.72 PLANS:\$5.28 12X18:\$6.48 24X36:\$93.60**

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAYS in McKean and Potter COUNTIES, VARIOUS TOWNSHIPS and BOROUGHs, Commonwealth of Pennsylvania, Group 2-22-ST5. For the improvement to 13 State Routes having a combined construction length of approximately 336,608 linear feet (63.7 miles), involving various combinations of milling, scratch and resurfacing, using various Superpave Asphalt Mixture Designs for binder and wearing courses, various pavement markings and legends, and miscellaneous construction as indicated on the approved drawings.

---

**FAYETTE COUNTY – SR 119(17M) #115920**

**PROPOSAL:\$8.16 PLANS:\$6.16 12X18:\$7.56 24X36:\$109.20**

The scope of this job is replacing worn and leaking seals as well as other various repairs including approach slabs, concrete repairs, and other miscellaneous construction as indicated on the approved drawings included in the bid package for STATE ROUTE 0119, SECTION 17M, in FAYETTE COUNTY SOUTH UNION TOWNSHIP and ten additional locations, to extend the life of the structures.

---

**ERIE COUNTY – SR 3014(B02) #116539**

**PROPOSAL:\$10.08 PLANS:\$2.64 12X18:\$3.24 24X36:\$46.80 Ex St:\$6.16 12x18:\$7.56 24x36:\$109.20**

For painting of existing structural steel and site restoration, as indicated on the approved drawings included in the bid package for STATE ROUTE 3014 SECTION B02, in Erie COUNTY Franklin TOWNSHIP at the I-79 overpass from approximately Segment 0170 Offset 0932 to approximately Segment 0180 Offset 2060.

---

**CRAWFORD COUNTY – SR 1010(C21) #116431**

**PROPOSAL:\$9.12 PLANS 8.5X11:\$3.60**

Asphalt binder overlay, guiderail, seal coat, pavement markings and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 1010 and 2029, in Crawford COUNTY, in Richmond and Oil Creek townships, and Hydetown Borough. This project being situated as follows: SR 1010 from the intersection with SR 77 then East 3.79 miles to the intersection with SR 408 and SR 2029 from the intersection with SR27 then North to the intersection with SR 408.

---

**ERIE COUNTY – SR 1009(E21) #116436**

**PROPOSAL:\$9.12 PLANS 8.5X11:\$1.80**

Asphalt binder overlay, guiderail, seal coat, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 1009, in Erie COUNTY from the intersection with SR 8 in Venango Township then North 4.45 miles to the intersection with SR 430 in Harborcreek Township.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING FEBRUARY 17, 2022  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 01.13.22

**ALLEGHENY COUNTY – SR 0000(LOC) #105603**

**PROPOSAL:\$32.28 PLANS:\$31.90 12X18:\$39.15 24X36:\$565.50 X-SEC:\$8.14 12X18:\$9.99  
24X36:\$144.30**

The description of the project is as follows: This is a partial Design Build roadway project. Design activities are limited to: Concrete Curb Ramps and a Radio Communication System. For the signals, milling and resurfacing, concrete pavement rehabilitation, drainage, signing and pavement markings, and other miscellaneous construction, all within a length of 2,405.00 linear feet (0.456 miles) as indicated on the approved drawings included in the bid package for SOUTH SIDE SIGNALS (South Eighteenth Street) in the CITY OF PITTSBURGH and MOUNT OLIVER BOROUGH, in ALLEGHENY COUNTY, Commonwealth of Pennsylvania. This project being situated as follows: From a point approximately 340 feet south of Carson Street (SR 837) at the intersection of South 18th Street with Sarah Street (Station 417+88) to a point approximately 4,315 feet to the east of Saw Mill Run Boulevard (SR 51) to the intersection of Brownsville Road, Bausman Street, Hays Avenue, and Amanda Street (Station 9+18).

---

**BEDFORD COUNTY – SR 0000(---) #116138**

**PROPOSAL:\$7.68 PLANS:\$7.48 12X18:\$9.18 24X36:\$132.60**

This project is for the application of painted pavement markings at various locations on STATE HIGHWAYS in BEDFORD, BLAIR, CAMBRIA, FULTON, HUNTINGDON and SOMERSET COUNTIES, VARIOUS TOWNSHIPS AND MUNICIPALITIES, Commonwealth of Pennsylvania, all as indicated on the approved drawings included in the bid package.

---

**BEDFORD COUNTY – SR 913(008) #110499**

**PROPOSAL:\$18.24 PLANS:\$3.96 12X18:\$4.86 24X36:\$70.20**

This project is for the pavement preservation of approximately 2.35 miles of SR 0913 in Bedford County. Work includes milling and resurfacing, guiderail, drainage, pavement markings, signing upgrades, design and construction of curb ramps and other miscellaneous construction as indicated on the approved drawings included in the bid package for STATE ROUTE 0913, SECTION 0008, in BEDFORD COUNTY, LIBERTY TOWNSHIP, SAXTON BOROUGH at the locations indicated in the bid package.

---

**LYCOMING COUNTY – SR 2014(109) #114257**

**PROPOSAL:\$32.64 PLANS:\$6.82 12X18:\$8.37 24X36:\$120.90**

Milling and resurfacing of existing roadway, including base repairs, Superpave binder, wearing, and scratch courses, bridge deck repairs, strip seal glands, guide rail, rumble strips, design and construction of ADA curb ramps, and other miscellaneous construction as indicated on approved drawings for STATE ROUTE 2014, SECTION 109 approximately 2.3 miles east of the intersection with State Route 2045 at Segment 0360 Offset 1115 to approximately 0.6 mile west of the intersection with State Route 2036 at Segment 0390 Offset 0366, and for STATE ROUTE 2014, SECTION 113 from approximately 1.9 miles southwest of the intersection with State Route 2036 at Segment 0440 Offset 1990 to approximately 0.3 mile north of the intersection with State Route 405 at Segment 0460 Offset 1701, and for STATE ROUTE 2053, SECTION 003 from the intersection with Industrial Park Road at Segment 0004 Offset 0000 to the intersection with State Route 2014 at Segment 0350 Offset 0350, and for STATE ROUTE 2049, SECTION 003 from the intersection with State Route 2014 at Segment 0010 Offset 0000 to approximately 0.3 miles south of the intersection with State Route 8018 (I-180 Ramp A Road) and Lycoming Mall North Entrance Road at Segment 0010 Offset 1000 in MUNCY, FAIRFIELD and MUNCY CREEK TOWNSHIPS, LYCOMING COUNTY.

---

**DAUPHIN COUNTY – SR 0000(---) #116231**

**PROPOSAL:\$4.20 PLANS:\$4.18 12X18:\$5.13 24X36:\$74.10**

For the furnishing and application of white and yellow waterborne pavement markings along various state highways within Engineering District 8-0, various municipalities, Commonwealth of Pennsylvania, all within an overall project length of 5,657,551.00 linear feet (1,071.51 miles) as indicated on the approved drawings included in the Bid Package.

---

**DAUPHIN COUNTY – SR 0000(---) #116232**

**PROPOSAL:\$4.08 PLANS:\$3.08 12X18:\$3.78 24X36:\$54.60**

For the placement/replacement of raised pavement markers (RPMs) and/or pavement marker reflectors along various state highways in Cumberland, Dauphin, Franklin, and Lebanon Counties, Commonwealth of Pennsylvania, within an overall length of 1,661,731.00 linear feet (314.72 miles) as indicated on the approved drawings included in the Bid Package.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
ECMS ADVANCED INFORMATION – LETTING FEBRUARY 17, 2022  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**CENTRE COUNTY – SR 26(RAR) #116540**

**PROPOSAL:\$11.88 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20**

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAY in CENTRE AND CLINTON COUNTY, VARIOUS BOROUGHES AND TOWNSHIPS, Commonwealth of Pennsylvania, Group 2-22-RAR1. For the repair or replacement of guide rail, median barrier, bridge railing, right-of-way fence, and appurtenances damaged by traffic and for new guide rail installation for safety updates on various state routes in CENTRE AND CLINTON COUNTY.

---

**JUNIATA COUNTY – SR 11(RAR) #116543**

**PROPOSAL:\$12.96 PLANS:\$1.76 12X18:\$2.16 24X36:\$31.20**

The description and location of the project is as follows: For the improvement of certain sections of STATE HIGHWAY in JUNIATA AND MIFFLIN COUNTY, VARIOUS BOROUGHES AND TOWNSHIPS, Commonwealth of Pennsylvania, Group 2-22-RAR4. For the repair or replacement of guide rail, median barrier, bridge railing, right-of-way fence, and appurtenances damaged by traffic and for new guide rail installation for safety updates on various state routes in JUNIATA AND MIFFLIN COUNTY.

---

**WESTMORELAND COUNTY – SR 0000(LCT) #111416**

**PROPOSAL:\$24.24 PLANS:\$9.02 12X18:\$11.07 24X36:\$159.90**

The project will be the new construction of segments 5 & 6 of the Loyalhanna Creek Trail. The existing land will now be converted into a multi-use trail providing public recreation for pedestrians and bicyclists. The work will include drainage, trail surfacing, trail landscaping, signage and other miscellaneous construction, as indicated on the approved drawings included in the bid package for Loyalhanna Creek Trail Segments 5 & 6, Section LCT, in Westmoreland County Derry Township from New Alexandria Borough to Keystone State Park.

---

**GREENE COUNTY – SR 3001(X10) #89086**

**PROPOSAL:\$9.60 PLANS:\$16.72 12X18:\$20.52 24X36:\$296.40 X-SEC:\$1.54 12X18:\$1.89 24X36:\$27.30**

The project consists of the replacement of the existing structure carrying SR 3001 over Crabapple Creek with a prestressed concrete spread box beam bridge and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 3001, SECTION X10, in GREENE COUNTY RICHHILL TOWNSHIP from approximately 200 feet south of the intersection of SR 4002 at segment 0410 offset 2977 to approximately segment 0420 offset 0043.

---

**LYCOMING COUNTY – SR 2039(09S) #112979**

**PROPOSAL:\$24.36 PLANS:\$11.66 12X18:\$14.31 24X36:\$206.70 X-SEC:\$20.90 12X18:\$25.65 24X36:\$370.50**

The description and location of the project is as follows: This work is performing slide repairs and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 2039, SECTION 09S, in LYCOMING COUNTY LOYALSOCK and ELDRED TOWNSHIPS from approximately 2.3 miles south of the intersection with SR 973 at segment 0100 offset 0342 to approximately 3.3 miles north of the intersection with SR 2014 at segment 0090 offset 0138.

---

**BLAIR COUNTY – SR 4015(01B) #22088**

**PROPOSAL:\$34.56 PLANS:\$24.42 12X18:\$29.97 24X36:\$432.90 X-SEC:\$6.16 12X18:\$7.56 24X36:\$109.20**

This project is for the removal and replacement of two existing structures on SR's 4013 & 4015 in Blair County. The existing Single Span Steel I-Beam Bridge which carries SR 4013 over Homers Gap Run will be replaced with Single Span Composite Prestressed Concrete Spread Box Beam Bridge. The existing Reinforced T-Beam Bridge which carries SR 4015 over Spring Run will be replaced with a 23'-0" x 8'-0" Precast Reinforced Concrete Box Culvert. The proposed work is for the replacement of both structures including roadway approach work, drainage, guide rail upgrades, waterline relocation on SR 4015 and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 4015, SECTION 01B, in BLAIR COUNTY, LOGAN TOWNSHIP, CITY OF ALTOONA at the locations indicated on the plans in the bid package.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**