

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING JANUARY 12, 2023  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated January 5, 2023

**WAYNE COUNTY – SR 670(650) #88469**

For the improvement of a certain section of STATE ROUTE 670, Sec 650 in WAYNE COUNTY, MOUNT PLEASANT TOWNSHIP. The location of the project is as follows: From a point approximately 0.73 miles from the intersection with SR 4017 (Egypt Road) at Segment 0170 Offset 0354 along SR 0670 (Bethany Turnpike), Mount Pleasant Township, Wayne County to a point near the intersection with SR 0247 (Creamton Drive) at Segment 0200 Offset 0000 along SR 0670 (Bethany Turnpike), Mount Pleasant Township, Wayne County, with a total work area length of 576.16 feet (0.109 miles). The SR 670 Sec 650 bridge replacement project includes a replacement of the existing corrugated steel pipe culvert with a proposed 9'-0" x 8'-6" precast concrete box culvert over Cramer Creek. Other work includes excavation, full depth bituminous paving bridge approach, new guiderail, drainage, E & S control measures, detour signing, temporary fencing, driveway adjustment, permanent signing, pavement markings, landscaping and other miscellaneous construction work.

---

**BEAVER COUNTY – SR 4018(B04) #108502**

The description and location of the project is as follows: For the milling, resurfacing, shoulder repair, base repair, drainage, guide rail, pavement marking, and other miscellaneous construction, all within a length of 36,237 linear feet (6.86 miles) as indicated on the approved drawings included in the bid package for BEAVER GROUP 112-23-7135-1 in BEAVER COUNTY, BEAVER BOROUGH, AND BRIGHTON TOWNSHIP, Commonwealth of Pennsylvania. This project being situated as follows: SR 4018, Section B04 (Park Road-Dutch Ridge Road-Market Street) – From SR 4012 (Bradys Run Road) at Segment 0010 Offset 0000 (Station 1+00) to SR 0068 (Third Street) at Segment 0080 Offset 1471 (Station 218+04). SR 4020, Section B02 (Dutch Ridge Road) – From SR 4028 (Tuscarawas Road) at Segment 0010 Offset 0000 (Station 1+00) to SR 4018 (Park Road) at Segment 0050 Offset 2606 (Station 149+32). Various State Routes and Facilities throughout Beaver County for unforeseen repair and/or resurfacing, as directed.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING JANUARY 12, 2023  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated December 21, 2022

**BLAIR COUNTY – SR 1013(01B) #117760**

This bridge preservation project is for work on 6 structures at various locations in Blair County. Preservation work on the structures on SR 1013 (Pemberton Road) over the Little Juniata River in Tyrone Township and SR 4102 (Carlisle Lane) over I-99 in Logan Township consists of the placement of latex modified concrete overlay and strip seal expansion dam replacement. Roadway work consists of minor roadway approach paving, maintenance of existing drainage features and guide rail upgrades. Minor work on the SR 3010 structure over Poplar Run include epoxy overlay and cleaning drainage structures. Minor work on the SR 3010 structure over Blue Knob Run include epoxy overlay, cleaning drainage structures and minor tree trimming. Work on SR 0022 EB and WB consists of elastomeric concrete repair and silicone sealing of the bridge joint expansion dams. All work to be completed as indicated on the approved drawings included in the bid package for STATE ROUTE 1013, SECTION 01B, in BLAIR COUNTY, TYRONE TOWNSHIP at the locations indicated on the plans in the bid package.

---

**BUCKS COUNTY – SR 332(MTF) #116258**

Roadway widening along Yardley-Newtown Road (SR 0332) to add an additional through lane in the westbound direction and a dual-left turn lane onto Stony Hill Road (SR 2069), roadway widening along the I-295 Westbound Off Ramp (SR 8011) to provide a dual-right turn lane and a left turn lane onto Yardley-Newtown Road (SR 0332), installation of a new concrete median, drainage improvements, traffic signal improvements at two (2) intersections, installation of fiber optic cable, guide rail, overhead sign structures and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0332, SECTION MTF, in BUCKS COUNTY, LOWER MAKEFIELD TOWNSHIP from approximately the intersection of Lindenhurst/Campus Drive at segment 0270 offset 0274 to approximately the intersection of the I-295 Westbound Off Ramp (SR 8011) at segment 0271 offset 3367.

---

**MERCER COUNTY – SR 2002(B01) #58081**

This project consists of removal of the existing structure, construction a single span integral abutment bridge and reconstruction of the approach roadway and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 2002, in Mercer COUNTY Springfield TOWNSHIP from approximately segment 70 offset 0 to approximately segment 80 offset 0.

---

**SCHUYLKILL COUNTY – SR 7233(ZRB) #110329**

Rehabilitation of a National Register listed single span timber covered bridge (County Bridge No. 114) carrying Covered Bridge Road (T-526) over Lower Little Swatara Creek and other miscellaneous construction, as indicated on the approved drawings included in the bid package for SR 7233, Section ZRB, in Schuylkill County, Washington Township from station 2+30.00 to 8+00.00.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING JANUARY 12, 2023  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**Updated December 14, 2022**

**CRAWFORD COUNTY – SR 2034(B00) #78780**

This project is the construction of approximately 0.15 mile from SR 2034/Segment 0020/Offset 0917 to SR 2034/Segment 0030/Offset 0070, including partial removal of an existing structure, repair and rehabilitation of existing structure over Interstate 79, approach roadway improvements including paving with Superpave asphalt mixtures, guiderail, and delineators as indicated on the approved drawings included in the Bid Package.

---

**ERIE COUNTY – SR 4104(B00) #97229**

This project includes bridge rehabilitation, patching, milling, paving, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 4104, in Erie COUNTY Mckean TOWNSHIP from approximately segment 0010 offset 0000 to approximately segment 10 offset 0256 and for STATE ROUTE 4107, in Erie COUNTY MillCreek TOWNSHIP from approximately segment 0010 offset 0000 to approximately segment 0010 offset 0214.

---

**WAYNE COUNTY – SR 2008(670) #9833**

For the improvement of a certain section of STATE ROUTE 2008, Sec 670 in Wayne COUNTY, Honesdale Borough. The location of the project is as follows: From a point approximately 1 mile North from the intersection with SR 0006 (US Route 6) along SR 1001 to the intersection with Louie Drive at Segment 7010 Offset 0000 (STA 10+00) to (SR 2008 – Seg 0012 Off 0000 to Seg 0012 Off 0066, Carley Brook Bridge) to Segment 7014 Offset 0368 (STA 18+36), with a total work area length of 726 feet (0.138 miles). The project consists of the replacement of an existing state-owned structure, SR 2008, located on the municipal road Louie Drive, carrying traffic over Carley Brook with roadway improvements to the shoulders and the installation of guide rail. The existing single-lane 29' long encased I-beam structure will be replaced with a spread box beam structure on integral abutments. The proposed structure and approach roadway will adhere to PennDOT Publication 13M, Design Manual Part 2, Table 1.7, which will be comprised of two (2) – 9'-0" to 11'-0" travel lanes and 2'-0" to 4'-0" shoulders. The proposed horizontal alignment will mostly match the existing condition which meets a 25 MPH design speed for a posted speed limit of 25 MPH. The approach horizontal curve will need to be modified to accommodate the new approach slab for the replacement structure. The vertical geometry will be realigned to meet current design criteria. Other work includes excavation, full depth bituminous paving bridge approach, E & S control measures, temporary traffic signal, temporary bridge/ run-around road, permanent signing, pavement markings, landscaping and other miscellaneous construction work.

---

**CRAWFORD COUNTY – SR 0000(---) #118466**

This project is the maintenance and repair of existing guide rail, cable median barrier, right-of-way fencing, delineators, and impact attenuators at various locations in Crawford, Erie, Mercer, and Venango Counties, as indicated in the Bid Package.

---

**MONROE COUNTY – SR 4003(DFB) #85851**

This project is for replacement of a box culvert and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 4003, SECTION DFB, in MONROE COUNTY TOBYHANNA TOWNSHIP from approximately STA 355+8.03 at segment 0010 offset 0841 to approximately STA 356+09.98 at segment 0010 offset 0853.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING JANUARY 12, 2023  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**Updated December 9, 2022**

**LACKAWANNA COUNTY – SR 4036(D50) #100499**

For the improvement of a certain section of STATE ROUTE 4036, Sec D50 in LACKAWANNA COUNTY, NEWTON TOWNSHIP. The location of the project is as follows: From a point approximately 0.07 miles from the Wyoming County Line at Segment 0010 Offset 0000 along SR 4036 (Falls Road), Newton Township, Lackawanna County to a point near the intersection with SR 4027 (Airport Drive) at Segment 0060 Offset 0000 along SR 4036 (Falls Road), Newton Township, Lackawanna County, with a total work area length of 352.00 feet (0.067 miles). The SR 4036 Sec D50 culvert replacement project includes the removal of the existing corrugated metal pipe culvert that carries SR 4036 (Falls Road) over the Unnamed Tributary to Falls Creek and replacing it with a precast reinforced concrete box culvert with precast wingwalls at the upstream and downstream ends. Other work includes excavation, full depth bituminous paving bridge approaches, new guiderail, drainage, E & S control measures, detour signing, driveway adjustment, permanent signing, pavement markings, landscaping and other miscellaneous construction work.

---

**LYCOMING COUNTY – SR 0000(66E) #111625**

The description and location of the project are as follows: Miller’s Run Greenway Trail, Phase 2. Construction of a shared use trail including selected borrow excavation rock, milling, Superpave Asphalt Mixture Design base and wearing courses, drainage, guide rail upgrades, sidewalks, ADA curb ramps, pavement markings, and other miscellaneous construction from approximately 390 feet south of East Third Street on the east side of Northway Road to the west side of the existing levee and East Third Street, in LOYALSOCK TOWNSHIP, LYCOMING COUNTY.

---

**YORK COUNTY – SR 1033(008) #112548**

This project involves adding an additional span to the existing 3-lane, 2-span Continuous Composite Steel Girder Bridge on Sherman Street (SR 1033) over I-83 and Mill Creek and replacing the county-owned bridge on Eberts Lane (T-854) with a 2-lane, 2-span P/S Concrete PA Bulb Tee Beam bridge. This project also consists of approach work, guide rail updates, pavement marking updates, and other miscellaneous construction, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 1033, SECTION 008, in YORK COUNTY, CITY OF YORK and SPRINGETTSBURY & SPRING GARDEN TOWNSHIPS, from Segment 0020 Offset 1605 to Segment 0020 Offset 2401, for an overall project length of 596.00 linear feet (0.113 mile).

---

**INDIANA COUNTY – SR 422(467) #25548**

This project consists of the bridge rehabilitation which includes the deck replacement, bearing replacement and painting of the steel of the existing structures carrying US 422 eastbound and westbound over Two Lick Creek and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE US 0422, SECTION 467, in Indiana COUNTY White TOWNSHIP from approximately 0.25 mile East of SR0119 at segment 0224 offset 0975 of the EB Structure and segment 0301 offset 0340 of the WB structure to segment 0310 offset 1387 of the EB structure and segment 0321 offset 0108 of the WB structure.

---

**WESTMORELAND COUNTY – SR 119(U20) #76105**

This project consists of the replacement of the bridge that carries S.R. 0119 (New Alexandria Road) over a branch of Crabtree Creek. Also included will be roadway approach work, drainage upgrades, guide rail upgrades, signing and pavement marking upgrades, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0119, SECTION U20, in Westmoreland COUNTY Hempfield Township from approximately six hundred(600) feet north of the intersection of S.R. 0119(New Alexandria Road) and S.R. 1055(Hannastown Road) at segment 0410 offset 0821 to segment 0410 offset 1417.

---

**PERRY COUNTY – SR 3007(018) #100425**

This project consists of two separate bridge projects. SR 3007-018 is a bridge replacement project with construction consisting of minor roadway reconstruction, guiderail improvements, and other miscellaneous construction. SR 3011-009 is a bridge rehabilitation project with construction consisting of beam and deck replacement, minor roadway reconstruction, pier and abutment repairs, and other miscellaneous construction activities, all as indicated on the approved drawings included in the Bid Package for STATE ROUTE 3007, SECTION 018, in PERRY COUNTY, NORTHEAST MADISON TOWNSHIP, from Segment 0050 Offset 1902 to Segment 0050 Offset 2356, for a project length of 399 linear feet (0.076 mile), also STATE ROUTE 3011, SECTION 009 in PERRY COUNTY, TYRONE TOWNSHIP, from Segment 0030 Offset 0000 to Segment 0030 Offset 0159, for a project length of 159 linear feet (0.030 mile), overall project length of 558 linear feet (0.106 mile).

---

**ERIE COUNTY – SR 699(B03) #110080**

Removal and replacement of existing structure over tributary to Walnut Creek including milling, paving, drainage, guiderail, line painting, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 699, in Erie COUNTY Summit TOWNSHIP from approximately segment 0360 offset 0007 to approximately segment 0360 offset 0482.

---

**MONTGOMERY COUNTY – SR 152(LPM) #111492**

The installation of drainage and sidewalk and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0152, SECTION LPM, in MONTGOMERY COUNTY, UPPER DUBLIN TOWNSHIP from approximately Dreshertown Road at segment 0100 offset 0540 to approximately Jarrettown Elementary School at segment 0110 offset 1210. Design-Build activities are limited to ADA curb ramp designs.

---

**VENANGO COUNTY – SR 0000(---) #118468**

This project is the maintenance and repair of existing highway lighting at various locations in Crawford, Erie, Mercer, and Venango Counties, as indicated in the Bid Package.

---

**LACKAWANNA COUNTY – SR 435(250) #97930**

For the rehabilitation and improvement of a certain section of STATE HIGHWAY in LACKAWANNA COUNTY, Scott Township, Roaring Brook Township, Commonwealth of Pennsylvania, STATE ROUTE 0435, SECTION 250. The proposed project includes the replacement of the existing bridge carrying S.R. 0435 over Interstate 84. The existing bridges are two-span steel plate girders with reinforced concrete abutments/pier perched on rock. The proposed replacement bridges will be two-span prestressed concrete PA Bulb Tee beams using similar substructures and foundations. Full depth roadway reconstruction will extend approximately 50 feet from each end of the bridge. New guide rail, pavement markings, and signing will also be installed. The proposed project will also include the removal of an existing structure mounted sign that is currently located on the existing S.R. 0435 bridge and a new monopipe frame sign structure will be constructed. During construction, SR 0435 traffic will be controlled by using single lane bi-directional crossovers, which will allow each bound to be reconstructed full width. Jug Handle Road will remain open throughout construction. Temporary long-term lane shifts on I-84 (protected by temporary barrier) will be necessary to construct the bridge replacement. Temporary single lane closures on I-84 are also expected to construct the new sign structure. Temporary traffic patterns will have speed reductions through the work zone but will not have any weight or width restrictions. All work with a total project length of 2713 linear feet (0.514 miles), all as indicated on the approved drawings included in the bid package.

---

**ALLEGHENY COUNTY – SR 50(0) #100382**

The description of the project is as follows: For the signal upgrading including controllers, controller upgrading and retiming, signal cables, electrical service, pedestrian push buttons and signal heads, signing and pavement markings, and other miscellaneous construction, all within a length of 20,431.00 linear feet (3.870 miles) as indicated on the approved drawings included in the bid package for the SINC-UP PROJECT in ALLEGHENY, BEAVER AND LAWRENCE COUNTIES, Commonwealth of Pennsylvania. This project being situated as follows: At the various locations throughout Allegheny, Beaver and Lawrence Counties.

---

**DELAWARE COUNTY – SR 0000(PT2) #110777**

The description and location of the project is as follows: Installation of a 10ft wide asphalt shared-use trail along former railroad bed, installation of steel truss bridge over Manoa Road with associated abutments, installation of retaining walls, curbs and sidewalk, stormwater management basin, expansion of municipal parking lot, and other miscellaneous construction, as indicated on the approved drawings included in the bid package for PENNSY TRAIL, SECTION PSY, in DELAWARE COUNTY, HAVERTOWN TOWNSHIP from approximately STA. 12+25 to approximately STA. 34+50.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS**  
**SUPPLEMENTAL ECMS ADVANCED INFORMATION – LETTING JANUARY 12, 2023**  
**(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

Updated 12.08.22

**LUZERNE COUNTY – SR 309(355) #93006**

For the improvement of a certain section of STATE ROUTE 0309, Sec 355 in Luzerne COUNTY, Butler TOWNSHIP. The location of the project is as follows: From a point approximately 1 ¼ miles North from the intersection with SR 3022 at Segments 0260/ 0261 Offsets 0229 to a point approximately one (1) mile South from the intersection with SR 0080 (I-80) at Segment 0270/ 0271 Offsets 0059 along SR 0309 (North Hunter Highway), with a total work area length of 2,791 feet (0.529 miles). The project involves the replacement of the existing S.R. 0309 bridge over Nescopeck Creek. The existing bridge is a two-span rolled steel multi-girder bridge built in 1956 and is open to traffic with no weight restrictions. The project will replace the two-span structure with a single-span prestressed concrete structure and will also include reconstructing the approach roadway surface and upgrading existing drainage features. The project will be staged construction maintaining one lane of traffic in each direction throughout the construction period. Other work includes excavation, Pile structure foundation, temporary excavation support & protection, drainage, new guiderail, concrete curbing, E & S control measures, temporary traffic control, temporary fencing, permanent signing, pavement markings, landscaping and other miscellaneous construction work.

---

**FAYETTE COUNTY – SR 0000(BMR) #96657**

The description and location of the project is as follows: Widening and resurfacing and other miscellaneous construction, as indicated on the approved drawings included in the bid package for TOWNSHIP ROAD T 311, SECTION BMR, in FAYETTE COUNTY, HENRY CLAY TOWNSHIP from approximately the township municipal line to the PA/WVA state line.

---

**BRADFORD COUNTY – SR 4031(009) #99309**

The description and location of the project are as follows: This work is the furnishing and installation of a 12'-0" x 7'-0" precast reinforced concrete box culvert, inlet section, and outlet section over tributary to Beckwith Creek and selective tree removal at a Department prepared site all within a length of 293.00 linear feet (0.055 miles) all as indicated on the approved drawings included in the bid package for STATE ROUTE 4031, SECTION 009 from approximately 0.5 miles north of the intersection with State Route 4038 at Segment 0140 Offset 2464 to approximately 0.8 miles south of the intersection with State Route 4034 at Segment 0150 Offset 0167 in WELLS TOWNSHIP, BRADFORD COUNTY.

---

**WARREN COUNTY – SR 3022(WPB) #74711**

This project is the construction of approximately 0.26 mile from SR 3022/Segment 0030/Offset 1849 to SR 3022/Segment 0040/Offset 0275, SR 0006/Segment 0780/Offset 1109 to SR 0006/Segment 0780/Offset 1422, SR 0062/Segment 0410/Offset 0763 to SR 0062/Segment 0410/Offset 1027, SR 8004/Segment 0502/Offset 1541 to SR 8004/Segment 0502/Offset 1436, SR 8004/Segment 0512/Offset 0000 to SR 8004/Segment 0512/Offset 0105, SR 0426/Segment 0250/Offset 1546 to SR 0426/Segment 0250/Offset 1225, SR 3010/Segment 0120/Offset 1265 to SR 3010/Segment 0120/Offset 1621, SR 4007/Segment 0100/Offset 2272 to SR 4007/Segment 0100/Offset 2578, SR 1003/Segment 0110/Offset 0692 to SR 1003/Segment 0110/Offset 1007, SR 1003/Segment 0110/Offset 2731 to SR 1003/Segment 0110/Offset 3104, and SR 2005/Segment 0070/Offset 3073 to SR 2005/Segment 0080/Offset 0186 including epoxy based surface treatment for bridge deck, pavement markings and other miscellaneous construction, as indicated on the approved drawings included in the bid package.

---

**CRAWFORD COUNTY – SR 618(B01) #90153**

This project is the design and construction of approximately 0.1 miles from SR 0618/Segment 0040/Offset 2329 to SR 0618/Segment 0050/Offset 0473, including replacement of existing structure over an unnamed stream, paving of approach roadway with Superpave Asphalt Mixtures, drainage, guiderail, sidewalk, ADA ramps, signing, delineators, and pavement markings, as indicated on the approved drawings included in the Bid Package.

---

**BUTLER COUNTY – SR 68(290) #106568**

Signal replacement, installation of turn lanes, and corridor improvements to enhance safety and reduce congestion and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0068, SECTION 290, in Butler COUNTY Butler and Connoquenessing TOWNSHIPS from approximately just east of Stevenson Road (T-425) at segment 0320 offset 0633 to approximately the intersection of Meridian Road/Benbrook Road (SR 3007) at segment 0360 offset 2343.

---

**SOMERSET COUNTY – SR 403(015) #113442**

This project is for the pavement preservation of approximately 6.447 miles of SR 0403 in Somerset County. Work includes milling and resurfacing, guide rail & drainage upgrades, signing and pavement markings, curbing and sidewalks, tree trimming and removal, traffic signal upgrades. Structure work consists of two Box Culvert replacements, one Anchored Soldier Pile Retaining Wall, three RC Arch Culvert bridge preservations and one RC Slab Bridge preservation and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 0403, SECTION 015, in SOMERSET COUNTY, SHADE, QUEMAHONING & CONEMAUGH TOWNSHIPS, HOOVERVILLE BOROUGH at the locations indicated on the plans in the bid package.

---

**WYOMING COUNTY – SR 6(FP6) #114028**

This project is for the resurfacing of approximately 2.19 miles of existing roadway on STATE ROUTE 6, MESHOPPEN TOWNSHIP, WYOMING COUNTY, in the COMMONWEALTH OF PENNSYLVANIA with Superpave Asphalt Mixture Design - binder and wearing courses, milling, guide rail, pavement markings, line painting, and other miscellaneous construction at the following locations: SR 6 Segment 0150 Offset 0000 to Segment 0170 Offset 1893 SR 6 Segment 0190 Offset 0000 to Segment 0220 Offset 1868

---

**PIKE COUNTY – SR 6(FP5) #114071**

This project is for the repair/resurfacing of approximately 7.76 miles of existing roadway on STATE ROUTE 6 in PIKE COUNTY, VARIOUS MUNICIPALITIES, in the COMMONWEALTH OF PENNSYLVANIA with Superpave Asphalt Mixture Design, wearing and scratch courses, milling, mechanized edge repair, base repair, guide rail, pavement markings, line painting and other miscellaneous construction. The limits of the project are as follows: SR 6 - Segment 0030 Offset 0000 to Segment 0100 Offset 3070. SR 6 - Segment 0160 Offset 0000 to Segment 0220 Offset 3268.

---

**LUZERNE COUNTY – SR 309(P57) #115729**

For the rehabilitation and improvement of a certain section of STATE HIGHWAY in LACKAWANNA & LUZERNE COUNTIES, Scott Township, Blakely Borough and Salem & Wright Townships, Commonwealth of Pennsylvania, STATE ROUTE 0309, SECTION P57. The project being situated as follows: SR 0347 Sec P71 Segment 0144 Offset 3104 to Segment 0150 Offset 0368 in Lackawanna County SR 0347 Sec P72 Segment 0180 Offset 1427 to Segment 0180 Offset 2263 in Lackawanna County SR 0309 Sec P57 Segment 0380 Offset 1894 to Segment 0390 Offset 0472 in Luzerne County SR 4037 Sec P63 Station 176+00 to Station 183+10 in Luzerne County This Bridge Preservation project consists of the repairs of Two (2) bridges in Lackawanna County and Two (2) bridges in Luzerne County. Work includes (but is not limited to) excavation, asphalt paving, pavement markings, rock protection & structure backfill, guiderail repairs, partial bridge & culvert removal, concrete bridge repairs. Additional work includes Unforeseen Bridge Repairs, temporary traffic control and other miscellaneous work as indicated on the approved drawings included in the bid package.

---

**VENANGO COUNTY – SR 8(S02) #117993**

This project is the construction of approximately 1.19 miles from SR 0008/Segment 0580/Offset 0868 to SR 0008/Segment 0590/Offset 0828, SR 0417/Segment 0030/Offset 0055 to SR 0417/Segment 0040/Offset 0300, and SR 3025/Segment 0110/Offset 0082 to SR 3025/Segment 0120/Offset 0075 including application of a high friction surface treatment, base repairs, and pavement markings as indicated on the approved drawings included in the Bid Package.

---

**CHESTER COUNTY – SR 23(IDA) #118309 – *Moved 12/15/22 To 1/12/23***

This project involves repairing severe repairs, because of Hurricane Ida in September 2021, at various locations in in Chester and Montgomery County in Pennsylvania.

---

**WASHINGTON COUNTY – SR 79(234) #118679**

The description and location of the project is as follows, Maintenance of highway lighting in Fayette, Greene, Washington and Westmoreland counties.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**

**ASSOCIATED PENNSYLVANIA CONSTRUCTORS  
ECMS ADVANCED INFORMATION – LETTING JANUARY 12, 2023  
(ALL WORK TO BE COMPLETED TO APPEAR IN THE PROPOSAL)**

**LEHIGH COUNTY – SR 329(01B) #11413**

Replacement of the Cementon Bridge over the Lehigh River and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 329, SECTION 01B, in Whitehall Township, Lehigh County and Northampton Borough, Northampton County from approximately Second Street at segment 0130 offset 0026 to approximately Center Street at segment 0010 offset 0517.

---

**LYCOMING COUNTY – SR 15(220) #114045**

The description and location of the project are as follows: For resurfacing, design and construct of ADA curb ramps, base and joint repairs, milling, Superpave Asphalt Mixture Design wearing and scratch courses, guide rail upgrades, and other miscellaneous construction as indicated on the approved drawings included in the bid package for STATE ROUTE 15, SECTION 220 and STATE ROUTE 9417, SECTION 015, in South Williamsport Borough and Armstrong Township, from 5.0 miles north of the intersection with SR 54 at Segment 0200 Offset 1541 to approximately 0.3 miles south of the intersection with SR 2012 at Segment 0265 Offset 500, and STATE ROUTE 2012, SECTION 015, in South Williamsport Borough, from the intersection with SR 15 Southbound at Segment at Segment 0010 Offset 0021 to the intersection with SR 15 Northbound at Segment 0010 Offset 0296, all in LYCOMING County.

---

**NORTHAMPTON COUNTY – SR 3016(01B) #12310**

Replacement of a 2-span steel stringer bridge carrying Indian Trail Road (SR 3016) over Hokendauqua Creek with a prestressed concrete spread box beam bridge and other miscellaneous construction, as indicated on the approved drawings included in the bid package for STATE ROUTE 3016, SECTION 01B, in NORTHAMPTON COUNTY, ALLEN TOWNSHIP from approximately segment 0020 offset 3159 to approximately segment 0030 offset 0331.

---



**SOMERSET COUNTY – SR 30(018) #110443**

This project is for the pavement preservation of approximately 4.345 miles of SR 0030 in Somerset County. Work includes milling and resurfacing, guiderail, drainage, tree trimming and removal, signing and pavement markings and also includes intersection improvements on SR 1001 and other miscellaneous construction as indicated on the approved drawings included in the bid package for STATE ROUTE 0030, SECTION 018, in SOMERSET COUNTY, QUEMAHONING & SOMERSET TOWNSHIPS, STOYSTOWN BOROUGH at the locations indicated in the bid package.

---

**CAMBRIA COUNTY – SR 56(38T) #117233**

This project is for the replacement of antiquated signal equipment at 15 intersections in the City of Johnstown in Cambria County. Work includes replacing controllers, signal heads, wire and detection and includes signing and pavement markings and other miscellaneous construction as indicated on the approved drawings included in the bid package.

---

**SOMERSET COUNTY – SR 2010(003) #118717**

This work is for the pavement rehabilitation (pavement patching) on SR's 2010, 2013 & 2015 in Somerset County. All work to be constructed as indicated on the approved drawings included in the bid package for STATE ROUTE 2010, SECTION 003, in SOMERSET COUNTY, VARIOUS TOWNSHIPS.

---

**ALLEGHENY COUNTY – SR 2048(A14) #27225**

The description and location of the project is as follows: For the structure widening and preservation, milling and resurfacing, base repairs, curbing, sidewalk, drainage, guide rail, signing, pavement markings, structure and other miscellaneous construction, all within a length of 21,848 linear feet (4.14 miles) as indicated on the approved drawings for STATE ROUTE 2048, SECTION A14, in ALLEGHENY COUNTY, WILKINS TOWNSHIP, CHURCHILL BOROUGH, AND MUNICIPALITY OF MONROEVILLE, Commonwealth of Pennsylvania. From approximately 100 feet west of the intersection of SR 2048 and Huntingdon Drive Segment 0011 Offset 550 (Sta. 11+45) Ramp A, Segment 0010 Offset 0690 (Sta. 12+45) Ramp B, to approximately 1,400 feet east of the intersection of SR 2048 with Moss Side Boulevard and SR 2047 at Segment 0110 Offset 1331 (Sta. 363+65).

---

**WESTMORELAND COUNTY – SR 2025(G10) #89043**

The scope of work consists of the replacement of the structure carrying SR 2025 (Ankney Hill Road) over Welty Run. In addition, the approach roadway will be reconstructed approximately 100 feet on each side of the structure as well as updating the drainage, guide rail and signing and pavement marking as indicated on the approved drawings included in the bid package for STATE ROUTE 2025, SECTION G10, in WESTMORELAND COUNTY MOUNT TOWNSHIP. The project is located 2610 feet of the SR 0982 (Welty Rd)/SR 2025 (Ankney Hill Rd) intersection segment 0110/0998.

---

**NORTHAMPTON COUNTY – SR 33(05B) #96431**

The project involves the replacement of the existing single span SR 33 NB and SB structures over Bushkill Creek. and other miscellaneous construction details, as indicated on the approved drawings and included in the bid package for STATE ROUTE 33, SECTION 05B, in NORTHAMPTON COUNTY in PALMER TOWNSHIP AND STOCKERTOWN BOROUGH from approximately SR 1002 (Main St) at segment 0110 NB/ 0111 SB offset 1609/ 1574 to approximately SR 191 (Industrial Blvd) at segment 0120 NB/ 0131 SB offset 2587/ 0069.

---

**INFO. ON SPECIFIC QUANTITIES IS AVAILABLE WITH AN APC SPECIAL SERVICE BULLETIN SUBSCRIPTION**