

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online and diskette bids will be received until 11:00 A.M., Local Time, on November 4, 2009. Diskette bids will be received by the Contract Management Services Manager for the Pennsylvania Turnpike Commission, at the Administration Building, Ground Address: 700 South Eisenhower Boulevard, Middletown, Pennsylvania 17057 (Mailing Address: P.O. Box 67676, Harrisburg, Pennsylvania 17106-7676). Bids will be publicly opened for the following Contract:

CONTRACT NO. T-025.00R001-03-02 - BITUMINOUS RESURFACING BETWEEN MILEPOST 24.90 AND MILEPOST 30.80 AND ACCESS RAMP CONSTRUCTION AT MILEPOST 15.9 W.B. IN BEAVER, BUTLER AND ALLEGHENY COUNTIES, PENNSYLVANIA

This contract provides for resurfacing of the Turnpike roadway. Work will be accomplished by milling and paving the Turnpike roadway with superpave wearing and binder courses, and replacing Sonic Nap Alert Patterns and Snowplowable Raised Pavement Markers. Work will also include guide rail and end treatment update, repairing inlets and wide area elimination.

This contract also provides for access ramp construction at Milepost 15.9 WB, and milling and paving of ramps, acceleration lanes, and deceleration lanes at the Cranberry Interchange, Exit 28.

12,520	CY	Excavation, Class 1, 1A, 1B, and 2 Excavation
239,144	SY	Milling of Existing Bituminous Pavement, Various Depths
2,257	TONS	Subbase (No. 2A)
25,374	TONS	Superpave Asphalt Mixture Design, HMA Wearing Course, Various Mixes
40,209	TONS	Superpave Asphalt Mixture Design, HMA Binder Course
5,320	LF	Removing Existing Guide Rail
6,773	LF	Guide Rail, Type 2-S and Type 2-SC
17	EACH	Vehicle Attenuating Terminal End Treatment (VATET), Type II and Type III and Type 2-S Approach End Transitions
24	EACH	Inlets and Endwalls
4,943	LF	Bituminous Concrete Curb
502	LF	Concrete Barrier, Safety Walls, and Abutment Transition Pieces
54,952	EACH	Sonic Nap Alert Pattern (SNAP)
853	EACH	Snowplowable Raised Pavement Markers (SRPM)

The resurfacing project is located between Milepost 24.90, approximately 3.5 miles west of Cranberry Interchange, Exit 28, and Milepost 30.80, approximately 2 miles east of Cranberry Interchange, Exit 28 in Butler and Allegheny Counties, Pennsylvania.

The access ramp construction is located at Milepost 15.9 westbound, approximately 3.0 miles east of Beaver Valley Interchange, Exit 13 in Beaver County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Direct any questions for this project to Charles J Buchanan, P.E., telephone 717-939-9551 Ext. 5785, fax 717-986-8707 or electronic mail: cbuchana@paturndpike.com

PENNSYLVANNIA TURNPIKE COMMISSION

J. William Lincoln
Secretary-Treasurer

Harrisburg, Pennsylvania
September 2009