

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online and diskette bids will be received until 11:00, Local Time, on February 10, 2010. Diskette bids will be received by the Contract Management Services Manager for the Pennsylvania Turnpike Commission, at the Administration Building, Ground Address: 700 South Eisenhower Boulevard, Middletown, Pennsylvania 17057 (Mailing Address: P.O. Box 67676, Harrisburg, Pennsylvania 17106-7676). Bids will be publicly opened for the following Contract:

CONTRACT NO. T-048.00R001-3-02 –BITUMINOUS RESURFACING BETWEEN MILEPOST 44.70 AND MILEPOST 50.66 AND MISCELLANEOUS REPAIRS BETWEEN MILEPOST 49.33 AND MILEPOST 56.68 IN ALLEGHENY COUNTY, PENNSYLVANIA

This project provides for resurfacing of the Turnpike travel lanes and repair and rehabilitation of the roadway shoulders. Resurfacing of the mainline roadway will be accomplished by milling and paving with superpave wearing and binder material. Repair and rehabilitation of the shoulder will be accomplished by reconstruction of the shoulder in selected areas and sealing the shoulder pavement. Work also includes cleaning behind and repair to the existing rock fall fence, reconstruction of bituminous curb, replacement of single face barrier, replacement of inlet tops, removal and replacement of post mounted signs and rehabilitation of a concrete bridge deck and painting on Bridge No WB-461 at Milepost 56.68.

Work items include, but are not limited to:

771	CY	Excavation, Various Classes
150	CY	Clean Behind Existing Rock Fall Fence
---	LS	Rock Slope Scaling
27,395	TON	Superpave Asphalt Mixture Design, HMA, Various Courses
78,707	SY	Shoulder Sealing
110,558	SY	Milling of Bituminous Pavement Surface, Various Depth
5	EACH	Repair Terminal Section, Bridge Connection
1,020	LF	Concrete Median Barrier, Various Heights
2,245	LF	Remove and/or Replace Existing Bituminous Concrete Curb
17,060	LF	Sealing of Existing Bituminous Concrete Curb
1,111	CY	Rock Lining
44,125	GAL	Slab Stabilization
1,000	SF	Post Mounted Signs, Various Types
75	CY	Class AA Cement Concrete
165	CY	High Performance Concrete for Bridge Decks
43,387	LB	Reinforcement Bars, Epoxy Coated
---	LS	Painting Existing Structural Steel

Milepost 44.70 is located approximately 3.03 miles west of the Allegheny Valley Interchange, Exit 48, and Milepost 56.68 is located approximately 0.24 miles east of the Pittsburgh Interchange, Exit 57, in Allegheny County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Direct any questions for this project to Mr. Matthew Burd, P.E., telephone (717) 939-9551, Extension 5760, fax (717) 986-8707, or electronic mail: mburd@paturnpike.com.

PENNSYLVANIA TURNPIKE COMMISSION

J. William Lincoln
Secretary-Treasurer

Harrisburg, Pennsylvania
December, 2009