

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online and diskette bids will be received until 11:30 AM, Local Time, on February 2, 2011. Diskette bids will be received by the Contract Management Services Manager for the Pennsylvania Turnpike Commission, at the Administration Building, Ground Address: 700 South Eisenhower Boulevard, Middletown, Pennsylvania 17057 (Mailing Address: P.O. Box 67676, Harrisburg, Pennsylvania 17106-7676). Bids will be publicly opened for the following Contract:

CONTRACT NO. T-099.00R001-3-02 – BITUMINOUS OVERLAY BETWEEN MILEPOST 99.08 AND MILEPOST 101.70 AND SHOULDER AND MEDIAN REHABILITATION BETWEEN MILEPOST 93.98 AND MILEPOST 99.20 IN WESTMORELAND AND SOMERSET COUNTIES, PENNSYLVANIA

This Contract provides for resurfacing of the Turnpike roadway and shoulders between Milepost 99.08 and Milepost 101.70. Work will be accomplished by milling the bituminous pavement to the existing concrete pavement and paving with Superpave binder and wearing courses and installing Snowplowable Raised Pavement Markers and Sonic Nap Alert Patterns. Work also includes concrete pavement patching, roadway slab stabilization, rehabilitation and sealing of the Turnpike shoulders and median between Milepost 93.98 and Milepost 99.20, shoulder inlet repairs, shoulder repairs and guide rail replacement. Also included is the maintenance and protection of Turnpike traffic.

Work items include, but are not limited to:

| | | |
|---------|------|--|
| 588 | CY | Class 1 & 1A Excavation |
| 181,519 | SY | Mill Existing Bituminous Surface Materials, Various Depths |
| 40,010 | TONS | Bituminous Concrete Materials |
| 16,002 | GAL | Sealing with GSB-88 Sealer – 2:1 Dilution |
| 637.5 | LF | Type 2-S Guide Rail |
| 3 | EACH | Inlet Repairs |
| 1,058 | EACH | Snowplowable Raised Pavement Markers |
| 68,461 | EACH | Sonic Nap Alert Pattern |

Milepost 93.98 is located approximately 3.3 miles east of the Donegal Interchange, Exit 91, and Milepost 101.70 is located approximately 8.2 miles west of the Somerset Interchange, Exit 110, in Westmoreland and Somerset Counties, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Direct any questions for this project to James R, Feguer, telephone (717) 939-9551, Extension 5772, fax (717) 986-8707, or electronic mail: jfeguer@paturndpike.com.

PENNSYLVANIA TURNPIKE COMMISSION

J. William Lincoln
Secretary-Treasurer

Harrisburg, Pennsylvania
December, 2010