

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online and compact disk bids will be received until 11:00 AM Local Time, on June 5, 2013. Compact disk bids will be received by the Contract Management Services Manager for the Pennsylvania Turnpike Commission, at the Administration Building, Ground Address: 700 South Eisenhower Boulevard, Middletown, Pennsylvania 17057 (Mailing Address: P.O. Box 67676, Harrisburg, Pennsylvania 17106-7676). Bids will be publicly opened for the following Contract:

CONTRACT NO. T-013.21S001-3-02 - REPLACEMENT OF BRIDGE NO. WB-207 AT MILEPOST 12.63 AND BRIDGE NO. WB-208 AT MILEPOST 12.67 IN BEAVER COUNTY, PENNSYLVANIA

This project provides for the furnishing of all labor, material, equipment, and work necessary to replace a single span thru-truss railroad structure with a 2-span thru-girder structure, to replace a single span thru-girder railroad structure with a 2-span thru-girder structure, to construct a post and plank retaining wall, and to construct two railroad roadbeds and associated drainage features. Also included is the Maintenance and Protection of Traffic.

Work items include, but are not limited to:

5,888	CY	Excavation
982	TON	Superpave Asphalt Mixture Design, Various Types
438	TON	Subbase (No. 2A)
1,751	SY	Milling of Bituminous Pavement Surface, Various Depths
127	LF	Thermoplastic Pipe, Various Types
318	LF	Reinforced Concrete Pipe, Various Types
2,834	LF	Concrete Glare Screen
2,533	LF	Temporary Concrete Barrier
62,668	CY	Class 3 Excavation, Rock
5,195	CY	Cement Concrete, Various Classes
9,431	CY	Selected Borrow Excavation, Structure Backfill
495,645	LB	Reinforcement Bars, Epoxy Coated
297	LF	36" Diameter Drilled Caisson, Rock Socket
66	LF	36" Diameter Drilled Caisson, Shaft Section
2,506,300	LB	Fabricated Structural Steel
148,065	LB	Fabricated Structural Steel, Galvanized
22	EACH	High Load Disc Bearings, Various Types
2,795	SF	Precast Concrete Panels

The project is located approximately 0.1 mile west of the Beaver Valley Interchange, Exit 13, in Beaver County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Prior to any site inspections within Turnpike right-of-way, prospective bidders are required to telephone the Duty Officer at the Operations Center at 866-332-5889 or *11 by cellular and ask for the Duty Officer. Provide the following information:

- location of site inspection (mileposts)
- type of vehicle(s) and license number(s)
- brief scope of work
- general timeframe
- telephone number for contact

Direct any questions for this project to Brad Updegrave, PE, telephone (717) 920-7365, fax (717) 986-9645, or electronic mail to bupdegra@paturndpike.com.

PENNSYLVANIA TURNPIKE COMMISSION

Pasquale T. Deon, Sr.
Secretary-Treasurer

Harrisburg, Pennsylvania
April 2013