

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online and compact disk bids will be received until 11:00 AM, Local Time, on July 2, 2014. Compact disk bids will be received by the Contract Management Services Manager for the Pennsylvania Turnpike Commission, at the Administration Building, Ground Address: 700 South Eisenhower Boulevard, Middletown, Pennsylvania 17057 (Mailing Address: P.O. Box 67676, Harrisburg, Pennsylvania 17106-7676). Bids will be publicly opened for the following Contract:

CONTRACT NO. T-220.00T001-3-04 – ROADWAY AND BRIDGE RECONSTRUCTION MP 220.30 TO MP 226.72 IN CUMBERLAND COUNTY, PENNSYLVANIA

This project provides for the furnishing of all labor, material, equipment and work necessary to do staged construction for full depth roadway reconstruction and widening of the Turnpike from 2 lanes in each direction to 3 lanes in each direction and the replacement of 6 mainline bridges and 1 overhead bridge. The project includes the removal of 3 reinforced concrete rigid frame bridges, 2 single span reinforced concrete T-beam bridges, one 2-span reinforced concrete T-beam bridge and 1 single span steel I-girder bridge; the elimination of 1 pedestrian underpass and 1 single span reinforced concrete T-beam mainline bridge; and construction of 6 single span prestressed concrete spread box beam bridges, 2 single span composite steel multi-girder bridges, 2 precast concrete arch bridges, 6 sound barrier walls and 2 retaining walls. Work also includes maintenance and protection of Turnpike and local roadway traffic.

Work items include, but are not limited to:

580,536	CY	Class 1 Excavation
88,755	CY	Selected Borrow Excavation Rock, Type A, Modified and Type B, Modified
162,008	TON	Subbase No. 2A
540,866	TON	Bituminous Concrete Base Course, Superpave Wearing and Superpave Binder
38,227	LF	Drainage Pipes, Various Sizes
272	EA	Inlets and Manholes, Various Types
279,103	LF	6" Pavement Base Drains
33,228	LF	4 – 1 ½" High Density Polyethylene Conduit
18,800	LF	Guide Rail
33,384	LF	Concrete Glare Screen
61,791	LF	Right-of-Way Fence, Type 2
60,078	CY	Class 3 Excavation
9,152	CY	Class A, AA, and AAAP Cement Concrete
5,112	LF	Prestressed Concrete Spread Box Beams
1,446	LF	Steel Beam Bearing Piles, HP 10x57
643,247	LB	Fabricated Structural Steel
715,905	LB	Fabricated Structural Steel, Galvanized
1,493	CY	Selected Borrow Excavation, Structure Backfill
38,406	CY	Flowable Backfill
28,912	LB	Reinforcement Bars
1,052,853	LB	Reinforcement Bars, Epoxy Coated
734	EA	Steel Posts (Sound Barrier Walls)
133,962	SF	Precast Reinforced Concrete Panels (Sound Barrier Walls and Retaining Walls)
13,138	LF	Drilled Caissons, Various Types and Sizes

Milepost 220.30 is located approximately 6 miles west of the Carlisle Interchange, Exit 226, and Milepost 226.72 is located approximately at the Carlisle Interchange, Exit 226, in Cumberland County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by a registered business partner.