

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online and compact disk bids will be received until 11:00 AM, Local Time, on January 28, 2015. Compact disk bids will be received by the Contract Management Services Manager for the Pennsylvania Turnpike Commission, at the Administration Building, Ground Address: 700 South Eisenhower Boulevard, Middletown, Pennsylvania 17057 (Mailing Address: P.O. Box 67676, Harrisburg, Pennsylvania 17106-7676). Bids will be publicly opened for the following Contract:

CONTRACT NO. T-242.00T002-3-03 – ROADWAY AND BRIDGE RECONSTRUCTION
MILEPOST 241.98 TO MILEPOST 245.33 IN YORK COUNTY, PENNSYLVANIA

This project provides for the furnishing of all labor, material, equipment and work necessary to perform staged construction for full depth roadway reconstruction and widening of the turnpike from 2 lanes in each direction to 3 lanes in each direction, reconstruction of a portion of the existing interchange ramps, removal of a single span concrete T-beam bridge and construction of a single span steel beam bridge, 2 culvert extensions, 4 retaining walls, and the extension of existing sound barrier wall. Also, included is the replacement of roadway drainage facilities, replacement of guide rail and concrete median barrier, erosion and sediment pollution controls, maintenance and protection of traffic during construction and signing and pavement markings.

Work items include, but are not limited to:

392,340	CY	Class 1 Excavation
1,408	LF	Steel Beam Bearing Pile HP 12x74
5,620	CY	Selected Borrow Excavation Rock, Type A
166,613	CY	Selected Borrow Excavation Rock, Type B
1,226,962	SY	Bituminous Material, various types
103,455	LF	6" Pavement Base Drain
21,212	LF	Concrete Glare Screen
34,041	CY	Class 3 Excavation
13,715	CY	No. 57 Coarse Aggregate
321	CY	AAAP Concrete
1,099	CY	Class AA Concrete
2,696	CY	Class A Concrete
150,067	SF	Precast Concrete Panels
26,532	LF	Drainage Pipe, various sizes and types
17,125	LF	Guide Rail
448,846	LB	Reinforcement Bars (Plain and Epoxy)
372	EACH	Inlet, various types
36,510	LF	Right-of-Way Fence, various types
259,649	SY	Subbase
4,687,567	LB	Fabricated Structural Steel

Milepost 241.98 is located at the Harrisburg West Interchange, Exit 242, and Milepost 245.33 is located 1.4 miles west of the Harrisburg East Interchange, Exit 247, in York County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.