

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online and compact disk bids will be received until 11:00 AM, Local Time, on November 9, 2016. Compact disk bids will be received by the Contract Management Services Manager for the Pennsylvania Turnpike Commission, at the Administration Building, Ground Address: 700 South Eisenhower Boulevard, Middletown, Pennsylvania 17057 (Mailing Address: P.O. Box 67676, Harrisburg, Pennsylvania 17106-7676). Bids will be publicly opened for the following Contract:

CONTRACT NO. S-006.00X002-3-06 - CONSTRUCTION OF SOUTHERN BELTWAY SR 0576, SECTION 55A1 BETWEEN MP S-5.08 AND MP S-8.81 IN WASHINGTON COUNTY, PENNSYLVANIA

This project provides for the furnishing of all labor, materials, equipment and all work necessary to perform staged construction of 3.7 miles of 4 lane concrete roadway including construction of two span continuous composite P/S concrete PA bulb-tee beam bridge, dual three span composite P/S concrete PA bulb-tee beam bridges, dual single span composite P/S concrete AASHTO I-beam bridges, and dual single span composite steel multi-girder bridges, one full and one half interchanges, relocation of SR 4010 (Beech Hollow Road) and reconstruction of SR 4009 (Candor Road), SR 0980 and SR 4011 (Quicksilver Road).

Major work items include the following:

5,246,011	CY	Class 1 and Class 1B Excavation
60,377	CY	Class 2 Excavation
35,252	CY	Class 3 Excavation
94,445	SY	Superpave Wearing Course, Various Types and Depths
79,100	SY	Superpave Binder Course, Various Types and Depths
55,762	SY	Superpave Base Course, Various Types and Depths
193,220	SY	Asphalt or Cement Treated Permeable Base Course
299,924	SY	Subbase No 2A, Various Depths
18,630	SY	Plain Cement Concrete Paving Various Depths
188,990	SY	Long-Life Concrete Pavement, 12" Depth
21,036	CY	Selected Borrow Excavation Structure Backfill
47,504	LF	Drainage Pipe, Various Types and Sizes
74,094	LF	Pavement Base Drain
28,788	LF	Type 2-S Guide Rail
7,751	CY	Class A Cement Concrete
1,038	CY	Class AA Cement Concrete
2,985	CY	Class AAAP Cement Concrete
1,111,964	LBS	Fabricated Structural Steel
8,110	LF	Prestressed Concrete Beams
1,333,522	LBS	Reinforcement Bars, Epoxy Coated
356,201	LBS	Reinforcement Bars
19,636	LF	Steel Beam Bearing Piles, 12 x 74

Milepost S-5.08 is located approximately 0.4 miles north of SR 0022. Milepost S-8.81 is located approximately 0.5 miles south of SR 4010 (Quicksilver Road), in Washington County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.