

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 AM, Local Time, on August 23, 2017 and will be publicly opened for the following Contract:

CONTRACT NO. T-057.00T001-3-06 – REPLACEMENT OF BRIDGE NO. WB-500 (S-35947) AND REPLACEMENT OF BRIDGE NO. WB-500B (S-35948) AT MILEPOST 59.58 IN WESTMORELAND COUNTY

This project provides for the replacement of a single span through steel plate girder bridge with a two span concrete multi-girder bridge, the replacement of a single span steel bridge with a single span concrete multi-girder bridge, the replacement of a 3’-3” X 14’-6” plate arch with a 6’-0” X 14’-0” precast box culvert, the reconstruction of SR-4033, the reconstruction of a portion of Lyons Run Road, the construction of two new access ramps and the construction of the mainline median and shoulder at the proposed bridge location.

Work items include, but are not limited to:

139,344	CY	Excavation, Various Classes
1,969	TON	Superpave Asphalt Mixture, Wearing Course, Various Depths
3,608	TON	Superpave Asphalt Mixture, Binder Course, Various Depths
2,479	TON	Superpave Asphalt Mixture, Base Course, Various Depths
4,529	TON	Subbase, 6” Depth (No. 2A)
6,009	LF	Pavement Base Drain, Various Sizes
2,806	LF	Drainage Pipe, Various Sizes and Types
38	EACH	Inlets, Various Sizes and Types
2,732	LF	Guide Rail, Various Types
2,821	LF	Right-of-Way Fence
3,132	CY	Topsoil
9,396	SY	Erosion Control Mulch Blanket
22,387	SY	Mulching, Bonded Fiber Matrix
5,901	LF	Compost Filter Sock, Various Sizes
1,773	CY	Cement Concrete, Various Classes
8,484	CY	Selected Borrow Excavation, Structure Backfill
1,308	CY	Selected Borrow Excavation Rock, Type R-3, R-4, and R-8
7,258	SY	Architectural Surface Treatment
1,460	LF	Prestressed Concrete PA Bulb-Tee Beam, Various Sizes
251,980	LB	Reinforcement Bars, Plain and Epoxy Coated
17,432	LF	Pavement Markings, Various Sizes and Types

Milepost 59.58 is located approximately 2.9 miles east of the Pittsburgh Interchange, Exit 57, and approximately 7.4 miles west of the Irwin Interchange, Exit 67, in Westmoreland County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.