

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 AM, Local Time, on November 14, 2017 and will be publicly opened for the following Contract:

CONTRACT NO. T-019.00R002-3-02 - BITUMINOUS RESURFACING AND SUBSTRUCTURE REHABILITATION BETWEEN MILEPOST 19.41 AND MILEPOST 31.25 IN BEAVER, BUTLER AND ALLEGHENY COUNTIES

This contract provides for resurfacing of the Turnpike roadway. Work will be accomplished by milling and paving the Turnpike roadway with superpave wearing course, and replacing Sonic Nap Alert Patterns. Work will also include shoulder reconstruction, guide rail end treatment update, repairing and replacement of inlets and wide area elimination. This contract also provides for bridge repairs which includes Class AA concrete repairs and type 2 latex modified concrete deck patching. Additional work includes Zelienople service plaza concrete pavement patching and access road full depth reconstruction, access ramp milling and paving at Mileposts 21.4 and 21.9, EB and milling and paving of the Warrendale Toll Plaza and access roads.

Work items include but are not limited to:

13,432	CY	Excavation, Class 1, 1A, 1B, 2 Excavation
523,895	SY	Milling of Existing Bituminous Pavement, Various Depths
10,740	TONS	Superpave Wearing Course, PG 64-22, 9.5 MM Mix, SRL-E
26,225	TONS	Superpave Wearing Course, PG 76-22, 12.5 MM Mix, SRL-E
15,725	TONS	Superpave Wearing Course, PG 76-22, 9.5 MM Mix, SRL-E
9,211	TONS	Superpave Binder Course, PG 64-22, 19 MM Mix
150	EACH	Inlet Repairs
26	EACH	Inlet Replacements
4,896	LF	Type 2-S Guide Rail
1,320	LF	Concrete Median Barrier, 48"
120,000	EACH	Sonic Nap Alert Pattern (SNAP)
3,578	LF	Rock Armor
5,529	CY	Rock Armor, Modified
22,193	LF	Compost Filter Sock, 18"
280,700	LF	Highly ReflectORIZED Polyurea Pavement Markings, 6"

Milepost 19.41 is located approximately 6.4 miles east of the Beaver Valley Interchange, Exit 13 and Milepost 31.25, is located approximately 2.8 miles east of Cranberry Interchange, Exit 28 in Beaver, Butler and Allegheny Counties, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.