

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 A.M., Local Time, on November 7, 2018 and will be publicly opened for the following Contract:

CONTRACT NO. T-174.00R002-3-02 - SHOULDER AND SLOPE REHABILITATION, RAMP RESURFACING AND BRIDGE PAINTING BETWEEN MILEPOST 173.23 AND MILEPOST 179.95 IN FULTON COUNTY

This project provides for shoulder resurfacing and rehabilitation, slope rehabilitation, and resurfacing of the existing bituminous travel lanes for the Ft. Littleton Interchange including resurfacing and patching of the Interchange shoulders. Work will also include parking area repairs, guide rail repairs, inlet and drainage pipe replacement and repair, and installation of Permanent Highly ReflectORIZED Polyurea Pavement Markings and Standard Pavement Markings at the Ft. Littleton Interchange and Ramps. This project also provides for the complete removal of existing paint system and the application of a new paint system and the application of an aesthetic concrete coating to concrete surfaces to the overhead bridges at Milepost 179.08 and Milepost 179.53 Maintenance and Protection of Traffic is also included.

Work items include, but are not limited to:

| | | |
|--------|------|--|
| 5,362 | CY | Excavation, Class 1, Class 1A, Class 1B and Class 2 Excavation |
| 69,483 | SY | Milling of Existing Bituminous Pavement, Various Depths |
| 4,579 | TON | Superpave Asphalt Mixture Design, HMA Wearing Course, PG 64-22 |
| 2,829 | TON | Superpave Asphalt Mixture Design, HMA Wearing Course, PG 76-22 |
| 2,784 | TON | Superpave Asphalt Mixture Design, HMA Binder Course, PG 64-22 |
| 8,716 | LF | Bituminous Concrete Curb |
| 83 | EACH | Inlets, Various Conditions |
| 852 | LF | Pipe, Various Types and Diameters |
| 18,775 | LF | Remove Existing Guiderail |
| 18,652 | LF | Install Guiderail |
| 31,660 | LF | Standard Pavement Markings |
| 8,050 | LF | Permanent Highly ReflectORIZED Polyurea Pavement Markings |
| 33,000 | SF | Painting Existing Structural Steel |
| 400 | SF | Class AA Cement Concrete Repairs |
| 10,000 | SF | Aesthetic Concrete Coatings |

Milepost 173.23 is located approximately 12.5 miles East of the Breezewood Interchange, Exit 161, and Milepost 179.95 is located approximately 8.5 miles West of the Willow Hill Interchange, Exit 189, in Fulton County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.