

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 AM, Local Time, on December 19, 2018. Bids will be publicly opened for the following Contract:

CONTRACT NO. S-006.00X002-3-10 FOR CONSTRUCTION OF SOUTHERN BELTWAY, SR 0576, SECTION 55C2-1, BETWEEN MILEPOST S-17.04 AND MILEPOST S-19.23 IN WASHINGTON AND ALLEGHENY COUNTIES, PENNSYLVANIA

This project provides for the furnishing of all labor, materials, equipment and work necessary to perform staged construction of a full interchange between SR 0576 and SR 0079 and a half interchange with SR 1009, Morganza Road. It includes demolition of two (2) – two span spread box beam bridges over SR 0079, construction of a two span curved steel plate girder bridge over SR 0576, two (2) - two span composite steel plate girder bridge over SR 0576, widening of an existing composite steel plate girder bridge over SR 1010 Cecil Henderson Road, widening of a composite P/S spread box beam bridge over SR 1032 Southpointe Boulevard, construction of a P/S PA Bulb Tee bridge over Ramp 79N-576W, drainage culvert, retaining wall along SR 0079, a decorative wall at the National Cemetery of the Alleghenies, intersection improvements to SR 0050, drainage, highway lighting, traffic signals and ITS.

Major work items include the following:

6,590,028	CY	Excavation, Classes 1, 1B, 2 & 4
293,829	CY	Select Borrow Excavation, Various Types
214,117	SY	Superpave Asphalt Materials (Base, Binder & Wearing Courses)
354,670	SY	Asphalt/Cement Treated Base Course
472,352	SY	Subbase No. 2A, Various Depths
167,037	CY	Plain Cement Conc. Paving Various Depths
190,106	SY	Long Life Concrete Pavement, 12” Depth
46,668	LF	Drainage Pipe, Various Types and Sizes
150,251	LF	Pavement Base Drain
480	EACH	Inlets, Endwalls, Manholes Various Types
23,558	LF	Guiderail, Type 31 Various Types
25,610	LF	Concrete Barrier Various Types
116,239	CY	Class 3 Excavation
12,350	CY	Class A Cement Concrete
1,878	CY	Class AA Cement Concrete
4,646	CY	Class AAAP Cement Concrete
1,025	LF	Prestressed Concrete Beams
7,089,279	LBS	Fabricated Structural Steel
2,937,854	LBS	Reinforcement Bars, Epoxy Coated
9,168	LF	Steel Bearing Piles
31,196	LF	Temporary Concrete Barrier
4,795	LF	Temporary Concrete Barrier, Structure Mounted

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3)

low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.