

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 AM, Local Time on March 27, 2019 and will be publicly opened for the following Contract:

CONTRACT NO. T-085.00R003-3-02 - BITUMINOUS RESURFACING BETWEEN MILEPOST 84.93 AND MILEPOST 94.13 AND SHOULDER AND SLOPE WORK BETWEEN MILEPOST 94.13 AND MILEPOST 99.00 IN WESTMORELAND COUNTY

This contract provides for milling and paving the Turnpike roadway with stone matrix wearing course. Work will also include shoulder reconstruction, guide rail replacement, drainage channel reconstruction, and repairing and replacement of inlets including replacing type A inlets with new inlets, drain pipes and end walls. This contract also provides for bridge repairs which includes Class AA concrete repairs and concrete deck repair and bridge expansion joint system. Additional work includes Donegal maintenance facility mill and overlay, installation of geosynthetic reinforced slopes and rock armor along the eastbound shoulder slope and milling and paving of the Donegal Interchange ramps at MP 90.6.

Work items include but are not limited to:

41,011	CY	Excavation, Class 1, 1A, 2 Excavation.
584,612	SY	Milling of Existing Bituminous Pavement, Various Depths
8,078	TONS	Superpave Wearing Course, PG 64-22, 12.5 mm Mix, SRL-E
37,970	TONS	Stone Matrix Asphalt Wearing Course, PG 76-22, 12.5 mm Mix, SRL-E
1,050	TONS	Superpave Wearing Course, PG 76-22, 12.5 mm Mix, SRL-E
7,886	TONS	Superpave Base Course, PG 64-22, 25 mm Mix
11,182	CY	No.57 Coarse Aggregate
331,764	SY	Micro Milling, ½” Depth
256	EACH	Inlet Repairs
25	EACH	Inlet Replacements
2,919.5	LF	Type 2- S Guide Rail
12,175	LF	Type 31-S Guide Rail
487	LF	Single Face Concrete Barrier, 52”
186,449	EACH	Sonic Nap Alert Pattern (SNAP)
3,075	CY	Rock Armor, Modified
27,252	LF	Compost Filter Sock, 18”
6,469	CY	Corrosion Resistant Gabions, Type B
19,062	LF	Temporary Concrete Barrier and Temporary Impact Attenuator
10,248	LF	Temporary Concrete Barrier
244,499	LF	Permanent Preformed Patterned Reflective Pavement Marking, 6”
654,322	LF	4” Standard Pavement Markings

Milepost 84.93 is located approximately 5.6 miles west of the Donegal Interchange, Exit 91, and Milepost 99.00 is located approximately 8.4 miles east of the Donegal Interchange in Westmoreland County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.