

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 AM, Local Time, on June 5, 2019, and will be publicly opened for the following Contract:

CONTRACT NO. T-186.20S004-3-02 - REHABILITATION OF THE TUSCARORA TUNNEL AND BRIDGES B-561 AND B-562 BETWEEN MILEPOST 185.89 AND MILEPOST 187.49 IN HUNTINGDON AND FRANKLIN COUNTIES, PENNSYLVANIA

This project provides for the rehabilitation of Tuscarora Tunnel and portal buildings including electrical and mechanical upgrades; full-depth replacement of approach roadways; rehabilitation of dual mainline 2-span continuous deck I-beam bridges at MP 185.9 including deck repairs, installation of membrane waterproofing and bituminous overlay, asphaltic plug expansion joints, painting, new concrete end diaphragms, and installation of a wingwall buttress system. Work in the eastbound tunnel includes removal of the existing tunnel ceiling, installation of a PVC membrane waterproofing system and shotcrete liner, replacement of walkway, roadway barriers and drainage. Work in the westbound tunnel includes installation of vertical drains in the existing liner walls and replacement of drainage system. Both tunnels receive new lighting and electronic systems.

Work items include, but are not limited to:

16,364	SY	Ceiling Demolition (Types 1 and 2)
287,590	SF	Waterproofing System
7,030	CY	Shotcrete Lining
86	EA	Type M Inlets
826	SY	Plain Cement Concrete Base Course, 10" Depth, Accelerated
2,642	CY	Class AA Cement Concrete (Barriers)
1,229	LF	Concrete Median Barrier, 34"
42,177	SY	Milling of Bituminous Pavement, Various Depths
6,569	TONS	Superpave Base Course
2,413	TONS	Superpave Binder Course
9,387	TONS	Superpave Wearing Course
1,804	EA	LED Tunnel Luminaires
10	EA	Dynamic Message Signs
42	EA	Lane Control Signs (Single sided and Double sided)
42	EA	CCTV (Standard Color and Thermal)
12	EA	Tunnel Ventilation Fans
180,061	LF	Exposed Conduit in Tunnel
24	EA	Motor Starters
4	EA	Diesel Emergency Generators
1,220	SY	Membrane Waterproofing System Installed on Bridge Deck
3,295	SF	Concrete Bridge Deck Repair, Types 2 and 3
180	LF	Asphaltic Plug Expansion Joint

Milepost 185.89 to Milepost 187.39 is located approximately 5 miles east of the Fort Littleton Interchange, Exit 180, and approximately 0.5 miles west of the Willow Hill Interchange, Exit 189 in Huntingdon and Franklin Counties, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An informal site visit is scheduled for 10:00 AM, Local Time, on Tuesday, May 7, 2019. Interested parties will meet at the Pennsylvania Turnpike Commission's Burnt Cabins Maintenance facility located at MP 186.1 Eastbound. The Commission will provide, weather permitting, cross-over traffic control for access to the eastbound tunnel between the hours of 10:00 AM and 1:00 PM local time for inspection inside the tunnels. This will be the only site visit for this project. This is not a prebid meeting and the Commission will not entertain or answer any questions.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.