

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 AM Local Time, on October 21, 2020 and will be publicly opened for the following Contract:

CONTRACT NO. T-099.00T002-3-05 ROADWAY RECONSTRUCTION FROM MILEPOST 101.69 TO MILEPOST 109.10 IN SOMERSET COUNTY

This project provides for the furnishing of all labor, material, equipment and work necessary to perform staged construction for full-depth reconstruction and widening of the Pennsylvania Turnpike from two lanes in each direction to three lanes in each direction. The project includes the construction of two box culverts, one box culvert extension, four arch culvert extensions, three retaining walls, one soil nail wall, three sign structures, and one DMS sign. The Type I DMS will be supplied by the Commission. The contract also provides for drainage modifications and maintenance and protection of traffic. Work items include, but are not limited to the following:

140,985	CY	Classes 1A and 2 Excavation
2,346,819	CY	Class 1 Excavation
182,736	CY	Class 1 Excavation (Rock)
13,155	CY	Rock Armor, Modified
16,159	CY	No. 57 Coarse Aggregate
272,360	SY	Topsoil
338,629	SY	Stone Matrix Asphalt Mixture, Wearing Course, 2" Depth
1,715,030	SY	Superpave Asphalt Materials
563,208	SY	Subbase (No. 2A), 6" Depth
338,629	SY	Asphalt Treated Permeable Base Course, 4" Depth
218,616	LF	Pavement Base Drain, Various (Excluding Stage Drain)
70,352	LF	6" Pavement Base Drain, Stage Drain
63,061	LF	Drainage Pipe, Various Sizes and Types
549	EACH	Inlets/Manholes/End Sections/Endwalls
378,293	SY	Rolled Erosion Control Products, Various Types
134,52	LF	Temporary Concrete Barrier
19,740	LF	Temporary Concrete Glare Screen
39,828	LF	Concrete Glare Screen
41,263	LF	Type 31-S Guide Rail
250,353	LF	Permanent Preformed Patterned Reflective Pavement Markings

Milepost 101.69 is located approximately 8.0 miles west of the Somerset Interchange, Exit 110 and Milepost 109.10 is located approximately 1.0 mile west of the Somerset Interchange, Exit No. 110, in Somerset County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five percent (5%) of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.