

**PENNSYLVANIA TURNPIKE COMMISSION**  
**Harrisburg, Pennsylvania**

**NOTICE TO BIDDERS**

Online bids will be received until 11:00 am, Local Time, on December 22, 2021 and will be publicly opened for the following Contract:

**CONTRACT NO. A-037.50T001-3-02 ROADWAY AND BRIDGE RECONSTRUCTION FROM MILEPOST A-37.39 TO A-43.33 IN MONTGOMERY AND BUCKS COUNTIES**

This project provides for the furnishing of all labor, material, equipment and work necessary to perform staged construction for full-depth reconstruction and widening of the Pennsylvania Turnpike from two (2) lanes in each direction to three (3) lanes in each direction. The project includes the construction of five (5) mainline bridges, two box culvert extensions, one retaining wall, five sign structures, and one DMS sign. The contract also provides for drainage modifications and maintenance and protection of traffic.

Work items include, but are not limited to:

731,736	CY	Excavation, Various Classes
667,842	SY	Superpave Asphalt Mixture, Base Course, Various Depths
254,721	SY	Asphalt Treated Permeable Base Course, 4" Depth
254,721	SY	Rich Bottom Superpave Asphalt Mixture, 4" Depth
337,607	SY	Stone Matrix Asphalt Mixture, Wearing Course, 2" Depth
154,128	SY	Superpave Asphalt Mixture, Wearing Course, 2" Depth
32	TON	Superpave Asphalt Mixture. Leveling Course
413,858	SY	Superpave Asphalt Mixture, Binder Course, Various Depths
415,586	SY	Subbase (No 2A), Various Depths
5,524	TON	Subbase Under Guide Rail
84,940	SY	Milling of Asphalt Pavement Surface
42,292	LF	Drainage Pipes, Various Sizes and Types
231,633	LF	Pavement Base Drain
349	Each	Inlets/Manholes/End Sections/Endwalls
78,062	LF	Guide Rail/Concrete Barrier
64,650	LF	Removal of Guide Rail/Concrete Barrier
110,546	LF	Temporary Concrete Barrier (Includes Structure Mounted)
65,070	LF	Right-of-Way Fence
29,394	CY	Class 3 Excavation, Structures
1,516,128	LB	Reinforcement Bars, Plain, Stainless and Epoxy Coated
2,472	CY	Over-Excavation and Backfilling with Cement and Rock
3,021	CY	Select Borrow Excavation, Structural Backfill
100,802	CY	Selected Borrow Excavation Rock, Type A & B
24,786	CY	Structure Backfill (Flowable)
11,727	LF	Prestressed Concrete Beams, All Sizes
121	LF	Drilled Caissons in Rock and Soil, All Sizes
6,000	SY	Topsoil
1,793	SF	Post Mounted Signs

Milepost A-37.39 is located approximately 6.5 miles south of the Quakertown Interchange, Exit 44 in Montgomery County and Milepost A-43.33 is located within the Quakertown Interchange, Exit 44, in

Bucks County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.