

**PENNSYLVANIA TURNPIKE COMMISSION**  
**Harrisburg, Pennsylvania**

**NOTICE TO BIDDERS**

Online bids will be received until 11:00 am, Local Time, on March 23, 2022 and will be publicly opened for the following Contract:

**CONTRACT NO. T-197.00R001-3-02 – ASPHALT RESURFACING BETWEEN MILEPOST 197.25 AND MILEPOST 201.73 AND TRAFFIC MANAGEMENT SYSTEM FOR BLUE MOUNTAIN AND KITTATINNY TUNNELS BETWEEN MILEPOST 196.57 AND MILEPOST 200.68 IN FRANKLIN AND CUMBERLAND COUNTIES**

This project provides for the asphalt resurfacing of the PA Turnpike mainline from Milepost 197.37 to Milepost 201.73 including correction of the roadway cross slope through variable depth milling and paving. Also included is the installation of DMS signing, concrete median barrier with swift gates and Traffic Management System for the Blue Mountain and Kittatinny Tunnels.

Work items include, but are not limited to:

520	CY	Class 1B Excavation
1,057	TON	Subbase Under Guide Rail
10,932	TON	Superpave Asphalt Mixture Design, Wearing Courses
2,587	TON	Superpave Asphalt Mixture Design, Binder Course PG 64S-22, 19.0mm Mix
19,709	TON	Stone Matrix Asphalt Mixture Design, Wearing Course PG 64E-22, 12.5mm Mix, SRL-E
255,333	SY	Milling of Asphalt Pavement Surface, Various Depths
448	LF	18” Pipe
8,828	LF	Type 31S Guide Rail
10	EA	Type M Inlets
9,602	LF	Concrete Median Barrier
48,190	EA	Sonic Nap Alert Pattern
--	LS	Maintenance and Protection of Traffic
139	EA	Junction Boxes, Various Sizes
45,135	LF	Underground Cable, Copper 1 Conductor Various AWG
26,565	LF	HDPE Communication / Power Conduit
57,200	LF	Exposed Conduit in Tunnel -1”
11,205	LF	Trench Method Modified, Various Types
748	SF	Signs, Various Types
3	EA	DMS Support Structures
3	EA	Traffic Signal Support Mast Arm
41	EA	Install Swift Gate, Various Lengths
--	LS	Swift Gate Materials and Installation
15,280	LF	Fiber Optic Cable, 6mm
4	EA	ITS Closed Circuit Television Camera Subsystem
--	LS	Portal Building Conduit Systems
3	EA	Walk-In (Type 1) DMS Sign and Installation
3	EA	Dynamic Message Sign, Type 2
112	EA	Lane Control Signal – Single Sided

Milepost 196.50 is located approximately 7.5 miles east of the Willow Hill Interchange, Exit 189, in Franklin County and Milepost 201.73 is located approximately 0.75 miles east of the Blue Mountain Interchange, Exit 201, in Cumberland County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.