

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00 AM, Local Time, on November 9, 2022 and will be publicly opened for the following Contract:

CONTRACT NO. EN-00268-03-02 – INSTALLATION OF INTELLIGENT TRANSPORTATION SYSTEMS BETWEEN MILEPOST 306.40 AND MILEPOST 349.00 AND MILEPOST A-27.10 AND MILEPOST A-107.40 IN CHESTER, MONTGOMERY, BUCKS, LEHIGH, CARBON, AND LUZERNE COUNTIES

This project provides for the necessary labor, material, equipment and work to install thirteen (13) completely functional Closed Circuit Television CCTV (Cameras), one (1) Dynamic Message Sign (DMS) Systems, one (1) Roadway Weather Information Station (RWIS), one (1) retrofit of an existing DMS with ladder cage and catwalk, furnishing and installation of foundations, structures, power, and communication conduit and wiring; and install micro-duct fiber optic cable raceway between existing Intelligent Transportation System (ITS) device locations and the nearest Pennsylvania Turnpike Commission’s Fiber Optic Communication Network in-shoulder round lid junction boxes. All DMS, controllers and cabinets; and network communications equipment will be supplied by the Commission. Also included are guide rail installation and Maintenance and Protection of Traffic.

Work items include, but are not limited to:

| | | |
|-------|----|---|
| 1 | EA | Install Full Color Full Matrix DMS Type 1, Centermount Sign and Structure |
| 1 | EA | Retrofit Full Color Full Matrix DMS Type 1, Half-Span with Catwalk |
| 10 | EA | Install 50’ CCTV Poles, Foundations and Cameras |
| 3 | EA | Install 70’ CCTV Poles, Foundations and Cameras |
| 3 | EA | Install Structure Mounted CCTV Camera |
| 1 | EA | Install Roadway Weather Information Station |
| 450 | LF | Guide Rail |
| 7,081 | LF | Micro-Duct Conduit |
| 6,685 | LF | 2” HDPE Conduit |
| 1,380 | LF | 4” HDPE Conduit |
| 158 | LF | 4” Galvanized Steel Exposed Conduit |
| 8,302 | LF | Trench and Backfill, Type I |
| 1,018 | LF | Trench and Backfill, Type III |
| 1,999 | LF | Directional Boring |
| 46 | EA | Junction Boxes, JB-1 |
| 34 | EA | Junction Boxes, JB-2 |
| 1 | EA | Junction Boxes, JB-11 |
| 17 | LF | Drilled Caisson Construction |

The project is located at various locations along the Mainline between Milepost 306.40 and Milepost 349.00 and Northeast Extension between Milepost A-27.10 and Milepost A-107.40 in Chester, Montgomery, Bucks, Lehigh, Carbon, and Luzerne Counties, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.