

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:30 AM, Local Time, on December 21, 2022 and will be publicly opened for the following Contract:

CONTRACT NO. T-031.00R002-3-02 – ASPHALT RESURFACING BETWEEN MILEPOST 31.20 AND 39.64 IN ALLEGHENY COUNTY

This project provides for the milling and asphalt overlay of the Pennsylvania Turnpike Mainline from Milepost 31.20 to Milepost 39.64. The project involves asphalt milling, asphalt wearing course pavement, shoulder reconstruction, rock armor, rock blanket, shoulder backup, single face concrete barrier/transitions, revised stormwater basin access points, guide rail updates, inlet top repairs/replacement, pipe extensions, rock lining, topsoil, seed, mulch, pavement markings, downspout riprap, spall repairs of bridge barriers/substructures/approach slabs, erosion stabilization and wingwall underpinning along the entirety of or localized areas within the project limits. Work also includes Maintenance and Protection of Traffic.

Work items include, but are not limited to:

4,947	CY	Excavation, Various Types
37,791	TON	Stone Matrix Asphalt Mixture Design, Wearing Course
13,068	TON	Superpave Asphalt Mixture Design, Various Courses
458,422	SY	Milling of Asphalt Pavement, 2” Depth
492	TON	Subbase (No. 2A)
6,807	CY	Rock Armor, Modified
4,958	CY	Rock Blanket
3,747	CY	Rock Blanket, Modified
8,482	SY	Shoulder Backup
118	EA	Type M Inlet, Condition BC
31	LF	Reinforced Concrete Pipe, Various Sizes and Types
2	EA	Type D-W Endwall
427	SY	Rock Lining, Class R-4
336	LF	Single Face Concrete Barrier, 52”
4	EA	End Transition, Single Face Concrete Barrier, 41”
7	EA	Transition Section, Single Face Concrete Barrier, 52” to 34”
1,629	LF	Asphalt Concrete Curb
433	LF	Replace Existing Asphalt Concrete Curb
7,942	LF	Remove Existing Guide Rail
5,418	LF	Type 31-S Guide Rail
4	EA	VATET Energy Absorbing Terminal
26	EA	Type 31-Strong Post Anchor Terminal
146,394	EA	Sonic Nap Alert Pattern (S.N.A.P.)
238,448	LF	Permanent Preformed Patterned Reflective Pavement Marking
1	LS	Maintenance and Protection of Traffic
398	SF	Class AA Cement Concrete Repairs
1	LS	WB-240A Underpin Wingwall

This project is located on the Mainline of the Pennsylvania Turnpike between Milepost 31.20, located

approximately 2.7 miles east of the Cranberry Interchange, Exit 28, and Milepost 39.64, located approximately 0.5 miles east of the Butler Valley Interchange, Exit 39 in Allegheny County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.