

PENNSYLVANIA TURNPIKE COMMISSION
Harrisburg, Pennsylvania

NOTICE TO BIDDERS

Online bids will be received until 11:00AM, Local Time, on April 10, 2024 and will be publicly opened for the following Contract:

CONTRACT NO. T-215.00R002-3-02 – ASPHALT RESURFACING BETWEEN MILEPOST 215.17 AND MILEPOST 220.30 IN CUMBERLAND COUNTY

This project provides for the resurfacing of the Turnpike travel lanes. Work will be accomplished by milling, paving 3” of Superpave Binder course and 2” of a Superpave wearing course, replacing Sonic Nap Alert Patterns, and applying Permanent Preformed Patterned Reflective Pavement Markings. Maintenance and protection of Turnpike Traffic is also included.

Work items include, but are not limited to:

215,090	SY	Micro Milling, ½” Depth
238,988	SY	Milling of Asphalt Pavement Surface, 5” Depth
41,584	TON	Superpave Asphalt Mixture Design, Binder Course, PG 64E-22, 10 to <30 Million ESALS, 19 MM Mix
26,290	TON	Superpave Asphalt Mixture Design, Wearing Course, PG 64E-22, 10 to <30 Million 12.5mm Mix, SRL-E
104,356	EA	Sonic Nap Alert Pattern (S.N.A.P)
92,090	LF	6” White Permanent Preformed Patterned Reflective Pavement Marking
54,009	LF	6” Yellow Permanent Preformed Patterned Reflective Pavement Marking
1,651	LF	8” White Permanent Preformed Patterned Reflective Pavement Marking
240,680	LF	4” White Standard Pavement Markings, Paint & Beads
162,026	LF	4” Yellow Standard Pavement Markings, Paint & Beads
80,227	LF	4” White Highly ReflectORIZED Temporary Polyurea Pavement Markings
54,009	LF	4” Yellow Highly ReflectORIZED Temporary Polyurea Pavement Markings
116	LF	24” Standard Pavement Markings, Pant & Beads, White
375	EA	Barrier Mounted Delineator, Top-Mount Type P, (Y/Y)
750	EA	Barrier Mounted Delineator, Side-Mount Type O, (Y/B)
531	LF	Pavement Marking Removal

Milepost 215.17 is located approximately 13.87 miles east of the Blue Mountain Interchange, Exit 201, and Milepost 220.30 is located approximately 6 miles west of the Carlisle Interchange, Exit 226, in Cumberland County, Pennsylvania.

The proposal and plans are published electronically in EBS and are available to registered business partners for downloading and printing.

An electronic bid bond, from an approved vendor, with corporate surety, in the amount of five (5%) percent of the bid must be submitted with the proposal as bid security. The bid security of the three (3) low bidders will be retained until the execution of the contract. (The normal time for execution of the contract is approximately four [4] weeks.)

A Prequalification Certification and Applicable Capacity Rating assigned by the Prequalification Office of the Pennsylvania Department of Transportation is a necessary prerequisite for bidding on this project.

The opening and listing of bids not meeting all the terms and conditions of the bid advertisement or bid procedures does not act as a waiver or modification of any requirements contained in the bid advertisement or bid procedure.

The Provisions of the Pennsylvania Prevailing Wage Act of August 15, 1961, P.L. 987, as amended, together with the rates and regulations promulgated by the Secretary of Labor and Industry applicable thereto, shall apply to this contract.

Any questions for this project must be submitted electronically in EBS by registered business partners.